

BILL OF QUANTITIES
(Building Construction/Rehabilitation Project)

PROJECT TITLE : PROPOSED CONSTRUCTION OF CANOPY AT 3RD FLOOR MULTI PURPOSE HALL AT SCOUT TUAZON CORNER SCOUT GANDIA

LOCATION : BARANGAY LAGING HANDA, DISTRICT 4, QUEZON CITY

PROJECT NO. : 20 - 00132

DURATION : Sixty (60) Calendar Days

SCOPE OF WORK :

1. General Requirements including temporary facilities and utilities, billboard, construction safety and health, scaffolding and clearing, hauling and disposal of construction materials and debris.
2. Remove portion of existing concrete hollow blocks for the installation of tubular bar column.
3. Installation of canopy framing with polycarbonate roofing.
4. All necessary testing of materials and commissioning works must be performed as per standard procedures.

ITEM NO.	WORK DESCRIPTION AND SCOPE OF WORKS	QTY.	UNIT	UNIT COST	TOTAL COST
I.	GENERAL REQUIREMENTS				
	Billboard	1	pc	P	P
	Clearing, Hauling and Disposal of Construction Materials and Debris	1	t.l.		
	Construction Safety and Health	1	unit		
	Scaffolding (Rental)	368	sq.m.		
	Temporary Electrical and Water Facilities	60	days		
	Temporary Enclosure Around the Construction Area (H=2.4m)	52	l.m.		
				Direct Cost I	P
II.	SITE WORKS				
	Removal of Existing CHB Wall	11	sq.m.	P	P
				Direct Cost II	P
III.	CIVIL / STRUCTURAL WORKS				
A.	Concrete Works				
	Concrete Topping	2	sq.m.	P	P
B.	Masonry Works				
	Plastering Works for Existing CHB Wall	16	sq.m.		
C.	Metal Fabrication				
	25mm x 25mm Tubular Bar	11,625	kg		
	50mm x 100mm Tubular Bar	1,069	kg		
	50mm x 13mm Flat Bar	359	kg		
	150mm x 150mm Base Plate	54	kg		
	150mm x 150mm Wing Plate	15	kg		
	25mmØ x 450mm Anchor Bolt	192	pc		
D.	Roofing Works				
	6mm Solid Polycarbonate Sheet	49	sq.m.		
	GI Flashing	49	l.m.		
	Tekscrew	171	pcs		
	Silicon Sealant	28	tubes		
E.	Miscellaneous & Consumables				
	Assorted Metal Drill Bit	10	pcs		
	Cut Off Blade	5	pcs		
	Grinding Disc	2	pcs		
	Hacksaw Blade	5	pcs		
	Welding Rod	2	boxes		
				Materials Cost III	P
				Labor Cost III	
				Direct Cost III	P
IV.	ARCHITECTURAL WORKS				
	Painting Works				
	Epoxy Enamel Paint Finish (Steel Surfaces)	290	sq.m.	P	P
	Elastomeric Paint Finish (Exterior Wall)	16	sq.m.		
				Materials Cost IV	P
				Labor Cost IV	
				Direct Cost IV	P

ITEM NO.	WORK DESCRIPTION AND SCOPE OF WORKS	QTY.	UNIT	UNIT COST	TOTAL COST
----------	-------------------------------------	------	------	-----------	------------

SUMMARY

ITEM NO.	WORK DESCRIPTION AND SCOPE OF WORKS	TOTAL COST
I.	GENERAL REQUIREMENTS	P
II.	SITE WORKS	
III.	CIVIL / STRUCTURAL WORKS	
IV.	ARCHITECTURAL WORKS	
TOTAL DIRECT COST Overhead, Contingencies & Miscellaneous (OCM) Profit VAT		P
TOTAL ESTIMATED COST		P

PROJECT TITLE: PROPOSED CONSTRUCTION OF CANOPY AT 3RD FLOOR MULTI-PURPOSE HALL AT SCOUT TUAZON CORNER SCOUT GANDIA

LOCATION : BARANGAY LAGING HANDA, DISTRICT 4, QUEZON CITY

PROJECT NO. : 20 - 00132

DURATION : Sixty (60) Calendar Days

BREAKDOWN OF COST

ITEM NO.	ITEM OF WORK (DESCRIPTION)	MATERIALS COST	LABOR COST	INDIRECT COST	AGGREGATE COST
I.	GENERAL REQUIREMENTS				
II.	SITE WORKS				
III.	CIVIL / STRUCTURAL WORKS				
IV.	ARCHITECTURAL WORKS				

TOTAL COST ₱ _____

LUMP SUM BID IN WORDS : _____

Contractor : _____