

PHILIPPINE BIDDING DOCUMENTS

Procurement of INFRASTRUCTURE PROJECTS

Government of the Republic of the Philippines

**PROPOSED CONSTRUCTION OF HOUSING 32 –
BALINGASA HIGH RISE HOUSING (PHASE 1A) AT
BARANGAY BALINGASA**

**Project number:
22-00074**

**Sixth Edition
July 2020**

Preface

These Philippine Bidding Documents (PBDs) for the procurement of Infrastructure Projects (hereinafter referred to also as the “Works”) through Competitive Bidding have been prepared by the Government of the Philippines for use by all branches, agencies, departments, bureaus, offices, or instrumentalities of the government, including government-owned and/or -controlled corporations, government financial institutions, state universities and colleges, local government units, and autonomous regional government. The procedures and practices presented in this document have been developed through broad experience, and are for mandatory use in projects that are financed in whole or in part by the Government of the Philippines or any foreign government/foreign or international financing institution in accordance with the provisions of the 2016 revised Implementing Rules and Regulations (IRR) of Republic Act (RA) No. 9184.

The PBDs are intended as a model for admeasurements (unit prices or unit rates in a bill of quantities) types of contract, which are the most common in Works contracting.

The Bidding Documents shall clearly and adequately define, among others: (i) the objectives, scope, and expected outputs and/or results of the proposed contract; (ii) the eligibility requirements of Bidders; (iii) the expected contract duration; and (iv) the obligations, duties, and/or functions of the winning Bidder.

Care should be taken to check the relevance of the provisions of the PBDs against the requirements of the specific Works to be procured. If duplication of a subject is inevitable in other sections of the document prepared by the Procuring Entity, care must be exercised to avoid contradictions between clauses dealing with the same matter.

Moreover, each section is prepared with notes intended only as information for the Procuring Entity or the person drafting the Bidding Documents. They shall not be included in the final documents. The following general directions should be observed when using the documents:

- a. All the documents listed in the Table of Contents are normally required for the procurement of Infrastructure Projects. However, they should be adapted as necessary to the circumstances of the particular Project.
- b. Specific details, such as the “*name of the Procuring Entity*” and “*address for bid submission*,” should be furnished in the Instructions to Bidders, Bid Data Sheet, and Special Conditions of Contract. The final documents should contain neither blank spaces nor options.
- c. This Preface and the footnotes or notes in italics included in the Invitation to Bid, BDS, General Conditions of Contract, Special Conditions of Contract, Specifications, Drawings, and Bill of Quantities are not part of the text of the final document, although they contain instructions that the Procuring Entity should strictly follow.
- d. The cover should be modified as required to identify the Bidding Documents as to the names of the Project, Contract, and Procuring Entity, in addition to date of issue.

- e. Modifications for specific Procurement Project details should be provided in the Special Conditions of Contract as amendments to the Conditions of Contract. For easy completion, whenever reference has to be made to specific clauses in the Bid Data Sheet or Special Conditions of Contract, these terms shall be printed in bold typeface on Sections I (Instructions to Bidders) and III (General Conditions of Contract), respectively.
- f. For guidelines on the use of Bidding Forms and the procurement of Foreign-Assisted Projects, these will be covered by a separate issuance of the Government Procurement Policy Board.

TABLE OF CONTENTS

Glossary of Terms, Abbreviations, and Acronyms.....	5
Section I. Invitation to Bid	8
Section II. Instructions to Bidders.....	9
1. Scope of Bid.....	10
2. Funding Information	10
3. Bidding Requirements.....	10
4. Corrupt, Fraudulent, Collusive, Coercive, and Obstructive Practices	10
5. Eligible Bidders.....	11
6. Origin of Associated Goods	11
7. Subcontracts	11
8. Pre-Bid Conference.....	12
9. Clarification and Amendment of Bidding Documents.....	12
10. Documents Comprising the Bid: Eligibility and Technical Components.....	12
11. Documents Comprising the Bid: Financial Component	13
12. Alternative Bids	13
13. Bid Prices	13
14. Bid and Payment Currencies.....	13
15. Bid Security.....	14
16. Sealing and Marking of Bids.....	14
17. Deadline for Submission of Bids	14
18. Opening and Preliminary Examination of Bids	14
19. Detailed Evaluation and Comparison of Bids.....	15
20. Post Qualification.....	15
21. Signing of the Contract	15
Section III. Bid Data Sheet.....	16
Section IV. General Conditions of Contract	19
1. Scope of Contract.....	20
2. Sectional Completion of Works	20
3. Possession of Site.....	20
4. The Contractor’s Obligations.....	20
5. Performance Security	20
6. Site Investigation Reports	21

7.	Warranty.....	21
8.	Liability of the Contractor.....	21
9.	Termination for Other Causes.....	21
10.	Dayworks.....	21
11.	Program of Work.....	22
12.	Instructions, Inspections and Audits.....	22
13.	Advance Payment.....	22
14.	Progress Payments.....	22
15.	Operating and Maintenance Manuals.....	22
	Section V. Special Conditions of Contract.....	24
	Section VI. Specifications.....	26
	Section VII. Drawings.....	28
	Section VIII. Bill of Quantities.....	29
	Section IX. Checklist of Technical and Financial Documents.....	31

Glossary of Terms, Abbreviations, and Acronyms

ABC – Approved Budget for the Contract.

ARCC – Allowable Range of Contract Cost.

BAC – Bids and Awards Committee.

Bid – A signed offer or proposal to undertake a contract submitted by a bidder in response to and in consonance with the requirements of the bidding documents. Also referred to as *Proposal* and *Tender*. (2016 revised IRR, Section 5[c])

Bidder – Refers to a contractor, manufacturer, supplier, distributor and/or consultant who submits a bid in response to the requirements of the Bidding Documents. (2016 revised IRR, Section 5[d])

Bidding Documents – The documents issued by the Procuring Entity as the bases for bids, furnishing all information necessary for a prospective bidder to prepare a bid for the Goods, Infrastructure Projects, and/or Consulting Services required by the Procuring Entity. (2016 revised IRR, Section 5[e])

BIR – Bureau of Internal Revenue.

BSP – Bangko Sentral ng Pilipinas.

CDA – Cooperative Development Authority.

Consulting Services – Refer to services for Infrastructure Projects and other types of projects or activities of the GOP requiring adequate external technical and professional expertise that are beyond the capability and/or capacity of the GOP to undertake such as, but not limited to: (i) advisory and review services; (ii) pre-investment or feasibility studies; (iii) design; (iv) construction supervision; (v) management and related services; and (vi) other technical services or special studies. (2016 revised IRR, Section 5[i])

Contract – Refers to the agreement entered into between the Procuring Entity and the Supplier or Manufacturer or Distributor or Service Provider for procurement of Goods and Services; Contractor for Procurement of Infrastructure Projects; or Consultant or Consulting Firm for Procurement of Consulting Services; as the case may be, as recorded in the Contract Form signed by the parties, including all attachments and appendices thereto and all documents incorporated by reference therein.

Contractor – is a natural or juridical entity whose proposal was accepted by the Procuring Entity and to whom the Contract to execute the Work was awarded. Contractor as used in these Bidding Documents may likewise refer to a supplier, distributor, manufacturer, or consultant.

CPI – Consumer Price Index.

DOLE – Department of Labor and Employment.

DTI – Department of Trade and Industry.

Foreign-funded Procurement or Foreign-Assisted Project – Refers to procurement whose funding source is from a foreign government, foreign or international financing institution as specified in the Treaty or International or Executive Agreement. (2016 revised IRR, Section 5[b]).

GFI – Government Financial Institution.

GOCC – Government-owned and/or –controlled corporation.

Goods – Refer to all items, supplies, materials and general support services, except Consulting Services and Infrastructure Projects, which may be needed in the transaction of public businesses or in the pursuit of any government undertaking, project or activity, whether in the nature of equipment, furniture, stationery, materials for construction, or personal property of any kind, including non-personal or contractual services such as the repair and maintenance of equipment and furniture, as well as trucking, hauling, janitorial, security, and related or analogous services, as well as procurement of materials and supplies provided by the Procuring Entity for such services. The term “related” or “analogous services” shall include, but is not limited to, lease or purchase of office space, media advertisements, health maintenance services, and other services essential to the operation of the Procuring Entity. (2016 revised IRR, Section 5[r])

GOP – Government of the Philippines.

Infrastructure Projects – Include the construction, improvement, rehabilitation, demolition, repair, restoration or maintenance of roads and bridges, railways, airports, seaports, communication facilities, civil works components of information technology projects, irrigation, flood control and drainage, water supply, sanitation, sewerage and solid waste management systems, shore protection, energy/power and electrification facilities, national buildings, school buildings, hospital buildings, and other related construction projects of the government. Also referred to as *civil works or works*. (2016 revised IRR, Section 5[u])

LGUs – Local Government Units.

NFCC – Net Financial Contracting Capacity.

NGA – National Government Agency.

PCAB – Philippine Contractors Accreditation Board.

PhilGEPS - Philippine Government Electronic Procurement System.

Procurement Project – refers to a specific or identified procurement covering goods, infrastructure project or consulting services. A Procurement Project shall be described, detailed, and scheduled in the Project Procurement Management Plan prepared by the agency which shall be consolidated in the procuring entity's Annual Procurement Plan. (GPPB Circular No. 06-2019 dated 17 July 2019)

PSA – Philippine Statistics Authority.

SEC – Securities and Exchange Commission.

SLCC – Single Largest Completed Contract.

UN – United Nations.

Section I. Invitation to Bid

Notes on the Invitation to Bid

The Invitation to Bid (IB) provides information that enables potential Bidders to decide whether to participate in the procurement at hand. The IB shall be posted in accordance with Section 21.2 of the 2016 revised IRR of RA No. 9184.

Apart from the essential items listed in the Bidding Documents, the IB should also indicate the following:

- a. The date of availability of the Bidding Documents, which shall be from the time the IB is first advertised/posted until the deadline for the submission and receipt of bids;
- b. The place where the Bidding Documents may be acquired or the website where it may be downloaded;
- c. The deadline for the submission and receipt of bids; and
- d. Any important bid evaluation criteria.

The IB should be incorporated into the Bidding Documents. The information contained in the IB must conform to the Bidding Documents and in particular to the relevant information in the Bid Data Sheet.



REPUBLIC OF THE PHILIPPINES
QUEZON CITY GOVERNMENT
BIDS AND AWARDS COMMITTEE FOR INFRASTRUCTURE &
CONSULTANCY



2nd floor, Finance Building, Procurement Department, Quezon City Hall Complex, Elliptical Road, Quezon City

February 21, 2022

Invitation to Bid

No	Project No.	Project Name	Location	Amount	Durati on Cal. Days	Office	Source Fund
<u>Buildings – Small B</u>							
1	22-00057	Proposed Rehabilitation of Tennis Court Clubhouse at Barangay Marilag	Marilag	1,422,335.72	90	Engineering Department	Engineering Department
2	22-00058	Proposed Construction of Handwashing Facility and Rehabilitation of Comfort Rooms at Masambong High School	Masambong	1,430,662.67	60	Engineering Department	Special Education Fund
3	22-00059	Proposed Construction of Handwashing Facility and Rehabilitation of Comfort Rooms at Justice Cecilia Muñoz Palma High School	Payatas	1,454,032.48	60	Engineering Department	Special Education Fund
4	22-00060	Proposed Construction of Handwashing Facility and Rehabilitation of Comfort Rooms at Quezon City Science High School	Sto. Cristo	2,447,399.33	60	Engineering Department	Special Education Fund
5	22-00061	Proposed Construction of Roofing and Rehabilitation of Multipurpose Hall at Barangay Kristong Hari	Kristong Hari	3,300,872.34	120	Engineering Department	OCM-20% CDF
6	22-00062	Proposed Rehabilitation of Comfort Rooms at Sauyo High School	Sauyo	3,453,351.14	120	Engineering Department	Special Education Fund
7	22-00063	Proposed Construction of Handwashing Facility and Rehabilitation of Comfort Rooms at Bagong Silangan Elementary School	Bagong Silangan	3,471,667.31	60	Engineering Department	Special Education Fund
8	22-00064	Proposed Rehabilitation of Basketball Court at Faustina Street in Barangay Holy Spirit	Holy Spirit	6,466,841.58	120	Engineering Department	Engineering Department
9	22-00065	Proposed Rehabilitation of Barangay Hall at Barangay Bayanihan	Bayanihan	7,315,815.77	120	Engineering Department	Special Education Fund
10	22-00066	Proposed Construction of Badminton Court at Acropolis Greens Homeowners Tennis Court Building at Barangay Bagumbayan	Bagumbayan	13,754,732.29	210	Engineering Department	Engineering Department
11	22-00067	Proposed Rehabilitation of Barangay Hall at Barangay Kamuning	Kamuning	16,653,378.78	210	Engineering Department	Engineering Department

12	22-00068	Proposed Construction of Four (4) Storey with Covered Roof Deck, Barangay Hall at Barangay West Kamias	West Kamias	22,287,115.12	270	Engineering Department	Engineering Department
13	22-00069	Proposed Rehabilitation of Police Station 10 at Barangay Kamuning	Kamuning	24,095,855.77	240	Engineering Department	Engineering Department
14	22-00070	Proposed Construction of Remaining Works for the 2 3 Storey Buildings, Housing 32 (Balingasa)	Balingasa	27,432,958.14	270	Engineering Department	Housing Community Development and Resettlement Department

Buildings – Medium A

15	22-00071	Proposed Construction of Three (3) Storey Multi-Purpose Building (Phase-1) at Barangay Project 6	Project 6	60,391,917.88	300	Engineering Department	OCM-20% CDF
16	22-00072	Proposed Construction of Quezon City Jail Fence and Guard Tower (Phase 2)	Bagong Silangan	86,771,396.36	360	Engineering Department	Engineering Department-Continuing Appropriation
17	22-00073	Proposed Construction of Three (3) Storey Parking Building with Roof Deck at Barangay Loyola Heights (Phase 1)	Loyola Heights	89,412,605.98	330	Engineering Department	Engineering Department

Buildings – Large B

18	22-00074	Proposed Construction of Housing 32 – Balingasa High Rise Housing (Phase 1A) at Brgy. Balingasa	Balingasa	454,323,547.80	510	Engineering Department	Housing Community Development and Resettlement Department
----	----------	---	-----------	----------------	-----	------------------------	---

Flood Control – Small B

19	22-00075	Proposed Construction of Reinforced Concrete Retaining Wall at Pasong Tamo River (Tandang Sora Avenue) in Barangay Culiat	Culiat	13,455,123.58	180	Engineering Department	OCM - LDRRMF
20	22-00076	Proposed Construction of Reinforced Concrete Retaining Wall at Blk. 15 (Violago Parkwood Hills) in Barangay Bagong Silangan	Bagong Silangan	15,524,797.05	180	Engineering Department	OCM - LDRRMF

Flood Control – Medium A

21	22-00077	Proposed Construction of Reinforced Concrete Canal at Sampaguita Creek (Maligaya Park Subdivision) in Barangay Pasong Putik	Pasong Putik	56,309,183.41	300	Engineering Department	OCM - LDRRMF
----	----------	---	--------------	---------------	-----	------------------------	--------------

Parks – Small B

22	22-00078	Landscape Development of Baesa Columbarium	Baesa	3,497,838.42	60	Parks Development & Admin. Dept.	Engineering Department
23	22-00079	Proposed Improvement of West Triangle Mini Park	West Triangle	3,697,090.86	75	Parks Development & Admin. Dept.	Engineering Department
24	22-00080	Proposed Construction of Pedestrian Safety Island Pocket Park at East Avenue corner NIA Road	Central	5,555,100.50	105	Parks Development & Admin. Dept.	Engineering Department
25	22-00081	Proposed Improvement of People's Park along Quezon Avenue	Tatalon	10,134,490.29	180	Parks Development & Admin. Dept.	Engineering Department
26	22-00082	Proposed Improvement of St. James Park along St. Benedict Street, St. James Subd.	Nagkaisang Nayon	15,972,224.89	225	Parks Development & Admin. Dept.	Engineering Department

Roads – Small B

27	22-00083	Proposed Rehabilitation of Road and Drainage at Albay Street in Barangay Alicia	Alicia	1,095,756.90	90	Engineering Department	OCM-20% CDF
28	22-00084	Proposed Rehabilitation (Surface Improvement) at Doña Rosario Compound	Novaliches Proper	1,320,422.33	20	Engineering Department	OCM-20% CDF
29	22-00085	Proposed Rehabilitation (Surface Improvement) at Doña Isaura Street	Novaliches Proper	1,754,468.25	30	Engineering Department	OCM-20% CDF
30	22-00086	Proposed Rehabilitation (Surface Improvement) at Doña Rosario Street	Novaliches Proper	2,254,674.45	20	Engineering Department	OCM-20% CDF
31	22-00087	Proposed Rehabilitation (Surface Improvement) at Austria Street	Novaliches Proper	3,191,904.00	90	Engineering Department	OCM-20% CDF
32	22-00088	Proposed Rehabilitation of Drainage and Surface Improvement at Kalliraya Street in Barangay Doña Josefa	Doña Josefa	3,263,621.90	90	Engineering Department	OCM-20% CDF
33	22-00089	Proposed Rehabilitation of Sidewalk, Curband Gutter of Anonas Extension in Barangay Sikatuna Village	Sikatuna Village	3,794,636.09	90	Engineering Department	OCM-20% CDF
34	22-00090	Proposed Rehabilitation (Surface Improvement) at S. Benito Street in Barangay Holy Spirit	Holy Spirit	4,084,087.37	40	Engineering Department	OCM-20% CDF
35	22-00091	Proposed Rehabilitation of Road and Drainage at Balabac Street in Doña Imelda	Doña Imelda	11,835,617.22	180	Engineering Department	OCM-20% CDF

1. The **QUEZON CITY LOCAL GOVERNMENT**, through *funding source of various years* intends to apply the sum stated above being the Approved Budget for the Contract (ABC) to payments under the contract *for the above stated Projects*. Bids received in excess of the ABC shall be automatically rejected at bid opening.
2. The **QUEZON CITY LOCAL GOVERNMENT** now invites bids for the above Procurement Project. Completion of the Works is required *as stated above*. Bidders should have completed a contract similar to the Project. The description of an eligible bidder is contained in the Bidding Documents, particularly, in Section II (Instructions to Bidders).
3. Bidding will be conducted through open competitive bidding procedures using non-discretionary "*pass/fail*" criterion as specified in the 2016 revised Implementing Rules and Regulations (IRR) of Republic Act (RA) No. 9184.
4. Interested bidders may obtain further information from **QUEZON CITY LOCAL GOVERNMENT – BAC Secretariat** and inspect the Bidding Documents at the address given below *weekdays from 8:00 am. – 5:00 p.m.*
5. A complete set of Bidding Documents may be acquired by interested bidders on **22 February 2022 (Tuesday)** from given address and website/s below *and upon payment of a non-refundable fee for the Bidding Documents, pursuant to the latest Guidelines issued by the GPPB*. The Procuring Entity shall allow the bidder to present its proof of payment for the fees *presented in person*.

STANDARD RATES:

Approved Budget for the Contract	Maximum Cost of Bidding Documents (in Philippine Peso)
More than 1 Million up to 5 Million	5,000.00
More than 5 Million up to 10 Million	10,000.00
More than 10 Million up to 50 Million	25,000.00
More than 50 Million up to 500 Million	50,000.00
More than 500 Million	75,000.00

The following are the requirements for purchase of Bidding Documents;

1. PhilGEPS Registration Certificate (Platinum – 3 Pages)
2. Document Request List (DRL)
3. Authorization to purchase bidding documents
 - 3.1 Secretary's Certificate (for corporation)
 - 3.2 Special Power of Attorney (for sole proprietorship)
4. Notarized Joint Venture Agreement (if applicable)
5. Letter of Intent

It must be duly received by the BAC Secretariat at 2nd Floor, Procurement Department, Finance Building, Quezon City Hall Compound on or before **March 2, 2022 - 5:00PM**.

6. The **QC- BAC- INFRASTRUCTURE & CONSULTANCY** will hold a Pre-Bid Conference¹ on **March 3, 2022 at 9:00 AM at 2nd Floor, Procurement Department-Bidding Room, Finance Building, Quezon City Hall Compound** or we encourage the prospective bidders to join through our **Virtual Conference (ZOOM APP)** which shall be open to prospective bidders.

Virtual Conference (ZOOM APP)

Meeting ID: 854 9489 0133

Password: 273320

¹ May be deleted in case the ABC is less than One Million Pesos (PhP1,000,000) where the Procuring Entity may not hold a pre-bid conference.

7. Bids must be duly received by the BAC Secretariat through manual submission at the office address as indicated below, on or before **March 17, 2022 – 9:00AM**. Late bids shall not be accepted.
8. All bids must be accompanied by a bid security in any of the acceptable forms and in the amount stated in **ITB Clause 16**.
9. Bid opening shall be on **March 17, 2022 - 10:00 AM** at **2nd Floor, Procurement Department-Bidding Room, Finance Building, Quezon City Hall Compound** and/or via Zoom. Bids will be opened in the presence of the bidders' representatives who choose to attend the activity.

Virtual Conference (ZOOM APP)

Meeting ID: 810 3646 5257

Password: 201522

10. The *Quezon City Local Government* reserves the right to reject any and all bids, declare a failure of bidding, or not award the contract at any time prior to contract award in accordance with Sections 35.6 and 41 of the 2016 revised Implementing Rules and Regulations (IRR) of RA No. 9184, without thereby incurring any liability to the affected bidder or bidders.

11. For further information, please refer to:

ATTY. DOMINIC B. GARCIA

OIC, Procurement Department

2nd Floor, Procurement Department,

Finance Building, Quezon City Hall Compound

Elliptical Road, Barangay Central Diliman, Quezon City.

Tel. No. (02)8988-4242 loc. 8506/8710

Email Add: bacinfra.procurement@quezoncity.gov.ph

Website: www.quezoncity.gov.ph

12. You may visit the following websites:

For downloading of Bidding Documents: <https://quezoncity.gov.ph/public-notices/procurement/>

By:


ATTY. MARK DALE DIAMOND P. PERRAL

Chairman, BAC-Infra and Consultancy 

Section II. Instructions to Bidders

Notes on the Instructions to Bidders

This Section on the Instruction to Bidders (ITB) provides the information necessary for bidders to prepare responsive bids, in accordance with the requirements of the Procuring Entity. It also provides information on bid submission, eligibility check, opening and evaluation of bids, post-qualification, and on the award of contract.

1. Scope of Bid

The Procuring Entity, **Quezon City Government** invites Bids for the **PROPOSED CONSTRUCTION OF HOUSING 32 – BALINGASA HIGH RISE HOUSING (PHASE 1A) AT BARANGAY BALINGASA**, with Project Identification Number **22-00074**.

[Note: The Project Identification Number is assigned by the Procuring Entity based on its own coding scheme and is not the same as the PhilGEPS reference number, which is generated after the posting of the bid opportunity on the PhilGEPS website.]

The Procurement Project (referred to herein as “Project”) is for the construction of Works, as described in Section VI (Specifications).

2. Funding Information

2.1. The GOP through the source of funding as indicated below for **2022** in the amount of **Four Hundred Fifty-Four Million Three Hundred Twenty-Three Thousand Five Hundred Forty-Seven Pesos and 80/100 Cts. (P 454,323,547.80)**.

2.2. The source of funding is:

a. LGUs, the Annual or Supplemental Budget, as approved by the Sanggunian.

3. Bidding Requirements

The Bidding for the Project shall be governed by all the provisions of RA No. 9184 and its 2016 revised IRR, including its Generic Procurement Manual and associated policies, rules and regulations as the primary source thereof, while the herein clauses shall serve as the secondary source thereof.

Any amendments made to the IRR and other GPPB issuances shall be applicable only to the ongoing posting, advertisement, or invitation to bid by the BAC through the issuance of a supplemental or bid bulletin.

The Bidder, by the act of submitting its Bid, shall be deemed to have inspected the site, determined the general characteristics of the contracted Works and the conditions for this Project, such as the location and the nature of the work; (b) climatic conditions; (c) transportation facilities; (c) nature and condition of the terrain, geological conditions at the site communication facilities, requirements, location and availability of construction aggregates and other materials, labor, water, electric power and access roads; and (d) other factors that may affect the cost, duration and execution or implementation of the contract, project, or work and examine all instructions, forms, terms, and project requirements in the Bidding Documents.

4. Corrupt, Fraudulent, Collusive, Coercive, and Obstructive Practices

The Procuring Entity, as well as the Bidders and Contractors, shall observe the highest standard of ethics during the procurement and execution of the contract. They or through an agent shall not engage in corrupt, fraudulent, collusive, coercive, and obstructive practices defined under Annex “I” of the 2016 revised IRR of RA No. 9184 or other integrity violations in competing for the Project.

5. Eligible Bidders

- 5.1. Only Bids of Bidders found to be legally, technically, and financially capable will be evaluated.
- 5.2. The Bidder must have an experience of having completed a Single Largest Completed Contract (SLCC) that is similar to this Project, equivalent to at least fifty percent (50%) of the ABC adjusted, if necessary, by the Bidder to current prices using the PSA’s CPI, except under conditions provided for in Section 23.4.2.4 of the 2016 revised IRR of RA No. 9184.

A contract is considered to be “similar” to the contract to be bid if it has the major categories of work stated in the **BDS**.

- 5.3. For Foreign-funded Procurement, the Procuring Entity and the foreign government/foreign or international financing institution may agree on another track record requirement, as specified in the Bidding Document prepared for this purpose.
- 5.4. The Bidders shall comply with the eligibility criteria under Section 23.4.2 of the 2016 IRR of RA No. 9184.

6. Origin of Associated Goods

There is no restriction on the origin of Goods other than those prohibited by a decision of the UN Security Council taken under Chapter VII of the Charter of the UN.

7. Subcontracts

- 7.1. The Bidder may subcontract portions of the Project to the extent allowed by the Procuring Entity as stated herein, but in no case more than fifty percent (50%) of the Project.

The Procuring Entity has prescribed that:

a. Subcontracting is not allowed.

- 7.1. *[If Procuring Entity has determined that subcontracting is allowed during the bidding , state:]* The Bidder must submit together with its Bid the documentary requirements of the subcontractor(s) complying with the eligibility criterial stated in **ITB** Clause 5 in accordance with Section 23.4 of the 2016 revised IRR of RA No. 9184 pursuant to Section 23.1 thereof.

- 7.2. *[If subcontracting is allowed during the contract implementation stage, state:]*
The Supplier may identify its subcontractor during the contract implementation stage. Subcontractors identified during the bidding may be changed during the implementation of this Contract. Subcontractors must submit the documentary requirements under Section 23.1 of the 2016 revised IRR of RA No. 9184 and comply with the eligibility criteria specified in **ITB** Clause 5 to the implementing or end-user unit.
- 7.3. Subcontracting of any portion of the Project does not relieve the Contractor of any liability or obligation under the Contract. The Supplier will be responsible for the acts, defaults, and negligence of any subcontractor, its agents, servants, or workmen as fully as if these were the Contractor's own acts, defaults, or negligence, or those of its agents, servants, or workmen.

8. Pre-Bid Conference

The Procuring Entity will hold a pre-bid conference for this Project on the specified date and time and either at its physical address on **March 3, 2022, 10:00 A.M. at 2nd Floor, Procurement Department-Bidding Room, Finance Building, Quezon City Hall Compound** and/or we encourage the prospective bidders to join through our **Virtual Conference (ZOOM APP) Meeting ID: 854 9489 0133 Password: 273320**

9. Clarification and Amendment of Bidding Documents

Prospective bidders may request for clarification on and/or interpretation of any part of the Bidding Documents. Such requests must be in writing and received by the Procuring Entity, either at its given address or through electronic mail indicated in the **IB**, at least ten (10) calendar days before the deadline set for the submission and receipt of Bids.

10. Documents Comprising the Bid: Eligibility and Technical Components

- 10.1. The first envelope shall contain the eligibility and technical documents of the Bid as specified in **Section IX. Checklist of Technical and Financial Documents**.
- 10.2. If the eligibility requirements or statements, the bids, and all other documents for submission to the BAC are in foreign language other than English, it must be accompanied by a translation in English, which shall be authenticated by the appropriate Philippine foreign service establishment, post, or the equivalent office having jurisdiction over the foreign bidder's affairs in the Philippines. For Contracting Parties to the Apostille Convention, only the translated documents shall be authenticated through an apostille pursuant to GPPB Resolution No. 13-2019 dated 23 May 2019. The English translation shall govern, for purposes of interpretation of the bid.
- 10.3. A valid PCAB License is required, and in case of joint ventures, a valid special PCAB License, and registration for the type and cost of the contract for this

Project. Any additional type of Contractor license or permit shall be indicated in the **BDS**.

- 10.4. A List of Contractor's key personnel (e.g., Project Manager, Project Engineers, Materials Engineers, and Foremen) assigned to the contract to be bid, with their complete qualification and experience data shall be provided. These key personnel must meet the required minimum years of experience set in the **BDS**.
- 10.5. A List of Contractor's major equipment units, which are owned, leased, and/or under purchase agreements, supported by proof of ownership, certification of availability of equipment from the equipment lessor/vendor for the duration of the project, as the case may be, must meet the minimum requirements for the contract set in the **BDS**.

11. Documents Comprising the Bid: Financial Component

- 11.1. The second bid envelope shall contain the financial documents for the Bid as specified in **Section IX. Checklist of Technical and Financial Documents**.
- 11.2. Any bid exceeding the ABC indicated in paragraph 1 of the **IB** shall not be accepted.
- 11.3. For Foreign-funded procurement, a ceiling may be applied to bid prices provided the conditions are met under Section 31.2 of the 2016 revised IRR of RA No. 9184.

12. Alternative Bids

Bidders shall submit offers that comply with the requirements of the Bidding Documents, including the basic technical design as indicated in the drawings and specifications. Unless there is a value engineering clause in the **BDS**, alternative Bids shall not be accepted.

13. Bid Prices

All bid prices for the given scope of work in the Project as awarded shall be considered as fixed prices, and therefore not subject to price escalation during contract implementation, except under extraordinary circumstances as determined by the NEDA and approved by the GPPB pursuant to the revised Guidelines for Contract Price Escalation guidelines.

14. Bid and Payment Currencies

- 14.1. Bid prices may be quoted in the local currency or tradeable currency accepted by the BSP at the discretion of the Bidder. However, for purposes of bid evaluation, Bids denominated in foreign currencies shall be converted to Philippine currency based on the exchange rate as published in the BSP reference rate bulletin on the day of the bid opening.

14.2. *Payment of the contract price shall be made in:*

- a. Philippine Pesos.

15. Bid Security

15.1. The Bidder shall submit a Bid Securing Declaration or any form of Bid Security in the amount indicated in the **BDS**, which shall be not less than the percentage of the ABC in accordance with the schedule in the **BDS**.

15.2. The Bid and bid security **in no case shall exceed One Hundred Twenty (120) calendar days from the date of opening of bids, unless duly extended by the bidder upon the request of the Head of the Procuring Entity (HoPE) of the Quezon City Local Government**. Any bid not accompanied by an acceptable bid security shall be rejected by the Procuring Entity as non-responsive.

16. Sealing and Marking of Bids

Each Bidder shall submit one copy of the first and second components of its Bid.

The Procuring Entity may request additional hard copies and/or electronic copies of the Bid. However, failure of the Bidders to comply with the said request shall not be a ground for disqualification.

If the Procuring Entity allows the submission of bids through online submission to the given website or any other electronic means, the Bidder shall submit an electronic copy of its Bid, which must be digitally signed. An electronic copy that cannot be opened or is corrupted shall be considered non-responsive and, thus, automatically disqualified.

17. Deadline for Submission of Bids

The Bidders shall submit on the specified date and time and either at its physical address or through online submission as indicated in paragraph 5 of the **IB**.

18. Opening and Preliminary Examination of Bids

18.1. The BAC shall open the Bids in public at the time, on the date, and at the place specified in paragraph 9 of the **IB**. The Bidders' representatives who are present shall sign a register evidencing their attendance. In case videoconferencing, webcasting or other similar technologies will be used, attendance of participants shall likewise be recorded by the BAC Secretariat.

In case the Bids cannot be opened as scheduled due to justifiable reasons, the rescheduling requirements under Section 29 of the 2016 revised IRR of RA No. 9184 shall prevail.

18.2. The preliminary examination of Bids shall be governed by Section 30 of the 2016 revised IRR of RA No. 9184.

19. Detailed Evaluation and Comparison of Bids

- 19.1. The Procuring Entity's BAC shall immediately conduct a detailed evaluation of all Bids rated "*passed*" using non-discretionary pass/fail criteria. The BAC shall consider the conditions in the evaluation of Bids under Section 32.2 of 2016 revised IRR of RA No. 9184.
- 19.2. If the Project allows partial bids, all Bids and combinations of Bids as indicated in the **BDS** shall be received by the same deadline and opened and evaluated simultaneously so as to determine the Bid or combination of Bids offering the lowest calculated cost to the Procuring Entity. Bid Security as required by **ITB** Clause 15 shall be submitted for each contract (lot) separately.
- 19.3. In all cases, the NFCC computation pursuant to Section 23.4.2.6 of the 2016 revised IRR of RA No. 9184 must be sufficient for the total of the ABCs for all the lots participated in by the prospective Bidder.

20. Post Qualification

Within a non-extendible period of five (5) calendar days from receipt by the Bidder of the notice from the BAC that it submitted the Lowest Calculated Bid, the Bidder shall submit its latest income and business tax returns filed and paid through the BIR Electronic Filing and Payment System (eFPS), and other appropriate licenses and permits required by law and stated in the **BDS**.

21. Signing of the Contract

The documents required in Section 37.2 of the 2016 revised IRR of RA No. 9184 shall form part of the Contract. Additional Contract documents are indicated in the **BDS**.

Section III. Bid Data Sheet

Notes on the Bid Data Sheet (BDS)

The Bid Data Sheet (BDS) consists of provisions that supplement, amend, or specify in detail, information, or requirements included in the ITB found in Section II, which are specific to each procurement.

This Section is intended to assist the Procuring Entity in providing the specific information in relation to corresponding clauses in the ITB and has to be prepared for each specific procurement.

The Procuring Entity should specify in the BDS information and requirements specific to the circumstances of the Procuring Entity, the processing of the procurement, and the bid evaluation criteria that will apply to the Bids. In preparing the BDS, the following aspects should be checked:

- a. Information that specifies and complements provisions of the ITB must be incorporated.
- b. Amendments and/or supplements, if any, to provisions of the ITB as necessitated by the circumstances of the specific procurement, must also be incorporated.

Bid Data Sheet

ITB Clause																																	
5.2	For this purpose, similar contracts shall refer to contracts which have the same major categories of work.																																
7.1	Subcontracting is not allowed.																																
10.3	<p><i>No additional contractor license or permit is required</i></p> <p><i>In addition, eligible bidders shall qualify or comply with the following:</i></p> <p>1. Bidders with valid Philippine Contractors Accreditation Board (PCAB)</p> <p style="padding-left: 40px;">Type</p> <p style="text-align: center;">Buildings – Large B</p>																																
10.4	<p>The minimum work experience requirements for key personnel are the following:</p> <table border="1" style="width: 100%; border-collapse: collapse; margin-left: 20px;"> <thead> <tr> <th style="text-align: center;">Qty.</th> <th style="text-align: center;">Key Personnel</th> <th style="text-align: center;">General Experience</th> <th style="text-align: center;">Relevant Experience</th> </tr> </thead> <tbody> <tr> <td style="text-align: center;">1</td> <td>Project Engineer</td> <td style="text-align: center;">3 years</td> <td style="text-align: center;">3 years</td> </tr> <tr> <td style="text-align: center;">1</td> <td>DPWH duly accredited Materials Engineer</td> <td style="text-align: center;">3 years</td> <td style="text-align: center;">3 years</td> </tr> <tr> <td style="text-align: center;">1</td> <td>Safety Officer</td> <td style="text-align: center;">3 years</td> <td style="text-align: center;">3 years</td> </tr> <tr> <td style="text-align: center;">1</td> <td>Foreman</td> <td style="text-align: center;">3 years</td> <td style="text-align: center;">3 years</td> </tr> <tr> <td style="text-align: center;">80</td> <td>Skilled Worker</td> <td style="text-align: center;">3 years</td> <td style="text-align: center;">3 years</td> </tr> <tr> <td style="text-align: center;">1</td> <td>Driver</td> <td style="text-align: center;">3 years</td> <td style="text-align: center;">3 years</td> </tr> <tr> <td style="text-align: center;">160</td> <td>Laborer</td> <td style="text-align: center;">1 year</td> <td style="text-align: center;">3 months</td> </tr> </tbody> </table> <p><i>In addition, the bidder must execute an affidavit of undertaking duly notarized stating that the foregoing personnel shall perform work exclusively for the project until its completion. Please see attached bid forms.</i></p>	Qty.	Key Personnel	General Experience	Relevant Experience	1	Project Engineer	3 years	3 years	1	DPWH duly accredited Materials Engineer	3 years	3 years	1	Safety Officer	3 years	3 years	1	Foreman	3 years	3 years	80	Skilled Worker	3 years	3 years	1	Driver	3 years	3 years	160	Laborer	1 year	3 months
Qty.	Key Personnel	General Experience	Relevant Experience																														
1	Project Engineer	3 years	3 years																														
1	DPWH duly accredited Materials Engineer	3 years	3 years																														
1	Safety Officer	3 years	3 years																														
1	Foreman	3 years	3 years																														
80	Skilled Worker	3 years	3 years																														
1	Driver	3 years	3 years																														
160	Laborer	1 year	3 months																														
10.5	<p>The minimum major equipment requirements are the following:</p> <table border="1" style="width: 100%; border-collapse: collapse; margin-left: 20px;"> <thead> <tr> <th style="text-align: left;">Equipment</th> <th style="text-align: center;">Capacity</th> <th style="text-align: center;">Number of Units</th> </tr> </thead> <tbody> <tr> <td>Elf Truck</td> <td></td> <td style="text-align: center;">1</td> </tr> <tr> <td>Scaffolding</td> <td></td> <td style="text-align: center;">as needed</td> </tr> <tr> <td>Power Tools</td> <td></td> <td style="text-align: center;">as needed</td> </tr> <tr> <td>Minor Tools</td> <td></td> <td style="text-align: center;">as needed</td> </tr> </tbody> </table> <p><i>In addition, the bidder must execute an affidavit of undertaking duly</i></p>	Equipment	Capacity	Number of Units	Elf Truck		1	Scaffolding		as needed	Power Tools		as needed	Minor Tools		as needed																	
Equipment	Capacity	Number of Units																															
Elf Truck		1																															
Scaffolding		as needed																															
Power Tools		as needed																															
Minor Tools		as needed																															

	<i>notarized stating that the foregoing equipment shall be used exclusively for the project until its completion. Please see attached bid forms.</i>
12	<i>[Insert Value Engineering clause if allowed.]</i>
15.1	The bid security shall be in the form of a Bid Securing Declaration with project number, or any of the following forms and amounts: <ul style="list-style-type: none"> a) The amount of not less than Php 9,086,470.96 or equivalent to two percent (2%) of ABC if bid security is in cash, cashier's/manager's check, bank draft/guarantee or irrevocable letter of credit; or b) The amount of not less than Php 22,716,177.39 or equivalent to five percent (5%) of ABC if bid security is in Surety Bond.
19.2	Partial bid is not allowed. The infrastructure project is packaged in a single lot and the lot shall not be divided into sub-lots for the purpose of bidding, evaluation, and contract award.
20	No additional requirement.
21	Additional Contract Documents relevant to the Project as required: <ol style="list-style-type: none"> 1. Construction Schedule and S-curve, 2. Manpower Schedule, 3. Construction Methods, 4. Equipment Utilization Schedule, 5. PERT/CPM or other acceptable tools of project scheduling, shall be included in the submission of Technical Proposal.

Section IV. General Conditions of Contract

Notes on the General Conditions of Contract

The General Conditions of Contract (GCC) in this Section, read in conjunction with the Special Conditions of Contract in Section V and other documents listed therein, should be a complete document expressing all the rights and obligations of the parties.

Matters governing performance of the Contractor, payments under the contract, or matters affecting the risks, rights, and obligations of the parties under the contract are included in the GCC and Special Conditions of Contract.

Any complementary information, which may be needed, shall be introduced only through the Special Conditions of Contract.

1. **Scope of Contract**

This Contract shall include all such items, although not specifically mentioned, that can be reasonably inferred as being required for its completion as if such items were expressly mentioned herein. All the provisions of RA No. 9184 and its 2016 revised IRR, including the Generic Procurement Manual, and associated issuances, constitute the primary source for the terms and conditions of the Contract, and thus, applicable in contract implementation. Herein clauses shall serve as the secondary source for the terms and conditions of the Contract.

This is without prejudice to Sections 74.1 and 74.2 of the 2016 revised IRR of RA No. 9184 allowing the GPPB to amend the IRR, which shall be applied to all procurement activities, the advertisement, posting, or invitation of which were issued after the effectivity of the said amendment.

2. **Sectional Completion of Works**

If sectional completion is specified in the **Special Conditions of Contract (SCC)**, references in the Conditions of Contract to the Works, the Completion Date, and the Intended Completion Date shall apply to any Section of the Works (other than references to the Completion Date and Intended Completion Date for the whole of the Works).

3. **Possession of Site**

3.1 The Procuring Entity shall give possession of all or parts of the Site to the Contractor based on the schedule of delivery indicated in the **SCC**, which corresponds to the execution of the Works. If the Contractor suffers delay or incurs cost from failure on the part of the Procuring Entity to give possession in accordance with the terms of this clause, the Procuring Entity's Representative shall give the Contractor a Contract Time Extension and certify such sum as fair to cover the cost incurred, which sum shall be paid by Procuring Entity.

3.2 If possession of a portion is not given by the above date, the Procuring Entity will be deemed to have delayed the start of the relevant activities. The resulting adjustments in contract time to address such delay may be addressed through contract extension provided under Annex "E" of the 2016 revised IRR of RA No. 9184.

4. **The Contractor's Obligations**

The Contractor shall employ the key personnel named in the Schedule of Key Personnel indicating their designation, in accordance with **ITB** Clause 10.3 and specified in the **BDS**, to carry out the supervision of the Works.

The Procuring Entity will approve any proposed replacement of key personnel only if their relevant qualifications and abilities are equal to or better than those of the personnel listed in the Schedule.

5. **Performance Security**

- 5.1. Within ten (10) calendar days from receipt of the Notice of Award from the Procuring Entity but in no case later than the signing of the contract by both parties, the successful Bidder shall furnish the performance security in any of the forms prescribed in Section 39 of the 2016 revised IRR.
- 5.2. The Contractor, by entering into the Contract with the Procuring Entity, acknowledges the right of the Procuring Entity to institute action pursuant to RA No. 3688 against any subcontractor be they an individual, firm, partnership, corporation, or association supplying the Contractor with labor, materials and/or equipment for the performance of this Contract.

6. Site Investigation Reports

The Contractor, in preparing the Bid, shall rely on any Site Investigation Reports referred to in the SCC supplemented by any information obtained by the Contractor.

7. Warranty

- 7.1. In case the Contractor fails to undertake the repair works under Section 62.2.2 of the 2016 revised IRR, the Procuring Entity shall forfeit its performance security, subject its property(ies) to attachment or garnishment proceedings, and perpetually disqualify it from participating in any public bidding. All payables of the GOP in his favor shall be offset to recover the costs.
- 7.2. The warranty against Structural Defects/Failures, except that occasioned-on force majeure, shall cover the period from the date of issuance of the Certificate of Final Acceptance by the Procuring Entity. Specific duration of the warranty is found in the SCC.

8. Liability of the Contractor

Subject to additional provisions, if any, set forth in the SCC, the Contractor's liability under this Contract shall be as provided by the laws of the Republic of the Philippines.

If the Contractor is a joint venture, all partners to the joint venture shall be jointly and severally liable to the Procuring Entity.

9. Termination for Other Causes

Contract termination shall be initiated in case it is determined *prima facie* by the Procuring Entity that the Contractor has engaged, before, or during the implementation of the contract, in unlawful deeds and behaviors relative to contract acquisition and implementation, such as, but not limited to corrupt, fraudulent, collusive, coercive, and obstructive practices as stated in ITB Clause 4.

10. Dayworks

Subject to the guidelines on Variation Order in Annex “E” of the 2016 revised IRR of RA No. 9184, and if applicable as indicated in the **SCC**, the Dayworks rates in the Contractor’s Bid shall be used for small additional amounts of work only when the Procuring Entity’s Representative has given written instructions in advance for additional work to be paid for in that way.

11. Program of Work

11.1. The Contractor shall submit to the Procuring Entity’s Representative for approval the said Program of Work showing the general methods, arrangements, order, and timing for all the activities in the Works. The submissions of the Program of Work are indicated in the **SCC**.

11.2. The Contractor shall submit to the Procuring Entity’s Representative for approval an updated Program of Work at intervals no longer than the period stated in the **SCC**. If the Contractor does not submit an updated Program of Work within this period, the Procuring Entity’s Representative may withhold the amount stated in the **SCC** from the next payment certificate and continue to withhold this amount until the next payment after the date on which the overdue Program of Work has been submitted.

12. Instructions, Inspections and Audits

The Contractor shall permit the GOP or the Procuring Entity to inspect the Contractor’s accounts and records relating to the performance of the Contractor and to have them audited by auditors of the GOP or the Procuring Entity, as may be required.

13. Advance Payment

The Procuring Entity shall, upon a written request of the Contractor which shall be submitted as a Contract document, make an advance payment to the Contractor in an amount not exceeding fifteen percent (15%) of the total contract price, to be made in lump sum, or at the most two installments according to a schedule specified in the **SCC**, subject to the requirements in Annex “E” of the 2016 revised IRR of RA No. 9184.

14. Progress Payments

The Contractor may submit a request for payment for Work accomplished. Such requests for payment shall be verified and certified by the Procuring Entity’s Representative/Project Engineer. Except as otherwise stipulated in the **SCC**, materials and equipment delivered on the site but not completely put in place shall not be included for payment.

15. Operating and Maintenance Manuals

15.1. If required, the Contractor will provide “as built” Drawings and/or operating and maintenance manuals as specified in the **SCC**.

- 15.2. If the Contractor does not provide the Drawings and/or manuals by the dates stated above, or they do not receive the Procuring Entity's Representative's approval, the Procuring Entity's Representative may withhold the amount stated in the **SCC** from payments due to the Contractor.

Section V. Special Conditions of Contract

Notes on the Special Conditions of Contract

Similar to the BDS, the clauses in this Section are intended to assist the Procuring Entity in providing contract-specific information in relation to corresponding clauses in the GCC found in Section IV.

The Special Conditions of Contract (SCC) complement the GCC, specifying contractual requirements linked to the special circumstances of the Procuring Entity, the Procuring Entity's country, the sector, and the Works procured. In preparing this Section, the following aspects should be checked:

- a. Information that complements provisions of the GCC must be incorporated.
- b. Amendments and/or supplements to provisions of the GCC as necessitated by the circumstances of the specific purchase, must also be incorporated.

However, no special condition which defeats or negates the general intent and purpose of the provisions of the GCC should be incorporated herein.

Special Conditions of Contract

GCC Clause	
2	Completion of work shall be within 510 calendar days.
4.1	The Procuring Entity shall give possession of all parts of the Site to the Contractor upon receipt of the Notice to Proceed.
6	The site investigation reports are: <i>[list here the required site investigation reports.]</i>
7.2	<p><i>[Select one, delete the other.]</i></p> <p><i>[In case of permanent structures, such as buildings of types 4 and 5 as classified under the National Building Code of the Philippines and other structures made of steel, iron, or concrete which comply with relevant structural codes (e.g., DPWH Standard Specifications), such as, but not limited to, steel/concrete bridges, flyovers, aircraft movement areas, ports, dams, tunnels, filtration and treatment plants, sewerage systems, power plants, transmission and communication towers, railway system, and other similar permanent structures:]</i> Fifteen (15) years.</p> <p><i>[In case of semi-permanent structures, such as buildings of types 1, 2, and 3 as classified under the National Building Code of the Philippines, concrete/asphalt roads, concrete river control, drainage, irrigation lined canals, river landing, deep wells, rock causeway, pedestrian overpass, and other similar semi-permanent structures:]</i> Five (5) years.</p> <p><i>[In case of other structures, such as bailey and wooden bridges, shallow wells, spring developments, and other similar structures:]</i> Two (2) years.</p>
10	Dayworks are applicable at the rate shown in the Contractor’s original Bid.
13	The amount of the advance payment is no more that fifteen percent (15%) of the Contract Price subject to approval by the HOPE and compliance with the conditions under RA 9184 and its IRR.
14	No further instructions.
15.1	<p>The date by which operating and maintenance manuals are required is <i>thirty (30) days</i></p> <p>The date by which “as built” drawings are required as part of final payment</p>
15.2	The amount to be withheld for failing to produce “as built” drawings and/or operating and maintenance manuals by the date required is ten (10%) percent of the contract price.

Section VI. Specifications

Notes on Specifications

A set of precise and clear specifications is a prerequisite for Bidders to respond realistically and competitively to the requirements of the Procuring Entity without qualifying or conditioning their Bids. In the context of international competitive bidding, the specifications must be drafted to permit the widest possible competition and, at the same time, present a clear statement of the required standards of workmanship, materials, and performance of the goods and services to be procured. Only if this is done will the objectives of economy, efficiency, and fairness in procurement be realized, responsiveness of Bids be ensured, and the subsequent task of bid evaluation facilitated. The specifications should require that all goods and materials to be incorporated in the Works be new, unused, of the most recent or current models, and incorporate all recent improvements in design and materials unless provided otherwise in the Contract.

Samples of specifications from previous similar projects are useful in this respect. The use of metric units is mandatory. Most specifications are normally written specially by the Procuring Entity or its representative to suit the Works at hand. There is no standard set of Specifications for universal application in all sectors in all regions, but there are established principles and practices, which are reflected in these PBDs.

There are considerable advantages in standardizing General Specifications for repetitive Works in recognized public sectors, such as highways, ports, railways, urban housing, irrigation, and water supply, in the same country or region where similar conditions prevail. The General Specifications should cover all classes of workmanship, materials, and equipment commonly involved in construction, although not necessarily to be used in a particular Works Contract. Deletions or addenda should then adapt the General Specifications to the particular Works.

Care must be taken in drafting specifications to ensure that they are not restrictive. In the specification of standards for goods, materials, and workmanship, recognized international standards should be used as much as possible. Where other particular standards are used, whether national standards or other standards, the specifications should state that goods, materials, and workmanship that meet other authoritative standards, and which ensure substantially equal or higher quality than the standards mentioned, will also be acceptable. The following clause may be inserted in the SCC.

Sample Clause: Equivalency of Standards and Codes

Wherever reference is made in the Contract to specific standards and codes to be met by the goods and materials to be furnished, and work performed or tested, the provisions of the latest current edition or revision of the relevant standards and codes in effect shall apply, unless otherwise expressly stated in the Contract. Where such standards and codes are national, or relate to a particular country or region, other authoritative standards that ensure a substantially equal or higher quality than the standards and codes specified will be accepted

subject to the Procuring Entity's Representative's prior review and written consent. Differences between the standards specified and the proposed alternative standards shall be fully described in writing by the Contractor and submitted to the Procuring Entity's Representative at least twenty-eight (28) days prior to the date when the Contractor desires the Procuring Entity's Representative's consent. In the event the Procuring Entity's Representative determines that such proposed deviations do not ensure substantially equal or higher quality, the Contractor shall comply with the standards specified in the documents.

These notes are intended only as information for the Procuring Entity or the person drafting the Bidding Documents. They should not be included in the final Bidding Documents.



Republic of the Philippines
Quezon City
Office of the City Mayor
QUEZON CITY BIDS & AWARDS COMMITTEE
(QC-BAC-INFRA)



PROJECT : PROPOSED CONSTRUCTION OF HOUSING 32 - BALINGASA HIGH RISE HOUSING (PHASE 1A) AT BRGY. BALINGASA ✓

LOCATION : Barangay Balingasa, Quezon City ✓

SUBJECT : GENERAL CONDITIONS AND TECHNICAL SPECIFICATIONS

I. GENERAL CONDITIONS

1.0 DEFINITIONS

- a. OWNER :** LOCAL GOVERNMENT OF QUEZON CITY
- b. CONTRACTOR :** Any individual, firm, corporation, partnership or association that enters into an agreement with the Owner for furnishing the materials and/or labor, tools, equipment, plant and other facilities required for the erection and completion of the project subject to the accompanying plans and working drawings.
- c.** The Owner/Implementing Agency and the Contractor are treated through the contract documents as if each were of the regular number, masculine gender

1.1 EXAMINATION OF MEMBER

The Contractor shall carefully examine the premises before submitting any bids to enable him to have full knowledge of conditions existing therein

1.2 LOCATION

The Proposed Construction of Housing no. 33 (Baesa) shall be built along Barangay Baesa , Quezon City. refer to the approved Location Plan.

1.3 EXECUTION, CORRELATION & INTENT OF DOCUMENTS

- a.** The Contract Documents are signed in sufficient number of copies by all parties concerned. In case anybody fails to sign copies of any item forming part of the set contract documents, the Implementing Agency's identification thereon shall suffice.
- b.** The items, specifications and all other documents forming the contract documents are complementary. Anything shown on plans but not mentioned in the specifications or vice versa or anything not expressly set forth in either, but necessarily implied, shall be furnished or done as if specifically shown and mentioned in both, with no extra charge. Where dimensions are given in figures, follow them in preference to measurement by scale.
- c.** Execute work as per agreement, making no changes or deviations whatsoever, without prior permission from the Implementing Agency.
- d.** The Contractor shall verify and check all dimensions particularly those on the plans. He will be held directly responsible in case of any discrepancy that may be discovered during the progress of work.

1.4 DETAIL DRAWINGS AND INSTRUCTIONS

Plans furnished for use at the jobsite are whenever necessary, supplemented by detail drawings and instructions essential to the proper execution of the work. Such supplementary detail drawings and instructions shall be treated as of equal force as though originally issued

1.5 PLANS AND PROJECT SITE

Keep at project site, in good order and condition, one (1) set of approved plans, specifications, supplementary detail drawings and instructions.

1.6 SHOP DRAWINGS

Shop drawings shall be provided by the Implementing Agency and/or Contractor during the progress of construction. The contractor should not place any item subject to shop drawings until the Implementing Agency shall have duly approved such drawings.

1.7 CHANGES

The Owner and the Implementing Agency reserve the right to make alterations or additions, including changes during the progress of work. The same shall be carried into effect without in any way deviating from or violating any agreement. Whatever amount shall necessarily be entailed in the cost of labor or materials or both shall be added to or deducted from the original contract price.

1.8 TIME OF COMPLETION AND SCHEDULE OF CONSTRUCTION

The Contractor shall, before actual commencement of the project operations prepare and submit to the Implementing Agency for verification and approval, a complete and comprehensive work schedule covering the entire duration of construction. He shall also include therein, the estimated number of days within which the entire project shall be completed stage by stage by phase.

1.9 WORKMANSHIP

The project shall be executed with the use of first class workmanship to the full intent and meaning of the plans and specifications and to the complete approval and acceptance by the Implementing Agency.

1.10 MATERIALS

All materials to be used shall be the best of their respective types and kind. They shall be properly stored and protected from damage or injury.

1.11 SAMPLES

Submit samples as specified and proceed with the work with the use of materials procured based on the samples previously approved by the Implementing Agency.

1.12 INSPECTION OF WORK

The Contractor shall provide the facility for inspecting the work to the Implementing Agency, the Owner and other personnel having jurisdiction over the work.

1.13 DEFECTIVE OR IMPROPER WORK

All work or materials not acceptable to the Architect shall be removed immediately and replaced with appropriate work or materials without extra charge. All condemned materials shall be taken away from the premises without delay.

1.14 BUILDING LAWS AND REGULATIONS

The Contractor shall be held responsible for strict compliance with existing labor laws and regulations and shall free the Owner from any responsibility in connection therewith, he shall pay on time at his own expense, all taxes, fees and/or licenses due to the government, both national and local arising from his work on the project.

1.15 MANNER OF PAYMENT

Payments to the Contractor shall be based on the periodic work accomplishments subject to verification, approval and recommendation by the Implementing Agency.

1.16 RETENTION MONEY

Progress payments shall be subject to a ten percent (10%) deduction, referred to as retention money. All retained amounts shall be released upon satisfactory completion of the work and issuance of the Certificate of Final Completion and Acceptance.

1.17 TEMPORARY WATER, POWER AND TELEPHONE FACILITIES

The Contractor shall make the necessary arrangements with the local utility companies so as to provide temporary facilities for the supply of water, power and telephone for the duration of construction, and all expenses in connection therewith shall be borne by the Contractor.

1.18 PRIVY

The Contractor shall provide a temporary privy in a most inconspicuous and sanitary manner, and shall have it removed at the termination of the work.

1.19 CLEARING AND CLEANING

Upon its completion, the project and its premises shall be cleared and cleaned as directed by the Implementing Agency, and made ready for immediate occupancy.

1.20 TEMPORARY BARRICADES, SIGNAL LIGHTS, BILLBOARDS, ETC.

The Contractor shall provide all temporary barricades, signal lights, Architect and Contractor's billboards, the required official building billboard, etc., necessary for the protection of the public and for the proper prosecution of the work and display of construction requirements.

1.21 PERFORMANCE AND GUARANTEE BOND

To guarantee the faithful performance of the Contractor under the contract he shall post a Performance Bond in the amount of thirty percent (30%) of the contract price in the form of cash, manager's check or surety bond, callable on demand.

1.22 QUESTIONS AND DISAGREEMENTS

All questions and disagreements between the Contractor and the Owner relative to the interpretation of the plans and specifications shall be referred to the Implementing Agency whose decision on the matter shall be final.

II. TECHNICAL SPECIFICATIONS

2.0 SITE WORK

WORK INCLUDED

- 2.0.1 Staking out and establishment of additional wall lines, grades and benchmarks.
- 2.0.2 All excavation works including all necessary shoring, bracing and drainage of storm water from the site.
- 2.0.3 All soil treatment, backfilling, filling, compaction and grading, removal of excess material from site.
- 2.0.4 Protection of property, work and structures, workmen and other people from damage and injury.
- 2.0.5 Soil Poisoning / Termite Proofing.
- 2.0.6 Gravel Bedding and Compaction (Ordinary Gravel).
- 2.0.7 Backfill and compaction.

- 2.0.8 Haul and disposal of excess materials
- 2.0.9 Demolition works

2.1 LINES, GRADES AND BENCHMARKS

- 2.1.1 Stake out accurately the lines of the building and/or the other structures included in the contract, and establish grades therefore, after which secure approval of the Project Manager before any excavation work is commenced.
- 2.1.2 Erect basic batter boards and basic reference marks at such places where they will not be disturbed during the construction of the foundation.

2.2 EXCAVATION

Structural Excavations: Excavations shall be to the depths indicated in the drawings where bearing value as indicated in the Soils Investigation Report provided as part of the Construction Documents shall be attained. Excavations for footings and foundations carried below required depths shall be filled with lean concrete and bottom of such shall be level. All structural excavations shall extend a sufficient distance from the walls and footings to allow for proper erection and dismantling of forms, for installation of service and for inspection.

All excavations shall be inspected and approved before pouring any concrete laying underground utility and auxiliary lines for placing select fill materials. The Contractor shall control the grading in the vicinity of all excavated areas to prevent surface drainage running into excavations. Water that accumulates in excavated areas shall be removed by pumping before fill is placed herein.

2.3 SOIL TREATMENT

Treat soil with 2% Chlordane or Aldrex solution in water to provide an unbroken horizontal and vertical chemical barrier between the proposed structure and the possible territe colonies in the soil after excavation is completed and prior to pouring of concrete foundation and ground floor slabs. At the time the soil treatment is to be applied, the soil shall be in a friable condition with a sufficient low moisture content to allow uniform distribution of the treatment solution throughout the soil.

Do not apply pesticide during or immediately after heavy rains, or whenever climatic conditions are such that runoff will occur to create an environmental hazard. Cover treated areas with polyethylene or waterproof sheeting if concrete is not poured on the same day as the soil treatment. Take adequate precautions to prevent disturbance of the pesticide barrier. Re-treat the soil or fill is disturbed after the treatment and before the placement of structural components. Apply pesticide prior to placement of vapor barrier or waterproofing membrane.

2.4 SHORING

Excavation shall be shored and braced by members of suitable sizes where necessary to prevent danger to persons, injurious caving or erosions. Shoring bracing and sheathing shall be removed, as the excavations are backfilled, in a manner such as to prevent injurious caving. The contractor shall keep all excavations free from water while construction is in progress.

2.5 FILLING AND BACKFILLING

After forms have been removed and when concrete work is hard enough to resist pressure resulting from fill, backfilling may then be done. Materials excavated may be used for backfilling. All filling shall be placed in layers not exceeding six (6) inches in thickness, each layer being thoroughly compacted and rammed by wetting, tamping, rolling.

2.6 PLACING AND COMPACTING FILL

- 2.6.1 Common Fill: shall be approved imported/site-excavated material free from roots, stumps and other perishable or objectionable matter.
- 2.6.2 Select Fill: shall be placed where indicated and shall consist of crushed gravel, crushed rock or a combination thereof. The material shall be free from adobe, vegetable matters and shall be thoroughly tamped after laying.

- 2.6.3 Before placing fill materials, the surface upon which it shall be placed shall be cleared of all brush, roots, vegetable matter and debris, and thoroughly wetted to ensure good bonding between grounds.
- 2.6.4 Compaction: Fills shall be evenly spread in horizontal layers of not more than 200mm in thickness. Each layer shall be wetted and compacted by approved mechanical compaction machine, roller or portable to a density of at least 90% or its maximum density for non-cohesive soils as determined by ASTM Method D-1557 or AASHTO Method T-180.

2.7 FINISH GRADING

The contractor shall fill and grade the whole area to the indicated sub-grade elevations as directed by the Architect or Engineer. The contractor shall verify the finish grade elevations of the proposed pavements. Prior to grading operations, the areas shall be cleared of all heavy growth or vegetation stumps, roots, cables, wires, rocks and other debris. The finished sub-grade shall be reasonably smooth and compacted and ready to receive the base course for the proposed pavement.

2.8 DISPOSAL OF EXCESS MATERIALS

Any excess and demolished materials remaining after completion of the earthwork shall be disposed of by hauling and transported out of the premises at the contractor's own expense.

2.9 SUB-GRADE PREPARATION

2.9.1 SCOPE

The sub-grade preparation shall be that part of the work which is the preparation for the support of the bases for pavements and structures. It shall extend to the full width of pavements including shoulders and lay-bys as shown on the drawings or as specified herein. Unless otherwise agreed upon by the Engineer, sub-grade preparation on a section of the road shall not be commenced unless the contractor is able, after the completion and acceptance of the work, to commence immediately pavement construction.

2.9.2 PRODUCTS

All materials and equipment necessary for proper completion of this work shall be subject to the approval of the Engineer.

2.9.3 EXECUTION

- 2.9.3.1 Prior Works: Prior to commencing the preparation of the sub-grade, all culverts, cross drains, and other similar structures (including the fully compacted backfill) shall be completed. No work shall be started on the preparation of the sub-grade before the prior works herein approved by the Engineer.
- 2.9.3.2 Sub-grade Level Tolerance: The finish compacted surface of the sub-grade shall conform to AASHTO M-145.
- 2.9.3.3 Sub-grade in Cutting Common Material
- a. Unless otherwise specified, all materials below sub-grade level in earth cutting to a depth of 150mm or other depth shown on the drawings or directed by the Engineer shall be excavated. The material, if suitable, shall be placed to one side for re-use, or if unsuitable, shall be disposed of in accordance with the requirements of AASHTO M-145.
 - b. Where material has been removed from below sub-grade level, the base of the resulting cutting shall be compacted to a depth of 150mm to the requirements of AASHTO M-145 Table 1. If necessary, the moisture content of the material shall be adjusted.

2.10 GRADED AGGREGATES AND BASE COURSE

2.10.1 SUBMITTALS

- a. Test Reports: Before delivery of materials, submit the following test reports.
 1. Gradation
 2. Bearing Ratio
 3. Atterberg Limits

2.10.2 DELIVERY AND STORAGE

Do not construct base course when rainfall or other weather conditions will detrimentally affect the quality of the finished course.

2.11 PRODUCTS

2.11.1 MATERIALS

- a. Aggregates: Consist of durable sound crushed gravel, crushed stone, free of lumps and balls of clay or other objectionable matter. Crushed stone shall be free from flat, soft or disintegrated pieces. Crushed gravel retained on a No. 4 sieve shall have at least ninety percent (90%) by weight with at least two fractured faces one hundred percent (100%) by weight with at least one fractured face.
- b. Base course materials samples shall have a Bearing Ratio of at least 100 as determined by laboratory tests on a 4-day soaked specimen in accordance with ASTM D 1557: compact specimen in accordance with ASTM D 1557, Method D. Determine grain size in accordance with ASTM C-117.
- c. Soil binder material, the surface of the layer by a combination of rolling and blading. Final surface shall be smooth and free from waves, irregularities and from ruts or soft yielding spots.

III CONCRETE

3.0 GENERAL

- 3.0.1 Unless otherwise specified herein, concrete work shall conform to the requirements of ACI Building Code. Full cooperation shall be given other trades to install embedded items. Provisions shall be made for setting items not placed in the forms. Before concrete is placed, embedded items shall have been inspected and tested for concrete aggregates and other materials shall have been done.

3.1 SUBMITTALS

- 3.1.1 Shop Drawings. Reproduction of contract drawings is unacceptable.
- 3.1.2 Shop Drawings for Reinforcing Steel: ACI 318. Indicate bending diagrams, assembly diagrams, splicing and lap of bars, shapes, Dimensions and details of bar reinforcing, accessories and concrete cover. Do not scale dimensions from structural drawings to determine lengths of reinforcing bars.
- 3.1.3 Contractor Mix Design. Thirty (30) days prior to concrete placement, submit a design for each strength and type of concrete. Furnish a complete list of materials including type, brand, source and amount of cement and admixtures; applicable reference specifications and copies of test reports showing that the mix has been successfully tested to produce concrete with the properties specified and will be suitable for the job conditions. Provide fly ash and pozzolan test results performed within six (6) months of submittal date. Obtain approval before concrete placement.

- 3.1.4 Certificates of Compliance
 - a. Aggregates
 - b. Admixtures
 - c. Reinforcement
 - d. Cement
- 3.1.5 Catalogue Data
 - a. Water stops
 - b. Materials for Curing Concrete
 - c. Joint Sealant
 - d. Joint Filler
 - e. Vapor Barrier
 - f. Epoxy Bonding Agents

3.2 MATERIALS

- 3.2.1 Cement for concrete shall conform to the requirements of specifications for Portland cement (ASTM C-150).
- 3.2.2 Water used in mixing concrete shall be clean and free from other injurious amounts of oil, acids, alkaline, organic materials or other substances that may be deleterious to concrete or steel.
- 3.2.3 Fine Aggregates shall consist of hard, tough, durable uncoated particles. The shape of the particles shall be generally rounded or cubicle and reasonably free from flat or elongated particles. The stipulated percentages of fines in the sand shall be obtained either by processing sand or by the production of suitable graded manufactured sand.
- 3.2.4 Coarse Aggregates shall consist of gravel, Crushed gravel or rock. Or a combination of gravel and rock. Coarse aggregates shall consist of hard, tough, durable, clean and uncoated particles. The size of coarse aggregates to be used in the various parts of the Work shall be ¾".
- 3.2.5 Reinforcing bars shall conform to the requirements of ASTM Standard specifications for Billet Steel Bars for concrete reinforcement (A15-625) and to Specification for minimum requirements for the deformed steel bars for concrete reinforcement (A305-56). Tensile strength and grade for all reinforcing bars such as main horizontal (for beams), vertical (for columns), ties, stirrups and inserts shall be as follows:

Grade 40 - 12 mmØ and smaller - $f_y = 275$ Mpa

Grade 60 - 16 mmØ to 25mmØ - $f_y = 415$ Mpa

3.3 PROPORTIONING AND MIXING

- 3.3.1 Proportioning of all materials entering into the concrete mixture of 3,000 psi concrete shall be as follows:

<u>Class</u>	<u>Cement</u>	<u>Sand</u>	<u>Gravel</u>
A	1	2.0	4
- 3.3.2 Proportioning of all materials entering into the concrete mixture of 4,000 psi concrete shall be as follows:

<u>Class</u>	<u>Cement</u>	<u>Sand</u>	<u>Gravel</u>
A	1	2.0	3
- 3.3.3 Strength of Concrete: Concrete shall have 28-day cylinder strength of 3,000 psi shall be for slab on grade, Main stairs, Fire exit stairs, Wall footing, Ramp, Canopy, Septic tank, Cistern tank, Fire Reserve tank, MRF, Handhole for electrical, Concrete encasement and Entrance steps
- 3.3.4 Strength of Concrete: Concrete shall have 28-day cylinder strength of 4,000 psi shall be for Columns, Beams, Suspended slabs, Footings and Elevator shaft wall,
- 3.3.5 Mixing: Concrete of 4,000 psi compressive strength shall be ready-mixed in transit from batching plant as scheduled order from qualified supplier. The 3,000 psi

concrete can be machine mixed on-site or also ~~may~~ mixed in transit from batching plant. On-site mixing shall be within 30 minutes after the cement has been added to the aggregates.

3.4 FORMS

- 3.4.1 General: Forms shall be used whenever necessary to contain the concrete and shape it to the required lines, or to ensure the concrete contamination with materials coming from adjacent excavated surfaces. Forms shall have sufficient strength to withstand the pressure resulting from placement and vibration of the concrete, and shall be maintained rigidly in correct position. Forms shall be sufficiently tight to prevent loss of mortar from the concrete. Forms for exposed surfaces against which backfill is not to be placed shall be lined with a form grade plywood or metal panels.
- 3.4.2 Cleaning and Use of Forms: Before placing the concrete, the contact surfaces of the form shall be cleansed of encrustation of mortar, the grout or other foreign material, and shall be coated with commercial form oil that will prevent sticking and will not stain the concrete surfaces.
- 3.4.3 Removal of Forms: Forms shall be removed in a manner that will prevent damage to the concrete. Forms shall not be removed without approval. Any repairs of surface imperfections shall be performed at once and work shall be started as soon as the surface is sufficiently hard to permit it without further damage.

3.5 PLACING REINFORCEMENT

General: Steel reinforcement shall be provided as indicated, together with all necessary gauge 18 G I wire ties, chairs, spacers, supports and other devices necessary to install and secure the reinforcement properly. All reinforcement, when placed, shall be free from rust, flaky rust and scale, oil grease, clay and other coating and foreign substances that would reduce or destroy its bond with concrete. Reinforcement shall be placed accurately and secured in place by use of metal or concrete supports, spacers and ties. Such supports shall be of sufficient strength to maintain the operation. The supports shall be used in such manner that they will not be exposed or contribute in any way, to the discoloration or deterioration of the concrete.

3.6 CONVEYING AND PLACING CONCRETE

- 3.6.1 Conveying: Concrete shall be conveyed from mixer to forms as rapidly as practicable, by methods that will prevent segregation, or loss of ingredients. There will be no vertical drop greater than 1.5 meters except where suitable equipment is provided to prevent segregation and where specifically authorized.
- 3.6.2 Placing: Concrete shall be worked readily into the corners and angles of forms and around all reinforcement and embedded items without permitting the material to segregate. Concrete shall be deposited as close as possible to its final position in the forms so that flow within the mass does not exceed two (2) meters and consequent segregation is reduced to a minimum near forms or embedded items, or elsewhere as directed. The discharge shall be so controlled that the concrete may be effectively compacted into horizontal layers not exceeding 30 centimeters in depth within the maximum lateral movement specified.
- 3.6.3 Time interval between mixing and placing: Concrete shall be placed before initial set has occurred and before it has lost its water content for more than 45 minutes.
- 3.6.4 Consolidation of concrete: Concrete shall be consolidated with the aid of mechanical vibrating equipment and supplemented by hand spading and tamping. Vibrators shall not be inserted into lower courses that have commenced initial set and reinforcement embedded in concrete beginning to set or already set shall not be disturbed by vibrators. Consolidation around major embedded parts shall be by hand spading and tamping and vibrators shall not be used.
- 3.6.5 Placing concrete through reinforcement: In placing concrete through reinforcement, care shall be taken that no segregation of the coarse aggregate occurs. On the bottom of beams and slabs, where the congestion of steel near the forms makes placing difficult, a layer of mortar of the same cement-sand ratio as used in concrete shall be first deposited to cover the surface.

3.7 CURING

- 3.7.1 General: All concrete shall be moist-cured for a period not less than seven (7) consecutive days by an approved method or combination applicable to local conditions.
- 3.7.2 Moist curing: The surface of the concrete shall be kept continuously wet by covering with burlap, plastic or other approved materials thoroughly saturated with water and keeping the covering wet spraying or intermittent hosing.

3.8 FINISHING

- 3.8.1 Concrete surfaces shall not be plastered unless otherwise indicated. Exposed concrete surfaces shall be formed with smooth form material, and after removal of forms, the surfaces shall be smooth, true to line and shall present a finished appearance except for minor defects which can be easily repaired by patching with current mortar, or can be ground to a smooth surface to remove all joint marks of the form work.
- 3.8.2 Concrete slabs on fill: The concrete slabs on fill laid on a prepared foundation consisting of sub-grade and granular fill with thickness equal to the thickness of overlying slab except as indicated otherwise.

3.9 SURFACE FINISHES

- 3.9.1 Defects: Repair formed surfaces by removing minor honeycombs, pits greater than one square inch surface area or 0.25 inch maximum depth, or otherwise defective areas. Provide edges perpendicular to the surface and patch with non-shrink leg-put. Patch the holes and defects when the forms are removed.
- 3.9.2 Floor slabs, Pavements and Miscellaneous Construction: Unless otherwise specified, slab at the fountain area are straight to finish with waterproofing. Slope floors uniformly to drains where drains are provided. Depress the concrete base slab where Granite or Ceramic tiles are indicated.
- 3.9.3 Finish: Place, consolidate and immediately strike-off concrete to obtain proper contour, grade and elevation. A set sufficient for floating and supporting the weight of the finisher and equipment.

3.10 MISCELLANEOUS

- 3.10.1 Construction Joints: Locate joints to least impair strength; continue reinforcement across joints unless otherwise indicated.
- 3.10.2 Expansion Joints and Contraction Joints: For slab on grade, provide at edges of interior floor slab, adjacent to walls as indicated. Completely fill joints exposed to weather with joint filler material and joint sealant. Do not extend reinforcement or other embedded metal items bonded to the concrete through any expansion joints unless an expansion sleeve is used. Provide contraction joints, either formed or saw cut or cut with a jointing tool, to the indicated depth after the surface has been finished. Sawed joints shall be completed within 4 to 12 hours after concrete placement. Protect joints from intrusion of foreign matter.

4.0 METALS WORKS

4.0.1 DESCRIPTION

- 4.0.1.1 Metal works shall conform to the approved plans and to the Standard Specifications.

4.0.2 REFERENCE STANDARDS

- 4.0.2.1 Comply with the latest edition of the following as applicable, unless otherwise specified or modified.

- 2.1.1 AMERICAN INSTITUTE OF STEEL CONSTRUCTION (AISC), 1978: Specification for the Design, Fabrication and Erection of Structural Steel for Buildings. Code of Standard Practice for Steel Buildings and Bridges; Specification for Architecturally Exposed Structural Steel.
- 4.0.2.1.2 AMERICAN WELDING SOCIETY (AWS): Standard Welding Symbols A2.0-68; Standard Welding Code D1.1-1973 (Rev 1-73 & 2-74) (To govern if in conflict with AISC).
- 4.0.2.1.3 RESEARCH COUNCIL ON RIVETED AND BOLTED JOINTS OF THE ENGINEERING FOUNDATION (RCRBJ): Specification for Structural Joints using ASTM A-325-76s Bolts
- 4.0.2.1.4 STRUCTURAL STEEL PAINTING COUNCIL (SSPC): Painting Manual, Vol. 1; Good Painting Practice. Painting Manual, Vol. 2, Systems and Specifications

4.0.3 SOURCE QUALITY CONTROL

Errors of Shop Drawings, fabrication, correct fitting and alignment of the various metal items or component members shall be the responsibility of the Contractor. However, the Contractor shall permit the Architect or an independent inspection agency, if engaged by the Owner, to inspect work in progress in his shop. Such inspections shall not relieve the Contractor of his responsibility to furnish materials and workmanship in accordance with the Contract Documents.

4.0.4 PRODUCT DELIVERY, HANDLING AND STORAGE

Handle and store in such manner as to prevent damage or disfigurement. Store finished items or components above ground on platforms, pallets or other supports and protect from harmful elements.

4.0.5 PROTECTION

The Contractor shall protect any existing work subject to damage during the installation of the specified work and shall adequately protect specified work during installation.

4.0.6 FIELD QUALITY CONTROL

Facilities shall be provided by the Contractor as needed for the proper inspection of the specified work, including temporary platforms, hoists, protective devices, electric current, etc. Improper workmanship, as determined by the Architect shall be corrected and replaced, at no additional cost to the Owner.

4.0.7 MATERIALS

Products shall conform to the respective reference specifications and standards and to the requirements specified herein:

4.0.7.1 STEEL AND IRON: If not specified otherwise, use standard mill-finished structural steel shapes or bar iron in compliance with AISC Specifications for Design, Fabrication and Erection of Structural Steel for Buildings.

4.0.7.2 BOLTS, NUTS, STUDS AND RIVETS: ASTM A 325

4.0.7.3 SCREWS: Fed. Spec. FF-S-65, Fed. Spec. FF-S-62, and Fed. Spec. FF-S-111

4.0.8 FABRICATION

By mechanics skilled in the trade and in accordance with the manufacturer's directions. Metalwork shall be fabricated to allow for expansion and contraction of materials. Provide welding and bracing of adequate strength and durability, with tight, flush joints, dressed smooth and clean. Complete with bolts and nuts.

4.0.9 MEASUREMENTS

Before fabrication, provide necessary field measurements and verify all measurements.

4.0.10 METAL SURFACES

Shall be clean and free from all scale, flake, rust and rust pitting; well-formed and finished to shape and size, with sharp lines, angles and smooth surface. Shearing and punching shall leave clean true lines and surfaces. Weld or rivet permanent connections. Weld and flush rivets shall be used and finished flush smooth on surfaces that will be exposed after installation. Do not use screws or bolts where they can be avoided; when used, heads shall be countersunk, screwed up tight and threads nicked to prevent loosening.

4.0.11 CONSTRUCTION

Thickness of metals and details of assembly and supports shall give ample strength and stiffness for the minimum loads specified or indicated. Joints exposed to weather shall be formed to exclude water.

4.0.12 SHOP FABRICATION

Fabrication and assembly shall be done in the shop to the greatest extent possible

4.0.13 SUBMITTALS

Shop Drawings: Submit along with catalogue, cuts, templates, and erection and installation details, indicating thickness, type, grade, class of metal and dimensions. Show construction details, reinforcement, anchorage, and installation with relation to the construction.

4.0.14 QUALIFICATION OF WELDERS

In accordance with AWS D1.1 using procedures, materials and equipment of the type required for the work.

4.0.15 DELIVERY AND STORAGE

Protect from corrosion, deformation and other types of damage. Store items in an enclosed area free from contact with soil and weather. Contractor shall replace and remove damaged items with new items.

4.0.16 WELDING

Use welding electrode E70xx and perform welding, welding inspection and corrective welding in accordance with AWS D1.1 Weld in a manner to prevent permanent distortion of the connected parts. Weld continuously along the entire area of contact (except where tack welding is permitted. Do not tack weld exposed to connections.) Grind smooth visible weld in finished installation.

4.1 METAL PURLINS

Metal purlins shall be of high grade galvanized steel with minimum tensile strength of 275 MPa, 2mm in thickness

V MASONRY

6.0 MATERIALS

- 5.0.0 All materials and workmanship shall be in accordance with the applicable standard and specifications of the Structural Code of the Philippines and uniform Building Code.

- 5.0.1 Concrete Hollow Blocks (CHB) shall have a minimum face thickness of 1" (25mm). Nominal size shall be 4' x 8' x 16', minimum compressive strength shall be 500 psi for non-load bearing and 700-1000 psi for load bearing. All units shall be stored for a period not less than 28 days (including curing period) and shall not be delivered to the job site prior to that time unless the structure is equal or more than the specified.
- 5.0.2 Prior to commencing the preparation of the sub-grade, all culverts, cross drains, and other similar structures (including the fully compacted backfill) shall be completed. No work shall be started on the preparation of the sub-grade before the prior works herein approved by the Engineer.
- 5.0.3 Cement shall be standard Portland cement ASTM 270 - Type N.
- 5.0.4 Mortar. Mix mortar from 3 to 5 minutes in such quantities as needed for immediate use. Re-tempering will not be permitted if mortar stiffens because of premature setting. Discard such materials as well as those that have not been used within one hour after mixing. Proportioning shall be one (1) part Portland cement and two (2) parts sand by volume, but not more than one (1) Portland cement and three (3) parts sand by volume.

5.1 SUBMITTALS

- 5.1.0 Submit samples for approval two (2) samples each of each type of wall reinforcement and wall ties.
- 5.1.1 Certificates of Conformance. Submit certificate attesting that masonry cement, masonry units, aggregates and accessories meet the requirements specified.

5.2 ERECTION

- 5.2.0 All masonry shall be laid plumb, true to line, with level and accurately spaced courses, and with each course breaking joint with the course below. Bond shall be kept throughout corners and reveals shall be plumb and true. Units with greater than 12% absorption shall be wet before laying. Work required to be built in masonry, including anchors, wall plugs and accessories shall be built-in as the erection progresses.
- 5.2.1 Masonry Units: Each course shall be solidly bedded in Portland cement mortar. All units shall be damp when laid units shall be showed into place not laid, in a full bed of un-furrowed mortar. All horizontal and vertical points shall be completely filled with mortar when and as laid. Each course shall be bonded at corners and intersections. No cells shall be left open on face surfaces. All cells shall be filled up with mortar for exterior walls. Units terminating against beam or slab soffits shall be wedged tight with mortar. Do not lay cracked, broken or defaced block.
- 5.2.2 Plastering: Clean and evenly wet surfaces. Apply scratch coat with sufficient force to form good keys. Cross scratch coat upon its initial set; keep damp. Apply coat after each scratch coat has set at least 24 hours after scratch coat application. Lightly scratch brown coat; keep moist for two (2) days; allow drying out. Do not apply finish until brown coat has seasoned for seven (7) days. Just before applying coat, wet brown coat again. Float finish coat to true even surface; trowel in manner that will force sand particles down into plaster, with final troweling, leave surfaces finished smooth free from rough areas, trowel marks, checks, other blemishes. Keep finish coat moist for at least two (2) days; thereafter protect against rapid drying until properly, thoroughly cured.

5.3 SCAFFOLDING

- 5.3.0 Provide safe wood or metal scaffolding required for masonry and other related work, including cleaning down on completion. Remove upon demobilization.

5.4 SURFACE PREPARATION

- 5.4.0 Lay floors without borders from centerline outward. Make adjustments at walls. Clean concrete sub-floor and moisten it without soaking. Sprinkle dry cement over surface. Spread setting bed mortar on concrete and tamp to assure good bond over the entire area then screed to smooth, level bed. Set average setting bed thickness at $\frac{1}{2}$ " but not less than $\frac{1}{4}$ ".
- 5.4.1 Wall: Scratch coat application as foundation coat shall be at most $\frac{1}{2}$ ". While still plastic, deeply score scratch coat or scratch and cross-scratch. Protect scratch coat and keep reasonably moist within seasoning period. Use mortar for scratch floor coats, within one hour after mixing. Re-tempering of partially hardened mortar is not permitted. Set scratch coat be cured for at least two (2) days before starting the setting.

5.5 CLEANING

- 5.5.0 Protection: Protect work which may be damaged, stained or discolored during cleaning operations.
- 5.5.1 Pointing: Upon completion of masonry work, cut out defective mortar joints and tuck joints and all holes solidly with mortar.
- 5.5.2 Cleaning: Clean exposed masonry surface with clear water and stiff fiber brushes and rinse with clean water. Where stains, mortar or other soil remain, continue cleaning as follows: Clean masonry surfaces by scrubbing with warm water and soap and rinsing thoroughly with clean water. Restore damaged, stained and discolored work to its original conditions or replace with new work.

VI ARCHITECTURAL

6.0 FLOOR AND WALL AND FINISHES

6.0.0 Exterior/Interior Walls & Floor finishes

- a. 600mm x 600mm Homogenous Floor Tiles
- b. 300mm x 600mm Unglazed/ Non-skid Ceramic Tiles
- c. 25mm Concrete Topping with Plain cement straight to finish
- d. 25mm concrete topping (for tiles)
- e. 300mm x 600mm Porcelain Wall Tiles,
- f. 300mm x 300mm Ceramic Wall Tiles
- g. Plastering Guide/ Grooves
- h. Stone Cladding
- i. Green Wall
- j. 2000mm high x 10mm thk formica compact, post forming grade, high pressure phenolic laminate EN438 & ISO 4586 compliant toilet partition including stainless steel accessories.

6.0.1 CEILING FINISHES

- a. Rubbed Concrete
- b. 12mm thk. Moisture Resistant Gypsum Board including framing and accessories

6.0.2 ROOF WORKS

- a. Rib type Roofing Ga. 24, Pre-painted Longspan with Double Sided insulation and complete Accessories with Flashing
- b. Stainless Roof Gutter(Ga. 24) including framing and accessories

6.0.3 WINDOWS

Follow as per approved plan and specifications.

6.0.4 DOORS

Follow as per approved plan and specifications.

6.0.5 PAINTING

1. All paints shall meet the required specifications and shall be delivered at the site in the original container. Use non Volatile Organic Compound (V.O.C) paint or approved by the implementing agency and only accredited painters of the manufacturer shall execute the work to ensure the true origin and quality of paint and warranty of work.
2. Concrete walls shall be treated with neutralizers. Exterior walls without wall veneer shall be applied with a primer before final coat. In general, rough surfaces of concrete, cabinets and woodworks surfaces shall be properly sandpapered and buffed before any application of paint
 - a. Epoxy Paint Finish (steel members)
 - b. Latex Paint Finish (exterior masonry walls)
 - c. Latex Paint Finish (interior masonry walls, stairs and Slab Soffit)
 - d. Painting of Doors and jambs
 - e. Scaffolding (exterior painting)
 - f. Painting of Parking Area

6.0.6 WATERPROOFING AND DAMP-PROOFING

- | | | |
|---------------------|---|-----------------------------------|
| a. Capillary Type | : | Toilets, Canopy |
| b. Flexible Type | : | Decks, Balcony, Fire Reserve Tank |
| c. Epoxy Food Grade | : | Cistern Tank. |

6.0.7 HARDWARE

1. Provide all rough hardware required for the construction of works: nails, straps, lag screws, etc.
2. Butt Hinges : Use Butt Hinges, 4" x 4" with bearings for panel door
3. Locksets : For PVC plastic, wood and metal swing doors use stainless mortise locksets with striker plate.
4. Door Stop : Locate position where no traffic could be obstructed. For restroom doors where tile finish abuts the door swing side, use 6" above inside floor finish on door panel
5. Door Closers : Door closer for metal doors.
6. Exit Door Panel: Use Panic Exit Device, horizontal without key for Device single panel for fire exits

6.0.8 HANDRAILS AND RAILINGS

Follow as per approved plan and specifications.

6.0.9 OTHER FINISHES

- a. 6mm thk facial mirror on 8mm thk manne plywood backing including all incidentals to complete
- b. Countertop including Tiles
- c. Countertop including Tiles (Pantry)
- d. Undercountertop Cabinet including accessories, Painted Finish
- e. Undercounter Cabinet including accessories, Painted Finish
- f. Bathroom Accessories (Bidet, tissue and soap holder, towel hook)
- g. Concrete Wheel Stopper
- h. Green Area

6.0.10 CLEAN-UP

When the work is completed, the Contractor shall remove all temporary structures and surplus materials of every sort, restore what has been removed before, and leave the premises or site in as good condition as he had originally found them.

VII THERMAL CONTROL AND MOISTURE PROTECTION

7.0 WATERPROOFING

Use waterproofing cementitious powder, capillary type, flexible type-liquid applied waterproofing seamless membrane latex-modified rubber reinforced on slabs. Refer to manufacturer's recommendation on proper application of the product listed herein.

7.1 VAPOR BARRIER

Use 8 mils thick, 6 feet wide roll plastic vapor barrier laid over compacted base course at ground floor slab with 300mm minimum overlap prior to setting up of steel reinforcing bars. Submit samples for approval.

7.2 WATERSTOPS

Use chemical grout water-stop specially formulated for construction joints to replace the use of conventional water-stop used for cold expansion joints on pipes, etc.

VIII FIRE PROTECTION DRY-STANDPIPE SYSTEM

8.0 GENERAL

Applicable provisions of the "General Conditions" govern work under this section.

8.1 QUALIFICATIONS OF CONTRACTORS

- 8.1.0 The Contractor for the fire protection installation shall be a qualified Fire Protection Contractor, regularly engaged in the installation of Fire Protection and must have at least one (1) Fire Protection Installation approved by the Philippine Insurance Rating Association (PIRA). Companies or corporations whose personnel have supervised an approved sprinkler plan and subsequently approved by PIRA or by the Fire Department are also qualified.

8.2 SCOPE OF WORK

- 8.2.0 This specification includes the furnishing of all labor, materials, equipment and services necessary or incidental to the complete installation, testing, adjusting and placing into service of the several systems of fire protection, all as shown on the drawings and as hereinafter specified. Drawings and specifications are considered as mutually explanatory and all works called for by one and not the other, shall be performed as though called for by both. In cases of conflicting information, the Architect and Engineer shall be notified at once.

in writing. ~~The~~ incidental equipment or appurtenances are required and not listed as shown, same shall be furnished as required for a complete fire protection system

8.2.2 Drawings are intended to show general arrangement and approximate physical sizes of equipment diagrammatically. Every bolt, nut, brace, strut, etc., is not necessarily indicated or specified; all such items as may be required, necessary or incidental to the proper and dependable operation of each system being a requirement of this contract, whether specifically referred to or not, must be supplied.

8.2.3 Work included in this specification shall consist of, but not limited to the following items.

1. Arrange for, obtain and bear the cost of necessary permits, bonds and fees for the automatic sprinkler work.
2. All fees, private or government shall be paid by the Contractor.
3. Furnish and install a system of dry standpipe complete with valves and fire department connection. Contractor to provide as shown in the plans, by-pass valve with pipe and fittings to connect the Wet Sprinkler pipe riser with the Dry Standpipe riser.
4. Furnish and install fire department connection for the Standpipe System.
5. Do the testing of all piping works and necessary cleaning of the fire protection works.
6. All openings through which fire may spread from one floor to the other, such holes through floors or walls for the pipe shall be sealed with fire resistant materials.
7. Chipping and plastering works necessary for the area covered in the installation of automatic sprinkler system.
8. Furnish the shop drawings and certificates of inspection.
9. Periodically remove from the jobsite all rubbish and debris resulting from the fire protection work.
10. Miscellaneous items as hereinafter provided.

8.3 SITE CONDITIONS

The Contractor shall be deemed to have visited the site and acquaint himself with the existing site condition, means of access and take into account any feature that may affect his tender. No claim for his neglect to do so or not, out of a misunderstanding on his part in these conditions shall be entertained.

The Fire Protection Contractor shall be responsible for the proper coordination with other trade contractors.

8.4 STANDARDS, CODES AND REGULATIONS

The applicable current standards for the fire protection systems shall be the National Fire Protection Association (NFPA), NFPA-13, and Philippine Fire Code-PD 1185, the PSME Code and all other applicable local codes and ordinances

8.5 SUBMITTAL (SHOP) DRAWINGS AND DATA

8.5.1 Before commencing any work or providing any materials at the jobsite for this project, the Fire Protection Contractor shall submit to the Engineer for approval, four (4) copies of catalogue cuts and descriptive matter regarding materials and equipment which he intends to furnish and install

Shop drawings and data shall be submitted specifically for, but not limited to the following items. Valves, pipes, pipe hangers, hose valves and accessories, Fire

Departments connections, mechanical grooved coupling, pipe riser support and sleeves.

8.5.2 The Fire Protection Contractor shall not proceed with the installation of the work until he has received the Engineer's approval on his stamp drawings.

8.5.3 The Engineer's approval of shop drawings, catalogue cuts, etc. shall not relieve the Fire Protection Contractor of the responsibility for any errors or omissions which may exist in the items neither submitted nor shall relieve him from the responsibility for deviations from the contract drawings and specifications.

The stamped approval of the shop drawings, catalogue cuts, etc. shall not be construed as a complete check, but will indicate only that the general design and method of construction is satisfactory.

8.5.4 In the event inspection authorities require additional clarifying details, the details shall be prepared and approval of the same secured by the Fire Protection Contractor at his expense.

8.6 CONDUCT OF WORK

The Fire Protection Contractor shall employ on the job at all times a competent superintendent Licensed Mechanical Engineer who shall be responsible for the progress and execution of the work. Workmanship shall be of high quality, conforming to standard practice as stipulated by NFPA, ASTM and ASA and PSME recommendations by skilled workmen during regular working hours.

8.7 LOCAL AND IMPORTED MATERIALS

8.7.1 All materials furnished under this section shall be new, manufactured in the United States, and Non-UL/FM but conforming to NFPA Standards.

8.7.2 The proposal submitted shall include all materials and equipment as specified or shown on the drawings.

8.8 STANDPIPE SYSTEM

8.8.1 Pipe shall be new, designed for 175psi working pressure, conforming to ASTM specifications, manufactured in the United States or approved local pipes and have the manufacturer's name or brand along with the applicable ASTM standard marked on each length of the pipe. The locally manufactured pipe brand "Supreme" are acceptable brand with proper schedule and wall thickness.

8.8.2 Pipe shall be steel, schedule 40, black and in accordance with the specifications ASTM A120 or A53.

8.8.3 Schedule 40 black steel pipes shall be joined by screwed joints in accordance with specifications ANSI B2.1 up to 2 1/2" and flanged, Victaulic type or screwed connections for 3" and up. Pipe fittings to be used with schedule 80 pipes shall be rated 300lbs. Class if there are any.

8.8.4 All ASTM A53 and ASTM A120 pipe must be hydrostatic tested at the mill per ASTM standard.

8.8.5 Screwed fitting shall be malleable iron, 300 lbs and 150 lbs. class, black and in accordance with ANSI B16.3. "Victaulic" brand mechanical tee and elbow UL/FM fittings can also be used.

8.8.6 Flanged fittings shall be steel, short body, 150, black and in accordance with ANSI B16.1. Gaskets shall be full face of 1/8" minimum thickness red sheet rubber. Flange bolts shall be hexagon head machine bolts with semi-finished hexagon head nuts, cadmium-plated having dimension in accordance with ANSI B18.2.

8.8.7 Weld fittings shall be steel, standard weight, black and in accordance with ANSI B16.9, ANSI B16.25, ASTM A234, ANSI B16.5 or ANSI B16.11

- 8.8.8 Outside screw and yoke (O.S. & Y) gate valves shall be flanged, iron body, bronze mounted, 175 psi working pressure, with hand wheel turning counterclockwise to open. Valve shall be tested and listed by UL and/or FM.
- 8.8.9 Fire Department connection shall be 4" x 2 1/2" x 2 1/2" Siamese connection, brass body, brass chain and plugs, and brass escutcheon letter "AUTOMATIC SPRINKLER" for sprinkler system, and/or "STANDPIPE" for standpipe system. Inlet threading shall be National Standard, same as municipal fire department connection shall be tested and listed by UL and/or FM and 175 psi rating.
- 8.8.10 Fire Hose Valve (Dry Standpipe) shall be angle type, 2 1/2" female iron pipe threads by 2 1/2" male NST hose threads, chromium plated with chromium plated cap and chain. Valve hose threads shall be National Standard same as municipal fire department. Valve shall be tested and listed by UL and/or FM and 175 psi rating.

8.9 STANDPIPE SYSTEM

- 8.9.1 The interior surfaces of all piping and equipment shall be clean and free of all dirt, loose scale, rust and other foreign materials before installation.
- 8.9.2 Pipe ends shall be reamed to remove all burrs and pipe sections shall be cleaned inside to remove all chips and foreign materials prior to making up joints. Approved joint compound shall be applied to the threads of the pipe and not in the fitting when making up joints. Pipe shall not exceed into the waterway of the fitting.
- 8.9.3 When welding pipe on jobsite, the fire hazard of the welding process shall be with suitable safeguards. Weld in place of pipe and fittings shall not be allowed at the jobsite. Only shop weld fabrication will be permitted with factory made fittings. Mitered weld will not be permitted. Intersection of feed main and cross main pipe shall be provided with flanged or Victaulic type fittings.
- 8.9.4 Pipe passing through the building walls and floors above grade shall be provided with sleeves of standard weight galvanized steel pipe and shall be installed prior to concreting works of the Civil Contractor. The annular spaces between pipe and sleeves shall be packed tight with insulation fire resistant materials. Provide chrome plated escutcheon plates enough to cover the pipe sleeves. Sleeves shall be sized as follows:

1"	pipe-2"	ID Sleeve
1 1/4"	pipe-2"	ID Sleeve
1 1/2"	pipe-2 1/2"	ID Sleeve
2"	pipe-3"	ID Sleeve
2 1/2"	pipe-4"	ID Sleeve
3"	pipe-5"	ID Sleeve
4"	pipe-6"	ID Sleeve
6"	pipe-8"	ID Sleeve
8"	pipe-10"	ID Sleeve

8.10 PIPE SUPPORTS

- 8.10.1 All piping shall be supported by means of hangers of approved quality, capable of supporting load. Sizing, spacing and installation shall be in accordance with national Fire Protection Association Standard No. 13, except as otherwise shown on drawings or specified herein.

- 8.10.2 The Fire Protection Contractor shall furnish and install the required sprinkler pipe seismic sway bracing for the risers, feed main pipe and cross main pipe all in accordance with tables and figures shown NFPA-13 requirements for the protection of the piping against breakage due to seismic earthquake movement.
- 8.10.3 No cutting, drilling, welding or burning of any structural steel member shall be allowed. Power driven studs and welding studs shall not be allowed.
- 8.10.4 All bolts and threaded rods shall be used with double nut and washer and lock washer wherever a single unsecured nut could work loose and allow either threaded rod or supported piping to drop.

8.11 TESTS AND INSPECTIONS

- 8.11.1 The Fire Protection Contractor shall conduct and bear the costs of all necessary tests of the fire protection work, furnishing all labor, power and equipment. All piping shall be tested with water and test witnessed by representatives of the Architect/Engineer and the Owner.
- 8.11.2 The fire protection piping shall be tested under a hydrostatic pressure of not less than 200 lbs. PSIG, for a duration of not less than two (2) hours or at 50 lbs psi in excess of the maximum static pressure when the maximum pressure is in excess of 150 lbs. psi.
- 8.11.3 The piping subjected to the hydrostatic test shall be filled with water and thoroughly checked for the elimination of all air. The control valves shall be closed during pressure testing. All joints shall be proven tight or acceptable by the test. Defective work or materials shall be corrected or replaced in approved manner. If necessary, piping shall be dismantled and re-assembled with the use of new pipe or fittings as no caulking or makeshift method of temporary repair of defective work will be permitted. Test shall be repeated until the particular line or system receives the approval of the representatives of the Architect/Engineer.
- 8.11.4 Acceptance of the Standpipe System work shall be based upon the inspection and tests of the completed installation by representatives of the local fire department, Architect, Engineer, PIRA and the Owner.

IX FIRE PROTECTION SPRINKLER SYSTEM, AUTOMATIC, WET-PIPE TYPE SPECIFICATIONS

9.0 GENERAL

Applicable provisions of the "General Conditions" govern work under this section.

9.1 QUALIFICATIONS OF CONTRACTORS

The Contractor for the fire protection installation shall be a qualified Fire Protection Contractor, regularly engaged in the installation of automatic fire sprinkler systems and other fire protection equipment, and must have at least one (1) sprinkler installation approved by the Philippine Insurance Rating Association (PIRA). Companies or corporations whose personnel have supervised an approved sprinkler plan and subsequently approved by PIRA or by the Fire Department are also qualified.

9.2 SCOPE OF WORK

- 9.2.1 This specification includes the furnishing of all labor, materials, equipment and services necessary or incidental to the complete installation, testing, adjusting and placing into service of the several systems of fire protection, all as shown on the drawings and as hereinafter specified. Drawings and specifications are considered as mutually explanatory and all works called for by one and not the other, shall be performed as though called for by both. In cases of conflicting information, the Architect and Engineer shall be notified at once in writing. Where incidental equipment or appurtenances are required and not listed as shown, same shall be furnished as required for a complete fire protection system.
- 9.2.2 Drawings are intended to show general arrangement and approximate physical sizes of equipment diagrammatically. Every bolt, nut, brace, strut, etc., is not necessarily

indicated or specified; all such items as may be required, necessary or incidental to the proper and dependable operation of each system being a requirement of this contract, whether specifically referred to or not, must be supplied.

0.2.3 Work included in this specification shall consist of, but not limited to the following items:

1. Arrange for, obtain and bear the cost of necessary permits, bonds and fees for the automatic sprinkler work.
2. All fees, private or government shall be paid by the Contractor.
3. Furnish and install a sprinkler system to the entire building where shown on the drawings. System to include all pipes, hangers, sway braces, sprinkler heads, control valves, drains, alarms, water flow switches and control valve monitor switches, (the fire pumps, drives, jockey pumps and controllers, pumps standard accessories may be supplied by pump suppliers under separate bid package), to be installed by the Sprinkler Contractor.
4. Fire hose cabinets and fire hose accessories, including connection pipe and fittings to the sprinkler system
5. Alarm check valves, complete with set of trimmings, retarding chamber, water motor alarm gong, alarm pressure switches, water flow switches and monitor switches. The Sprinkler Contractor shall coordinate and interface the required electrical wiring connections for the water flow and monitor switches to the building fire alarm system
6. Furnish and install a system of dry standpipe complete with valves and fire department connection. Contractor to provide as shown in the plans, by-pass valve with pipe and fittings to connect the Wet Sprinkler pipe riser with the Dry Standpipe riser.
7. Furnish and install fire department connection for the sprinkler system.
8. Furnish and install inspector's test connection pipe, nozzles and valves on the farthest point of each floor, located where shown on the drawings.
9. Furnish and install water flow alarm switches, and monitor tamper switch to floor control valves. The Sprinkler Contractor shall furnish and install the Control Panel and the wiring in conduits for the connection of the water flow and monitor switches to the sprinkler supervisory panel. The supervisory control panel shall be interfaced to the building fire alarm system.
10. Do the testing of all piping works and necessary cleaning of the fire protection works. This includes also the testing of the fire department pipeline and drain pipe and water flow alarms.
11. Fire extinguishers as shown in the plans shall be supplied and installed by the Contractor. Over and above those specified, the owner of the building shall supply the requirements of the Fire Department.
12. All openings through which fire may spread from one floor to the other, such holes through floors or walls for the pipe shall be sealed with fire resistant materials.
13. Chipping and plastering works necessary for the area covered in the installation of automatic sprinkler system.
14. Furnish the shop drawings and certificates of inspection.
15. Periodically remove from the jobsite all rubbish and debris resulting from the fire protection work
16. Furnish and install one (1) unit of 10 lbs. (HCFC) portable fire extinguishers for Electrical Rooms, Pump Room.
17. Miscellaneous items as hereinafter provided.

9.3 SITE CONDITIONS

The Contractor shall be deemed to have visited the site and acquaint himself with the existing site condition, means of access and take into account any feature that may affect his tender. No claim for his neglect to do so or not, out of a misunderstanding on his part in these conditions shall be entertained.

The Fire Protection Contractor shall be responsible for the proper coordination with other trade contractors.

9.4 STANDARDS, CODES AND REGULATIONS

The applicable current standards for the fire protection systems shall be the National Fire Protection Association (NFPA), NFPA-13, and Philippine Fire Code-PD 1185, the PSME Code and all other applicable local codes and ordinances.

9.5 SUBMITTAL (SHOP) DRAWINGS AND DATA

9.5.1 Before commencing any work or providing any materials at the jobsite for this project, the Fire Protection Contractor shall submit to the Engineer for approval, four (4) copies of catalogue cuts and descriptive matter regarding materials and equipment which he intends to furnish and install.

9.5.2 Shop drawings and data shall be submitted specifically for, but not limited to the following items. Sprinkler heads, valves, pipes, pipe hangers, hose valves and accessories, Fire Department connections, fire pumps and jockey pumps, controllers, fire hose cabinets, mechanical grooved coupling, flexible pipe connectors, pressure reducing valves, pipe riser support and sleeves, portable fire extinguishers and foam equipment.

9.5.3 The Fire Protection Contractor shall not proceed with the installation of the work until he has received the Engineer's approval on his shop drawings.

9.5.4 The Engineer's approval of shop drawings, catalogue cuts, etc. shall not relieve the Fire Protection Contractor of the responsibility for any errors or omissions which may exist in the items neither submitted nor shall relieve him from the responsibility for deviations from the contract drawings and specifications.

The stamped approval of the shop drawings, catalogue cuts, etc. shall not be construed as a complete check, but will indicate only that the general design and method of construction is satisfactory.

9.5.5 In the event inspection authorities require additional clarifying details, the details shall be prepared and approval of the same secured by the Fire Protection Contractor at his expense.

9.6 CONDUCT OF WORK

The Fire Protection Contractor shall employ on the job at all times a competent superintendent Licensed Mechanical Engineer who shall be responsible for the progress and execution of the work. Workmanship shall be of high quality, conforming to standard practice as stipulated by NFPA, ASTM and ASA and PSME recommendations by skilled workmen during regular working hours.

9.7 LOCAL AND IMPORTED MATERIALS

9.7.1 All materials and equipment furnished under this section shall be new, manufactured in the United States, and Non-UL/FM but conforming to NFPA Standards.

9.7.2 The proposal submitted shall include all materials and equipment as specified or

9.7.3 shown on the drawings.

9.8 AUTOMATIC SPRINKLER AND STANDPIPE SYSTEM

- 9.8.1 Pipe shall be new, designed for 175psi working pressure, conforming to ASTM specifications, manufactured in the United States or approved local pipes and have the manufacturer's name or brand along with the applicable ASTM standard marked on each length of the pipe. The locally manufactured pipe brand "Supreme" are acceptable brand with proper schedule and wall thickness.
- 9.8.2 Pipe shall be steel, schedule 40, black and in accordance with the specifications ASTM A120 or A53.
- 9.8.3 Schedule 40 black steel pipes shall be joined by screwed joints in accordance with specifications ANSI B2.1 up to 2 1/2" and flanged, Victaulic type or screwed connections for 3" and up. Pipe fittings to be used with schedule 80 pipes shall be rated 300lbs. Class if there are any.
- 9.8.4 Sprinklers' piping that is exposed to the weather or used in a corrosive atmosphere shall be painted with protective coating. Sprinkler piping in the building shall be painted with two (2) coats of enamel primer and two (2) coats of Fire Red color enamel paint.
- 9.8.5 All ASTM A53 and ASTM A120 sprinkler pipe must be hydrostatic tested at the mill per ASTM standard.
- 9.8.6 Screwed fitting shall be malleable iron, 300 lbs. and 150 lbs. class, black and in accordance with ANSI B16.3. "Victaulic" brand mechanical tee and elbow UL/FM fittings can also be used.
- 9.8.7 Flanged fittings shall be steel, short body, 150, black and in accordance with ANSI B16.1. Gaskets shall be full face of 1/8" minimum thickness red sheet rubber. Flange bolts shall be hexagon head machine bolts with semi-finished hexagon head nuts, cadmium-plated having dimension in accordance with ANSI B18.2.
- 9.8.8 Weld fittings shall be steel, standard weight, black and in accordance with ANSI B16.9, ANSI B16.25, ASTM A234, ANSI B16.5 or ANSI B16.11.
- 9.8.9 Outside screw and yoke (O.S. & Y) gate valves shall be flanged, iron body, bronze mounted, 175 psi working pressure, with hand wheel turning counterclockwise to open. Valve shall be tested and listed by UL and/or FM.
- 9.8.10 Check valve shall be flanged, swing type, iron body bronze seal ring and disc ring, and 175 psi working pressure rating. Valve shall be tested and listed by UL and/or FM.
- 9.8.11 Check valve shall be butterfly wafer style, iron body, rubber seal 175 psi working pressure rating. Valve shall be tested and listed by UL and/or FM.
- 9.8.12 Fire Department connection shall be 4" x 2 1/2" x 2 1/2" Siamese connection, brass body, brass chain and plugs, and brass escutcheon letter "AUTOMATIC SPRINKLER" for sprinkler system, and/or "STANDPIPE" for standpipe system. Inlet threading shall be National Standard, same as municipal fire department connection shall be tested and listed by UL and/or FM and 175 psi rating.
- 9.8.13 Valve for main user drain shall be angle type or globe type, bronze body, screwed, 175 psi working pressure rating, 2" size and a renewable composition soft disc.
- 9.8.14 Valve for auxiliary drain and inspector's test connection shall be globe type, bronze body, screwed, 175 psi working pressure rating, 1" size and a renewable composition disc.
- 9.8.15 At each location where called for on plans or where required by the fire department, provide an approved retard-type electric flow alarm switch. Provide alarm bell as required. Flow alarm switch shall have extra set of contacts for extension by others to central alarm panel.
- 9.8.16 Interior bell or horn shall be 24 VDC. Horn or bell shall be tested and listed by UL and/or FM. (Shall be supplied by the Electrical Contractor)

- 9.8.17 Flow switch shall be vane type, 24 DC. Flow switch shall be tested and listed by UL and/or FM.
- 9.8.18 Butterfly valve with lamper switch shall be tested and listed by UL and/or FM.
- 9.8.19 Fire Hose Valve (Dry Standpipe) shall be angle type, 2½" female iron pipe threads by 2½" male NST hose threads, chromium plated with chromium plated cap and chain. Valve hose threads shall be National Standard same as municipal fire department. Valve shall be tested and listed by UL and/or FM and 175 psi rating.
- 9.8.20 Valves for the fire hose stations shall be angle type, pressure restricting type 1½" female iron pipe threads, rough brass male NST threads, polished brass, chromium plated. Valve shall be tested and listed by UL and/or FM.
- 9.8.21 Cabinet for fire hose shall be recessed, 16-gauge body, aluminum door trim. Cabinet shall be designed for 100 feet hose pin rack and fire extinguisher. Door shall be full panel glass. Cabinet finish shall be baked white enamel inside with "Fire Red" coat inside. Cabinet may be locally made of approved quality.
- 9.8.22 Pin rack for the fire hose station cabinet shall be semi-automatic, baked red enamel finish, designed for 100 feet of 1½" hose, and furnished with 1½" chrome plated brass rack nipple.
- 9.8.23 Fire hose for fire hose station shall be 100 feet of 1½" cotton single jacket, rubber lined hose with wax and gum treatment. Hose couplings shall be 1½" chrome plated male-female National Standard hose threads. Fire hose and couplings shall be approved by UL and/or FM.
- 9.8.24 Nozzle for fire hose station shall be 1½" adjustable capable of complete shut-off, solid straight stream or any degree of solid conical fog with chrome plate. Threads shall be National Standard hose threads. Nozzle shall be approved by UL and/or FM.
- 9.8.25 Provide 1½" spanner to each FHC cabinet.
- 9.8.26 Furnish and install one (1) each - 10 lbs capacity HCFC chemical multi-purpose type portable fire extinguisher UL-listed and Factory Mutual approved to each fire hose cabinet.

9.9 IDENTIFICATION SIGNS

The drain, alarm test valves, etc. shall have standard identification signs, painted fire red with white lettering. The signs shall be attached to the valve in a conspicuous position.

9.10 SPRINKLER HEADS

- 9.10.1 Sprinkler heads shall be 1½" NPT, (quick response or residential sprinkler), chrome finish, pendant, upright and horizontal sidewall. Sprinklers in the areas with suspended ceiling shall have escutcheon plates of the same finish as the textures of the ceiling boards. Sprinklers shall be tested and listed by UL and/or FM.
- 9.10.2 Furnish the Owner a steel enameled box housing for the space heads and a sprinkler wrench as shown in the plans.

9.11 FIRE PUMP

- 9.11.1 Fire Pump Assembly: Furnish and install fire pumps as shown on plans. One (1) Underwriters Laboratory Inc. approved fire service pump. The Fire pump at the Basement Floor shall be electric motor-driven with automatic controllers, and one (1) jockey pump complete with motors, motor starters, controls, fittings and other appurtenances necessary to complete the equipment installation in each respect. Pumps shall be connected as shown in the drawings. Complete installation shall be

piping shall be dismantled and re-assembled with the use of new pipe or fittings as no caulking or makeshift method of temporary repair of defective work will be permitted. Test shall be repeated until the particular line or system receives the approval of the representatives of the Architect/Engineer.

- 9.14.4 Acceptance of the automatic sprinkler work shall be based upon the inspection and tests of the completed installation by representatives of the local fire department, Architect, Engineer, PIRA and the Owner.

X PLUMBING

10 GENERAL

10.1 DESCRIPTION

10.1.0 Applicable provisions of General Conditions govern work under this section.

10.1.1 All fittings, connections and piping embedded in concrete shall be subject to inspection by the Architect and/or his representative before covering and/or completion.

10.1.2 The contractor shall provide all items, articles, materials, operations or methods listed, mentioned or scheduled on the drawings and/or herein, including labor, materials and incidentals necessary and required for their completion.

10.1.3 The contract drawings and specifications are complementary to each other and any labor or materials called for by either, whether or not called for by both, if necessary, for the successful operation of any of the particular type of equipment furnished and installed will be without additional cost to the owner.

10.1.4 Intent: It is not intended that the drawings shall show every pipe fitting. All such items, whether specifically mentioned or not, or indicated in the drawings shall be furnished and installed, if necessary to complete the system in accordance with the best practice of the plumbing trade and to the satisfaction of the engineer and the owner.

10.1.4.1 The plumbing contractor is required to refer to all architectural, structural and electrical plans and specifications and shall investigate all possible interferences and conditions affecting his work.

10.2 SCOPE OF WORK

Work included under this section of this specification consists of furnishing all labor, tools and equipment, appliances and materials necessary for complete installation, testing and operation of the storm drainage system in accordance with the contract.

- a. Arrange for, obtain and bear the cost of necessary permits, bonds and fees, private or government shall be paid by the contractor
- b. Supply and installation of Sanitary lines of the Building
- c. Supply and installation of waterlines of the Building.
- d. Storm drainage system and connection to the nearest storm drainage outlets
- e. Rainwater collector system
- f. Supply and installation of Transfer pumps and Overhead Tanks.
- g. Supply and installation of Plumbing fixtures.
- h. The contractor shall provide all necessary shop drawings and two (2) sets of As-Built Plans.
- i. Excavation and backfilling in connection with the work shall be included.

They be of standard size and weight, made of polyvinyl chloride, extruded, heavy wall, rated for 90-degree centigrade cable, schedule 40, pipes

Limitations of use shall be as follows:

- a. As per requirement of the latest edition of PEC and/or NEC.
 - b. Not permitted where subject to mechanical damage.
- 11.12.2 All conduits shall be of true cylindrical form and shall be within the actual size called for.
- 11.12.3 No conduits shall be used in any system smaller than 15-mm electrical trade size, not shall have more than four 90 degrees' bend in any one run, and where necessary, hand hole and pull boxes shall be provided.
- 11.12.4 No wires shall be pulled in any conduit until the conduit system is complete in all details, in case of underground work, until concrete envelope or masonry has been completed in every detail. In case of concealed work, until rough plastering has been completed.
- 11.12.5 The ends of all conduits shall be lightly plugged to exclude plaster dust sand and soil including moisture while the renovation of the perimeter is in the process.

11.13 OUTLET BOXES AND FITTINGS

- 11.13.1 At all outlets of every kind, for all systems, there shall be provided a suitable fitting which shall be either a box or other device especially designed to receive the type of fitting to be mounted thereon.
- 11.13.2 The Contractor shall consult with the Electrical Engineer as to the nature of various fittings to be used before installing his outlet fittings and shall conform strictly in the use of fittings so that the work when completed will be finished design.
- 11.13.3 In case of lamp post, the outlet of fittings shall be provided with suitable fixtures supports or a support of a size and a kind required by the fixture to be erected.

11.14 SWITCHES

- 11.14.1 Local lighting switches shall be flush type, heavy duty, 15- ampere size 250 volts, bakelite case, quick connect terminal Outdoor lights shall be automatically operated by means of photo switch and manual selection. Or it might be a manual switch by means of breaker switch inside the lighting panel.

11.15 RECEPTACLES

- 11.15.1 Standard receptacles shall be 15- ampere size 250volts, parallel slots, duplex, flush mounted composition case, side wired with the insulated mounting yoke. If weatherproof wall plate is required, standard factory made metal waterproof plate

11.16 PLATES

- 11.16.1 All switches and receptacles plates shall be bakelite plastic, ivory-colored or as directed by the Architect.

11.17 SWITCH GEAR, PANEL BOARDS AND CABINETS

- 11.17.1 Panel boards for outdoor lightings shall conform as indicated in the drawings with respect to supply characteristics, rating of main lug or main circuit breaker, main magnetic contactor, number and sizes of branch circuit breakers. All should have factory-wired control wirings with terminal block connection for external leads.
- 11.17.2 Lighting and power panel board either wall mounted or free standing shall consist of a factory complete dead front assembly of back plan, main busses, overcurrent and switching units, sheet metal cabinet and trim. Cabinet shall be fabricated from cold gauge galvanized sheet metal with cover capped and fastened

- 11.17.3 Panel boards and trim shall be suitable for the type of mounting shown on the drawings. The inside and outside of the panel boards cabinet and trim shall be factory painted and having two (2) coats of rust proof prime coat and one finish shop of gray enamel paint.
- 11.17.4 All cabinets and enclosure shall be general purpose, NEMA type 1 for indoor installation. Except where specifically noted on plans for outdoor use shall be rain tight and dust type NEMA 4X type enclosure.
- 11.17.5 All circuit breakers with frame size above 100AT shall have minimum interrupting capacity of 22 KAIC at 240 volts and frame size 100AT and below shall have minimum interrupting capacity of 18 KAIC at 240 volts. All circuit breakers shall be molded case, bolt on type with thermal magnetic trip elements. Number of poles, trip coil rating and frame size shall be as indicated on plans.
- 11.17.6 Switchgear main circuit breaker shall be stationary type, programmable trip device, or electronic relay that employs microprocessors-based technology. Functions to overload protection, short circuit protection, with selectivity, instantaneous short circuit protection with adjustment and ground fault protection.
- 11.17.7 Cardholder on inside of door with clear plastic cover and complete typewritten schedule of panel branch circuit shall be provided. Leave spare circuit blank.
- 11.17.8 Local panel boards and switchgear manufacture shall include among others,
- 11.17.9 Submit samples and or product description of panel board to be used for approval prior to ordering and installation.

11.18 ELECTRIC SERVICE

- 11.18.1 The electric service shall be three (3)-phase, 3 wire + 1 - neutral, 220volts, 60 hertz. The sizes of service entrance conductor and conduit are shown in the plans.
- 11.18.2 The electrical contractor shall inspect the site, consult with MERALCO and check the orientation of the proposed service entrance before commencing work to avoid field problems.

11.19 LIGHTING SYSTEM

- 11.19.1 The lighting system shall be complete in every respect as indicated on the electrical plans or as specified in the Architectural plans. Exact fixture location shall be determined.
- 11.19.2 All wiring shall be installed in conduits, and in general shall be concealed. Buried underground in concrete encasement and/or embedded in concrete.
- 11.19.3 Mounting height of devices shall be as indicated in the plans and/or subject to Architect's approval prior to installations as follows

Local switches - 1.4 above finish floor line
Receptacles - 0.3 above finish floor line

11.20 DISTRIBUTION FEEDERS

- 11.20.1 Distribution voltage shall be 220volts, three (3)-phase, 3 wire + 1 neutral. Feeder conductors and raceway shall be installed as shown on drawings and no change in size shall be made without the written consent of the Engineer. Feeder conductors shall be continuous, and without splices between terminals. When feeders are run in multiple, they shall be exactly of the same length to avoid unbalanced division of the current.

- 12.10.1 All ~~—~~ cables and optic-fibers shall comply with the requirements of the Underwriter's Laboratories, Inc. (UL), the ASTM, the IPCEA as to their particular usage, and the cabling/wiring requirement set by EIA- 568A.
- 12.10.2 All thermoplastic texture (TF) to be used shall be copper soft-drawn and annealed, shall be 98% conductivity or better, shall be smooth and true of a cylindrical form and shall be within the actual size called for.
- 12.10.3 For the CCTV and Security System, Category 6 (CAT6) UTP cable shall be used to power-up all the security cameras via Power Over Ethernet (PoE), and captured video shall be transmitted and recorded to the network video recorder (NVR).
- 12.10.4 Category 6 (CAT6) UTP cable for horizontal cabling and multi-pair CAT6 for backbone shall be used for the entire Voice System. The UTP cable shall be UL approved and should be able to run applications up to 1000 MHz. UTP cables shall be manufactured by a reliable manufacturing company acceptable to the Engineer or the Owner.
- 12.10.5 Thermoplastic texture (TF) copper wire shall be used for the wiring connections of Fire Alarm System. Class A wiring communication shall be provided.
- 12.10.6 All copper wires (TF wire) and co-axial cables shall be manufactured by a reliable manufacturing company acceptable to the Engineer or the Owner.

12.11 CONDUITS

- 12.11.1 The conduit system shall consist of the following:
Intermediate Metallic Conduit (IMC) & Electrical Metallic Tubing (EMT)
 Conduit shall be of standard size and weight, mild steel hot dipped galvanized with inside enamel or epoxy coating by a brand approved and acceptable to the Engineer or the Owner.
- Polyvinyl Chloride Conduit (PVC)
 Conduit shall be of standard size and weight, made of polyvinyl chloride, extruded, heavy wall, rated for 90-degree cantigrade cable, schedule 40, by a brand approved and acceptable to the Engineer or the Owner.
- 12.11.2 All conduits shall be of true cylindrical form and shall be within the actual size called for.
- 12.11.3 No conduits shall be used in any system smaller than 15-mm electrical trade size, shall not have more than four 90 degrees bend in any one run, and where necessary, hand hole and pull boxes shall be provided.
- 12.11.4 No wires shall be pulled in any conduit until the conduit system is complete in all details. In case of underground work, until concrete envelope or masonry has been completed in every detail. In case of concealed work, until rough plastering has been completed.
- 12.11.5 The ends of all conduits shall be tightly plugged to exclude plaster dust sand and soil including moisture while other works in the perimeter is in process.

12.12 TELECOM OUTLET BOXES AND FITTINGS

- 12.12.1 Telecom (Voice) outlet is the interface between horizontal cabling and the modular line cord connecting to the computer/ telephone terminal. The eight (8)- position modular UTP telecom outlet and its pin assignments shall meet EIA- 568 standards. All voice/ data outlets should be RJ45 type, ISO compliant, Insulation Displacement Contact, modular for RJ45 connector universal application and multi-vendor supportive.
- 12.12.2 Use a modular line cord (patch cord) with $L \leq 3m$ to connect the telecom outlet to a workstation. Patch cord is a flexible piece of cable terminated at both ends with plugs. Patch cords shall connect either the ports of active equipment on patch panel or the workstations to the wall outlet at the workplace. Twisted pair patch cord RJ45/ RJ45 shall be very high speed multimedia patch cords. Patch cord gray (G) will be

Install ~~one~~ telecom outlet to workstation, while patch cord blue (B) will be installed from modular patch panel (MPP) to hub.

12.12.3 All telecom outlets of every kind, for all auxiliary systems, there shall be provided suitable fittings which shall be either a box or other device especially designed to receive the type of fitting to be mounted thereon.

12.12.4 The auxiliary systems Contractor shall consult with the Engineer as to the nature of various fittings to be used before installing. The outlet fittings and shall conform strictly in the use of fittings so that the work when completed will be finished design.

12.13 ELECTRONIC COMPONENTS & EQUIPMENT

12.13.1 All CCTV electronic devices/components and equipment shall be listed by Underwriter's Laboratories Inc (UL) approved by the Factory Mutual System. It should be furnished by a single supplier/ manufacturer (one brand) only who are regularly engaged in the production/supply of such component/equipment, to achieve devices compatibility and for a reliable CCTV and Security system. All electronics equipment shall be state of the art and shall be only solid state component, and must be suitable for the purpose intended.

12.13.2 PoE Switch

All security cameras should be Power over Ethernet (PoE) supplied using a 26- port UTP 10/100/1000 Managed Ethernet injector.

12.13.3 CCTV Camera

All security cameras installed outdoors shall be Compact Bullet Smart IP Camera with water-tight housing (IP 66), while those installed indoors shall be 2MP Smart IP Indoor- Dome Camera. Both cameras shall use 1/2.8" progressive scan CMOS as image sensor, with a minimum effective pixel of 2.0 MP, maximum IR range of 30m and at least 120 dB WDR.

12.13.4 Network Video Recorder (NVR)

NVR supports H.264/H.264+/MPEG4 video formats, can handle up to 60 IP cameras, recording at up to 12MP resolution and has up to 8 SATA interfaces and 1 eSATA interface connectable for recording and backup.

12.13.5 LED Monitor/Display

The monitor should be CCTV- graded, with LED BL panel better than 43", supports NTSC/ PAL signal system, with a minimum resolution of 1920 x 1080 Full HD, and supports 2 x BNC, VGA, DVI & HDMI at input/ output. It shall require an AC input of 100 – 240Vac and consumes a power of at least 24W. It shall have a high- end video processor, PIP control function and automatic color control and color adjustment.

12.13.6 All Telephone (Voice) and Data System electronic devices/components and equipment shall be listed by Underwriter's Laboratories Inc. (UL), or approved by the Factory Mutual System. It should be furnished by a single supplier/ manufacturer (one- brand) only who are regularly engaged in the production/supply of such component/equipment, to achieve devices compatibility and for a reliable voice and data system. The specifications are intended to provide a broad outline of the required voice and data system, but are not intended to include all details of design and construction.

12.13.7 IP based Private Automatic Branch Exchange (IP PBX)

IP PBX shall be capable of connecting virtually all types of data/ voice telecommunication equipment into an integrated, easily controllable and configurable network. IP PBX can provide 20- direct lines and 120- IP extensions. This compatibility boosts speed and broadens networks for global connections. The system can be easily upgradable/ stackable to handle at multiple of 256 extensions with a range of capabilities.

12.13.8 Cabinets/ Rack Enclosures

Cabinets are the basis for housing all cabling system components. The cabinets shall be fully equipped with internal frames for patch panel, active equipment (cross-connect hardware), connection modules, and to organize the cable and patch cord lay out. Typically, a standard 19" framing and paneling shall be used provided by

proper climate control or ventilation. Cabinets should be in a room that is environmentally suitable, climate controlled and that can be secured. All cabinets should have locks or intrusion detection to safeguard the network infrastructure.

12.13.9 IDC Frame

Insulation displacement contact (IDC) frame shall have sufficient space for overvoltage protection, front side connections for easy installation, one single insertion tool for all connections. The front panel covers all underlying modules and cabling for a homogenous appearance and orderly installation.

- 12.13.10 All Fire Alarm electronic devices/components and shall be listed by Underwriter's Laboratories Inc. (UL), or approved by the Factory Mutual System. It should be furnished by a single supplier/ manufacturer (one- brand) only who are regularly engaged in the production/supply of such component/equipment, to achieve devices compatibility and for a reliable fire detection and alarm system. Provide a complete, manual fire alarm system. The actuation of any manual station or shall cause building alarm devices to sound.

12.13.11 DC Power Supply

Obtain a power input of 240Vac from emergency support panel, transformed and rectified to 24V DC output. This DC supply is enough for operation of initiating, alarm signal, trouble signal, and tripping circuits.

12.13.12 Battery Back-up

This is provided for FDAS operation in the event of primary power source failure. Transfer from normal to auxiliary power shall be done automatically. The rechargeable batteries shall have a sufficient ampere-hour rating to operate the system under supervisory and troubled conditions, including audible trouble signal devices for 60 hours and audio visual signal devices under alarm conditions for an additional 5 minutes. Provide a solid-state automatic battery charger capable of recharging a completely discharged batteries to fully charged condition in 48- hours or less.

12.13.13 Manual Pull Station

It contains electronics that communicate the station's status (alarm, normal) to the transponder over two wires which also provide power to the pull station. Stations shall be flush mounted.

12.13.14 Audiovisual Alarms

Provide surface mounted approved audiovisual alarm devices consisting of a single vibrating type alarm horn/bell suitable for use in an electronically-supervised circuit and top-mounted integral flashing strobe light. Horn/bell shall have a sound rating of at least 90 dB at 3m. Strobe light shall have a ruby colored lens and shall pulse in march-time sequence.

12.14 AUXILIARY SERVICE ENTRANCE REQUIREMENTS

- 12.14.1 Use two (2) sets of 50mmØ PVC empty conduit for each incoming telecommunication service. A tapered entrance column is required. It is also possible to utilize the electrical system service entrance column (co-shared).
- 12.14.2 Provide a telecom and CCTV room with a minimum floor area of 7.5 m² (3.0m x 2.5m typical), enough to house the main distribution frame IP PBX equipment, control PCs, the NVR, power supply, control PCs, LED displays/monitors and other CCTV equipment. This telecom room should be climate-controlled and shall be manned by network administrator(s) and security personnel.

12.15 RECORD DRAWINGS AND AS BUILT PLANS

- 12.15.1 The auxiliary system Contractor shall keep an active record of the actual installation works during the progress job. The said records shall become the reference for the preparation of the As-Built Plans which shall include all pertinent information, complete in all aspects of the actual installations, all new information not originally shown in the contract drawings. The As-Built Plans shall be prepared by the auxiliary system Contractor at his expense and shall be submitted to the Architect and the

Engineer approval upon the completion of the work. The approval of the As-Built drawings shall be a pre-requisite for the final acceptance of the electronic works.

- 12.15.2 Two (2) copies of the As-Built drawings, signed and sealed by the auxiliary system Contractor's Professional Electronics Engineer, shall be submitted to the Architect and Engineer consultants. Original tracing/ reproducible copy shall also be submitted.

Note: *In contrast between these Technical Specifications and the approved Plans issued to the Contractor, the approved Plans shall prevail. See also the approved program of works. In case of doubt, for clearer outlooks consult the assigned Architect/Engineer.*

Section VII. Drawings

[Insert here a list of Drawings. The actual Drawings, including site plans, should be attached to this section, or annexed in a separate folder.]

Section VIII. Bill of Quantities

Notes on the Bill of Quantities

Objectives

The objectives of the Bill of Quantities are:

- a. to provide sufficient information on the quantities of Works to be performed to enable Bids to be prepared efficiently and accurately; and
- b. when a Contract has been entered into, to provide a priced Bill of Quantities for use in the periodic valuation of Works executed.

In order to attain these objectives, Works should be itemized in the Bill of Quantities in sufficient detail to distinguish between the different classes of Works, or between Works of the same nature carried out in different locations or in other circumstances which may give rise to different considerations of cost. Consistent with these requirements, the layout and content of the Bill of Quantities should be as simple and brief as possible.

Daywork Schedule

A Daywork Schedule should be included only if the probability of unforeseen work, outside the items included in the Bill of Quantities, is high. To facilitate checking by the Entity of the realism of rates quoted by the Bidders, the Daywork Schedule should normally comprise the following:

- a. A list of the various classes of labor, materials, and Constructional Plant for which basic daywork rates or prices are to be inserted by the Bidder, together with a statement of the conditions under which the Contractor will be paid for work executed on a daywork basis.
- b. Nominal quantities for each item of Daywork, to be priced by each Bidder at Daywork rates as Bid. The rate to be entered by the Bidder against each basic Daywork item should include the Contractor's profit, overheads, supervision, and other charges.

Provisional Sums

A general provision for physical contingencies (quantity overruns) may be made by including a provisional sum in the Summary Bill of Quantities. Similarly, a contingency allowance for possible price increases should be provided as a provisional sum in the Summary Bill of Quantities. The inclusion of such provisional sums often facilitates budgetary approval by avoiding the need to request periodic supplementary approvals as the future need arises. Where such provisional sums or contingency allowances are used, the SCC should state the manner in which they will be used, and under whose authority (usually the Procuring Entity's Representative's).

The estimated cost of specialized work to be carried out, or of special goods to be supplied, by other contractors should be indicated in the relevant part of the Bill of Quantities as a particular provisional sum with an appropriate brief description. A separate procurement procedure is normally carried out by the Procuring Entity to select such specialized contractors. To provide an element of competition among the Bidders in respect of any facilities, amenities, attendance, etc., to be provided by the successful Bidder as prime Contractor for the use and convenience of the specialist contractors, each related provisional sum should be followed by an item in the Bill of Quantities inviting the Bidder to quote a sum for such amenities, facilities, attendance, etc.

Signature Box

A signature box shall be added at the bottom of each page of the Bill of Quantities where the authorized representative of the Bidder shall affix his signature. Failure of the authorized representative to sign each and every page of the Bill of Quantities shall be a cause for rejection of his bid.

These Notes for Preparing a Bill of Quantities are intended only as information for the Procuring Entity or the person drafting the Bidding Documents. They should not be included in the final documents.

**PROJECT TITLE : PROPOSED CONSTRUCTION OF HOUSING 32 - BALINGASA HOUSING
(PHASE 1A) AT BGY. BALINGASA**

LOCATION : BARANGAY BALINGASA, DISTRICT 1, QUEZON CITY

PROJECT NO. : 22 - 00074

DURATION : Five Hundred Ten (510) Calendar Days

BREAKDOWN OF COST

ITEM NO.	ITEM OF WORK (DESCRIPTION)	MATERIALS COST	LABOR COST	INDIRECT COST	AGGREGATE COST
I	GENERAL REQUIREMENTS				
II	CONSTRUCTION OF HIGH RISE HOUSING				
III	CONSTRUCTION OF GENSET ROOM				

TOTAL COST P _____

LUMP SUM BID IN WORDS : _____

Contractor : _____

BILL OF QUANTITIES
(Building Construction/Rehabilitation Project)

PROJECT TITLE : PROPOSED CONSTRUCTION OF HOUSING 32 - BALINGASA HIGH RISE HOUSING (PHASE 1A) AT BGY. BALINGASA

LOCATION : BARANGAY BALINGASA, DISTRICT 1, QUEZON CITY

PROJECT NO. : 22 - 00074

DURATION : Five Hundred Ten (510) Calendar Days

SCOPE OF WORK :

I GENERAL REQUIREMENTS

1.) General Requirements include temporary facilities and utilities, billboard, scaffolding, construction safety and health, and clearing, hauling and disposal of construction materials and debris.

II CONSTRUCTION OF HIGH RISE HOUSING

- 1.) Site Works include site clearing and preparation, layout and staking, soil treatment and earthworks.
- 2.) Civil / Structural Works include concrete works, masonry works, moisture protection, and metal works.
- 3.) Architectural Works include floor finishes, wall finishes, ceiling finishes, installation of doors and windows, painting works, logos and letterings, and fabricated materials.
- 4.) Sanitary/Plumbing Works include installation of roughing-ins, equipments, fixtures and accessories.
- 5.) Electrical Works include installation of roughing-ins, wirings, devices, panel boards, fixtures and accessories.
- 6.) Auxiliary Works include installation of CCTV system, data and LAN system, and fire detection and alarm system (FDAS).
- 7.) Mechanical Works include installation of roughing-ins, equipments, fixtures and accessories.
- 8.) Fire Protection Works include installation of fire pump assembly, roughing-ins, equipments, fixtures and accessories.
- 9.) Utility and Ancillary Works include construction of cistern tank and fire reserve tank, sewerage treatment plant, electrical utilities, and sewer utilities; and installation of utility pumps.

III CONSTRUCTION OF GENSET ROOM

- 1.) Site Works include demolition / removal works, site clearing and preparation, layout and staking, and earthworks.
- 2.) Civil / Structural Works include concrete works, masonry works, metal works, and roofing works.
- 3.) Architectural Works include painting works.
- 4.) Electrical Works include installation of roughing-ins and equipments.

IV All necessary testing and commissioning shall be performed in accordance to standards.

ITEM NO.	WORK DESCRIPTION & SCOPE OF WORKS	QTY.	UNIT	UNIT COST	TOTAL COST
I	GENERAL REQUIREMENTS				
	Billboard	1	unit	₱	₱
	Clearing, Hauling and Disposal of Construction Materials	34	t.l.		
	Construction Safety and Health	1	unit		
	Scaffolding (Rental)	4,441	sq.m.		
	Temporary Electrical and Water Facilities	510	day		
	Temporary Enclosure Around the Construction Area (H=2.4m)	226	l.m.		
	Temporary Facility /Container Van (L=12.20m x W=2.44m x H=2.4m)	1	unit		
				DIRECT COST I	₱

ITEM NO.	WORK DESCRIPTION & SCOPE OF WORKS	QTY.	UNIT	UNIT COST	TOTAL COST
II	CONSTRUCTION OF HIGH RISE HOUSING				
A	Site Works				
	Layout and Staking	3,231	sq.m.	₱	₱
	Site Clearing and Preparation	3,231	sq.m.		
	Excavation for Structures				
	Footing	5,012	cu.m.		
	Wall Footing	163	cu.m.		
	Footing Tie Beam	73	cu.m.		
	Concrete Wall	15	cu.m.		
	Elevator	62	cu.m.		
	Stair Footing	1	cu.m.		
	Excavation for Reinforced Concrete Pipe	188	cu.m.		
				Subtotal	₱
	Soil Treatment	3,231	sq.m.	₱	₱
	Gravel Bedding	138	cu.m.		
	Imported Earthfill	323	cu.m.		
				Material Cost	₱
				Labor Cost	
				Subtotal	₱
	Backfill and Compaction				
	High Rise Housing	4,299	cu.m.	₱	₱
	Backfill and Compaction for Reinforced Concrete Pipe	149	cu.m.		
				Subtotal	₱
				Material Cost A	₱
				Labor Cost A	
				Direct Cost A	₱
B	Civil / Structural Works				
	Concrete Works				
	Ready Mix Concrete, 35MPa, 3/4" Gravel @ 28 days				
	Column Footing	822	cu.m.	₱	₱
	Footing Tie Beam	71	cu.m.		
	Wall Footing	4	cu.m.		
	Concrete Wall	35	cu.m.		
	Column	864	cu.m.		
	Beam	1,751	cu.m.		
	Suspended Slab	1,421	cu.m.		
	Ramp	117	cu.m.		

ITEM NO.	WORK DESCRIPTION & SCOPE OF WORKS	QTY.	UNIT	UNIT COST	TOTAL COST
	Ready Mix Concrete, 28MPa, 3/4" Gravel @ 28 days				
	Slab-on Fill	293	cu.m.		
	Wall Footing	55	cu.m.		
	Stair Footing	3	cu.m.		
	Main Stairs	59	cu.m.		
	On-Site Mix Concrete, 21MPa, 3/4" Gravel @ 28 days				
	Lean Concrete (Footing Bed)	89	cu.m.		
	Stiffener Column	96	cu.m.		
	Stiffener Beam	76	cu.m.		
	Reinforcing Steel Bars				
	Grade 40 Reinforcing Steel Bars including G.I. Tie Wire # 16				
	10mmØ Reinforcing Steel Bars				
	Wall Footing	651	kg		
	Slab-on Fill	7,379	kg		
	Column (Ties)	210	kg		
	Entrance Stair	246	kg		
	Main Stair	5,251	kg		
	Stiffener Column (Ties)	6,799	kg		
	Stiffener Beam (Stirrups)	5,366	kg		
	Ramp Slab	4,331	kg		
	Ramp Beam	430	kg		
	Suspended Slab	94,160	kg		
	Beam	2,423	kg		
	12mmØ Reinforcing Steel Bars				
	Wall Footing	1,493	kg		
	Footing Tie Beam	758	kg		
	Footing Tie Beam (Stirrups)	4,872	kg		
	Concrete Wall Footing	154	kg		
	Concrete Wall	1,595	kg		
	Beam	3,665	kg		
	Beam (Stirrups)	83,428	kg		
	Column (Ties)	85,276	kg		
	Main Stair	298	kg		
	Stiffener Column	11,855	kg		
	Stiffener Beam	9,305	kg		
	Ramp Slab	7,928	kg		
	Ramp Beam	430	kg		
	Suspended Slab	168,881	kg		
	Grade 60 Reinforcing Steel Bars including G.I. Tie Wire # 16				
	16mmØ Reinforcing Steel Bars				
	Column Footing	3,712	kg		
	Footing Tie Beam	4,716	kg		
	Beam	27,360	kg		
	Ramp Beam	883	kg		
	Column	319	kg		

ITEM NO.	WORK DESCRIPTION & SCOPE OF WORKS	QTY.	UNIT	UNIT COST	TOTAL COST
	Concrete Wall Footing	98	kg		
	20mmØ Reinforcing Steel Bars				
	Column Footing	25,371	kg		
	Beam	90,311	kg		
	Ramp Beam	6,271	kg		
	25mmØ Reinforcing Steel Bars				
	Column Footing	7,073	kg		
	Beam	61,861	kg		
	Ramp Beam	2,675	kg		
	Column	69,753	kg		
	28mmØ Reinforcing Steel Bars				
	Column Footing	64,434	kg		
	Beam	66,683	kg		
	32mmØ Reinforcing Steel Bars				
	Column Footing	91,716	kg		
	Column	45,779	kg		
	Formworks				
	Column Footing	983	sq.m.		
	Slab-on Fill	33	sq.m.		
	Ramp Slab	453	sq.m.		
	Column	4,838	sq.m.		
	Beam	11,719	sq.m.		
	Concrete Wall	438	sq.m.		
	Suspended Slab	10,014	sq.m.		
	Stiffener Column	5,714	sq.m.		
	Stiffener Beam	1,690	sq.m.		
	Stair	616	sq.m.		
	Scaffoldings / Shoring				
	Column	1,573	l.m.		
	Beam	6,513	l.m.		
	Suspended Slab	10,014	sq.m.		
	Stairs	590	sq.m.		
	Masonry Works				
	100mm CHB Laying including Mortar, Reinforcement and Two-Face Plastering	4,813	sq.m.		
	150mm CHB Laying including Mortar, Reinforcement and Two-Face Plastering	6,814	sq.m.		
	Moisture Protection				
	Vapor Barrier	2,513	sq.m.		
	Cementitious Capillary Type Waterproofing	654	sq.m.		
	Flexible Type Waterproofing	1,649	sq.m.		
	Metal Works				
	Façade				
	Green Wall	169	sq.m.		
	100mm x 100mm Tubular B.I. Pipe	1,803	kg		
	150mm x 150mm Tubular B.I. Pipe	1,881	kg		

ITEM NO.	WORK DESCRIPTION & SCOPE OF WORKS	QTY.	UNIT	UNIT COST	TOTAL COST
	200mm x 200mm Tubular B.I. Pipe	2,695	kg		
	300mm x 300mm Tubular B.I. Pipe	4,601	kg		
	Canopy				
	16mmØ Sag Rod	15	kg		
	25mmØ Tension Rod	84	kg		
	25mmØ Turn Buckle	8	piece		
	25mmØ Anchor Bolt	24	piece		
	50mm x 150mm x 6mm Channel Bar	138	kg		
	50mm x 150mm C-Purlins, Ga.20	138	kg		
	400mm x 650mm x 25mm Thick Anchor Plate	205	kg		
	Tapered Cantilever Beam	1,009	kg		
	Tubular Bar Railing	70	l.m.		
	B.I. Pipe Stair Railing				
	Elevator Stair	61	l.m.		
	Fire Exit 1	70	l.m.		
	Fire Exit 2	70	l.m.		
	Fire Exit 3	70	l.m.		
	Fire Exit 4	70	l.m.		
	Stainless Steel Ramp Railing				
	PWD Ramp	36	l.m.		
	Miscellaneous and Consumables				
	Acetylene Tank Refill	16	tank		
	Cut Off Blade	12	piece		
	Grinding Disc Metal	9	piece		
	Oxygen Tank for Refill	31	tank		
	Welding Rod	16	box		
				Material Cost B	₱
				Labor Cost B	
				Direct Cost B	₱
C	Architectural Works				
	Floor Finishes				
	50mm Thick Concrete Topping with Plain Cement Finish	4,751	sq.m.	₱	₱
	600mm x 600mm Non-Skid Homogeneous Floor Tiles	1,460	sq.m.		
	300mm x 600mm Vitrified Ceramic Floor Tiles	191	sq.m.		
	300mm x 300mm Non-Skid Ceramic Floor Tiles	150	sq.m.		
	300mm x 300mm Tactile Floor Finish	23	sq.m.		
	Floor Topping for Preparation of Tile Works	1,824	sq.m.		
	Wall Finishes and Partitions				
	300mm x 600mm Ceramic Wall Tiles	514	sq.m.		
	300mm x 300mm Ceramic Wall Tiles	767	sq.m.		
	4mm thk Aluminum Composite Panel Cladding with Metal Framing	286	sq.m.		
	2m x 10mm thick Laminated Plyboard Toilet Partition including Ledge and Stainless Steel Accessories	95	sq.m.		

ITEM NO.	WORK DESCRIPTION & SCOPE OF WORKS	QTY.	UNIT	UNIT COST	TOTAL COST
	Urinal Partitions	8	set		
	Ceiling Finishes				
	12mm thk Moisture Resistant Gypsum Board including	340	sq.m.		
	Rubbed Concrete Finish for Slab Soffit	11,191	sq.m.		
				Material Cost	₱
				Labor Cost	
				Subtotal	₱

ITEM NO.	WORK DESCRIPTION & SCOPE OF WORKS	QTY.	UNIT	UNIT COST	TOTAL COST
	Installation of Doors				
	D1 - (2.10m x 0.80m) Panel Door	49	set	₱	₱
	D2 - (2.10m x 0.60m) Flush Door	49	set		
	D3 - (2.10m x 0.60m) PVC Door with Louver	49	set		
	D4 - (2.10m x 1.00m) Steel Door with Panic Hardware	20	set		
	D5 - (2.40m x 2.40m) Full Louvered Metal Two Leaf Door	4	set		
	D6 - (2.50m x 2.10m) Frameless Glass Door, Double Leaf	2	set		
	D7 - (2.40m x 1.80m) Frameless Glass Door with Film Sticker, Double Leaf	11	set		
	D8 - (2.10m x 0.70m) Panel Door	14	set		
	D9 - (2.10m x 1.20m) Full Louvered Metal Two Leaf Door	5	set		
	D10 - (2.10m x 1.00m) Frameless Glass Door with Film Sticker, Double Leaf	7	set		
	D11 - (2.10m x 0.90m) Flush Door with Louver	9	set		
	Door Jambs				
	D1 - (2.10m x 0.80m) Panel Door	49	set		
	D2 - (2.10m x 0.60m) Flush Door	49	set		
	D4 - (2.10m x 1.00m) Steel Door with Panic Hardware	20	set		
	D5 - (2.40m x 2.40m) Full Louvered Metal Two Leaf Door	4	set		
	D8 - (2.10m x 0.70m) Panel Door	14	set		
	D9 - (2.10m x 1.20m) Full Louvered Metal Two Leaf Door	5	set		
	D11 - (2.10m x 0.90m) Flush Door with Louver	9	set		
	Hardwares and Accessories				
	Door Hinges, Heavy Duty Stainless	597	set		
	Door Knob, Lever Type, Stainless	170	set		
	38mm Ø X 1.0m Vertical Stainless Hairline Finish Door Handle	40	set		
	Installation of Windows				
	W1 - (1.20m x 1.20m) Aluminum Framed Powder Coated Casement Window	51	set		
	W2 - (1.20m x 0.80m) Aluminum Framed Powder Coated Sliding Window	98	set		
	W3 - (1.10m x 0.50m) Jalousie Window	49	set		
	W4 - (0.50m x 0.50m) Aluminum Framed Powder Coated Awning Window	49	set		
	W5 - (2.40m x 3.50m) Aluminum Framed Powder Coated Fixed Glass Window	9	set		
	W6 - (0.50m x 2.00m) Aluminum Framed Powder Coated Awning Window	2	set		
	W7 - (0.50m x 1.50m) Aluminum Framed Powder Coated Awning Window	5	set		

ITEM NO.	WORK DESCRIPTION & SCOPE OF WORKS	QTY.	UNIT	UNIT COST	TOTAL COST
	W8 - (1.20m x 1.20m) Steel Louver Window	2	set		
	Glass Blocks	13	sq.m.		
				Material Cost	₱
				Labor Cost	
				Subtotal	₱
	Painting Works				
	Elastomeric Paint Finish (Exterior Surfaces)	10,885	sq.m.	₱	₱
	Epoxy Enamel Paint Finish (Steel Members)	532	sq.m.		
	Epoxy Paint Finish (Basketball Court)	230	sq.m.		
	Flat Latex Paint Finish				
	Interior Wall	9,507	sq.m.		
	Ceiling	340	sq.m.		
	Slab Soffit	11,191	sq.m.		
	Fire Red Paint Finish (Fire Protection Works)	4,687	sq.m.		
	Rubberized Paint Finish	5,340	sq.m.		
	Logos and Letterings				
	QC Logo	1	set		
	500mm Stainless Steel Lettering with Neon Backlight				
	BALINGASA HOUSING	16	piece		
	Fabricated Materials				
	Built Up Concrete Lavatory, Granite Finish (Wash Areas, Shower Rooms)	26	l.m.		
				Material Cost	₱
				Labor Cost	
				Subtotal	₱
				Material Cost C	₱
				Labor Cost C	
				Direct Cost C	₱
D	Sanitary / Plumbing Works				
	Sewer Line / Storm Drainage System				
	Roughing-Ins				
	50mm Ø PVC Pipe with Hub	687	piece	₱	₱
	75mm Ø PVC Pipe with Hub	151	piece		
	100mm Ø PVC Pipe with Hub	411	piece		
	150mm Ø PVC Pipe with Hub	185	piece		
	200mm Ø PVC Pipe with Hub	42	piece		
	250mm Ø PVC Pipe with Hub	84	piece		
	315mm Ø PVC Pipe with Hub	40	piece		
	50mm Ø x 50mm Ø PVC Wye	138	piece		
	75mm Ø x 50mm Ø PVC Wye	12	piece		
	75mm Ø x 75mm Ø PVC Wye	10	piece		
	100mm Ø x 50mm Ø PVC Wye	833	piece		
	100mm Ø x 75mm Ø PVC Wye	99	piece		

ITEM NO.	WORK DESCRIPTION & SCOPE OF WORKS	QTY.	UNIT	UNIT COST	TOTAL COST
	100mm Ø x 100mm Ø PVC Wye	202	piece		
	150mm Ø x 50mm Ø PVC Wye	47	piece		
	150mm Ø x 100mm Ø PVC Wye	36	piece		
	150mm Ø x 150mm Ø PVC Wye	4	piece		
	200mm Ø x 100mm Ø PVC Wye	2	piece		
	200mm Ø x 150mm Ø PVC Wye	5	piece		
	250mm Ø x 200mm Ø PVC Wye	3	piece		
	50mm Ø x 50mm Ø PVC Tee	1,252	piece		
	75mm Ø x 50mm Ø PVC Tee	59	piece		
	75mm Ø x 75mm Ø PVC Tee	3	piece		
	250mm Ø x 250mm Ø PVC Tee	14	piece		
	50mm Ø PVC 1/4 Bend	996	piece		
	75mm Ø PVC 1/4 Bend	113	piece		
	100mm Ø PVC 1/4 Bend	12	piece		
	250mm Ø PVC 1/4 Bend	39	piece		
	50mm Ø PVC 1/8 Bend	2,326	piece		
	75mm Ø PVC 1/8 Bend	226	piece		
	100mm Ø PVC 1/8 Bend	557	piece		
	150mm Ø PVC 1/8 Bend	96	piece		
	200mm Ø PVC 1/8 Bend	14	piece		
	250mm Ø PVC 1/8 Bend	18	piece		
	315mm Ø PVC 1/8 Bend	14	piece		
	150mm Ø x 100mm Ø PVC Reducer	2	piece		
	200mm Ø x 150mm Ø PVC Reducer	7	piece		
	250mm Ø x 200mm Ø PVC Reducer	6	piece		
	315mm Ø x 250mm Ø PVC Reducer	7	piece		
	50mm Ø PVC Cleanout	174	piece		
	100mm Ø PVC Cleanout	95	piece		
	150mm Ø PVC Cleanout	16	piece		
	200mm Ø PVC Cleanout	4	piece		
	250mm Ø PVC Cleanout	3	piece		
	50mm Ø PVC P-Trap	721	piece		
	50mm Ø No-hub PVC Coupling	174	piece		
	Waterline System				
	Roughing-Ins				
	20mmØ PPR Pipe	243	piece		
	25mmØ PPR Pipe	38	piece		
	32mmØ PPR Pipe	38	piece		
	40mmØ PPR Pipe	23	piece		
	50mmØ PPR Pipe	24	piece		
	65mmØ PPR Pipe	39	piece		
	75mmØ PPR Pipe	18	piece		
	90mmØ PPR Pipe	22	piece		
	110mmØ PPR Pipe	8	piece		
	20mmØ x 20mmØ Tee Equal	524	piece		

ITEM NO.	WORK DESCRIPTION & SCOPE OF WORKS	QTY.	UNIT	UNIT COST	TOTAL COST
	25mmØ x 25mmØ Tee Equal	13	piece		
	32mmØ x 32mmØ Tee Equal	11	piece		
	50mmØ x 50mmØ Tee Equal	16	piece		
	65mmØ x 65mmØ Tee Equal	15	piece		
	75mmØ x 75mmØ Tee Equal	28	piece		
	90mmØ x 90mmØ Tee Equal	17	piece		
	25mmØ x 20mmØ Unequal Tee	38	piece		
	32mmØ x 20mmØ Unequal Tee	39	piece		
	40mmØ x 20mmØ Unequal Tee	27	piece		
	40mmØ x 25mmØ Unequal Tee	12	piece		
	40mmØ x 32mmØ Unequal Tee	13	piece		
	50mmØ x 25mmØ Unequal Tee	19	piece		
	50mmØ x 32mmØ Unequal Tee	14	piece		
	50mmØ x 40mmØ Unequal Tee	11	piece		
	65mmØ x 20mmØ Unequal Tee	11	piece		
	65mmØ x 50mmØ Unequal Tee	11	piece		
	75mmØ x 65mmØ Unequal Tee	11	piece		
	25mmØ x 20mmØ Reducer	30	piece		
	32mmØ x 20mmØ Reducer	13	piece		
	32mmØ x 25mmØ Reducer	22	piece		
	40mmØ x 20mmØ Reducer	13	piece		
	40mmØ x 25mmØ Reducer	11	piece		
	40mmØ x 32mmØ Reducer	16	piece		
	50mmØ x 20mmØ Reducer	11	piece		
	50mmØ x 32mmØ Reducer	12	piece		
	50mmØ x 40mmØ Reducer	17	piece		
	65mmØ x 20mmØ Reducer	13	piece		
	65mmØ x 25mmØ Reducer	12	piece		
	65mmØ x 40mmØ Reducer	12	piece		
	65mmØ x 50mmØ Reducer	14	piece		
	75mmØ x 50mmØ Reducer	13	piece		
	75mmØ x 65mmØ Reducer	11	piece		
	90mmØ x 65mmØ Reducer	15	piece		
	110mmØ x 90mmØ Reducer	10	piece		
	20mmØ 90° Elbow	1055	piece		
	25mmØ 90° Elbow	57	piece		
	32mmØ 90° Elbow	21	piece		
	40mmØ 90° Elbow	11	piece		
	50mmØ 90° Elbow	15	piece		
	65mmØ 90° Elbow	16	piece		
	75mmØ 90° Elbow	16	piece		
	90mmØ 90° Elbow	22	piece		
	20mmØ x 12mm Ø Female Threaded Tee	306	piece		
	20mmØ End Cap	306	piece		
	25mmØ End Cap	17	piece		

ITEM NO.	WORK DESCRIPTION & SCOPE OF WORKS	QTY.	UNIT	UNIT COST	TOTAL COST
	20mmØ Union Patent	22	piece		
	25mmØ Union Patent	8	piece		
	32mmØ Union Patent	6	piece		
	50mmØ Union Patent	2	piece		
	65mmØ Union Patent	3	piece		
	75mmØ Union Patent	19	piece		
	90mmØ Union Patent	4	piece		
	20mmØ Coupling	81	piece		
	25mmØ Coupling	13	piece		
	32mmØ Coupling	13	piece		
	40mmØ Coupling	8	piece		
	50mmØ Coupling	8	piece		
	65mmØ Coupling	13	piece		
	75mmØ Coupling	6	piece		
	90mmØ Coupling	8	piece		
	110mmØ Coupling	3	piece		
	20mmØ Male Adaptor	186	piece		
	25mmØ Male Adaptor	32	piece		
	32mmØ Male Adaptor	24	piece		
	50mmØ Male Adaptor	8	piece		
	65mmØ Male Adaptor	12	piece		
	75mmØ Male Adaptor	76	piece		
	90mmØ Male Adaptor	30	piece		
	90mmØ Female Adaptor	4	piece		
	Rainwater Collection System				
	50mm Ø PPR Pipe, PN 16	76	piece		
	50mm Ø x 50mm Ø PPR Wye	31	piece		
	50mm Ø PPR 90° Elbow	5	piece		
	50mm Ø PPR 45° Elbow	61	piece		
	50mm Ø PPR End Cap	38	piece		
	50mm Ø PPR Coupling	70	piece		
	50mmØ No-Hub Coupling	96	piece		
	75mm Ø PPR Male Adaptor	16	piece		
	Sump Pit Assembly				
	B.I.Pipe, SCH 40				
	50mm Ø x 6m B.I. Pipe	9	piece		
	Fittings				
	50mm Ø x 90° Elbow	8	piece		
	50mm Ø Coupling	12	piece		
	Other Items				
	Lifting Cables (Stainless Steel Wire Rope - 4mm dia.)	1	roll		
	Water Level Indicator (4-20MA Level Sensor- Beam Digital Display)	2	piece		
	Flow Switch (Automatic Pump Control)	2	piece		
	Valve and Appurtenances				

ITEM NO.	WORK DESCRIPTION & SCOPE OF WORKS	QTY.	UNIT	UNIT COST	TOTAL COST
	20mmØ Gate Valve PPR	71	piece		
	25mmØ Gate Valve PPR	8	piece		
	32mmØ Gate Valve PPR	6	piece		
	50mmØ Gate Valve PPR	2	piece		
	65mmØ Gate Valve PPR	3	piece		
	75mmØ Gate Valve PPR	19	piece		
	90mmØ Gate Valve PPR	8	piece		
	90mmØ Check Valve	3	piece		
	90mmØ Float Valve	2	piece		
	20mmØ Water Meter	49	piece		
	90mmØ Water Meter	1	piece		
	Fixtures				
	50mmØ PWD Toilet Grab Bar	2	l.m.		
	Bidet, Heavy-Duty, Stainless with Complete Accessories (Water Efficient)	69	unit		
	Facial Mirror on Marine Pywood Backing with Fasteners	54	sq.m.		
	Floor Drain, 100mm x 100mm Stainless Steel	14	piece		
	Grease Trap, 5GPM, Heavy Duty, with Accessories	49	set		
	Hose Bibb, Lever-Type, Stainless, Heavy Duty (Water Efficient)	76	piece		
	Kitchen Sink, Single, Stainless	49	piece		
	Kitchen Sink Faucet, Lever Type, Stainless, Heavy Duty (Water Efficient)	49	piece		
	Lavatory, Countertop-Mounted	19	set		
	Lavatory, Wall Hung	50	set		
	Lavatory Faucet, Lever Type, Stainless, Heavy Duty (Water Efficient)	69	set		
	Slop Sink	14	piece		
	Shower Set, Fixed-Type, Stainless (Water Efficient)	49	piece		
	Urinal, Flush Valve (Water Efficient)	12	set		
	Water Closet, Tank Type (Water Efficient)	69	set		
	Hardware and Accessories				
	Angle Valve, Single-Way Stainless Steel	160	piece		
	Angle Valve, Two-Way Stainless Steel	68	piece		
	Flexible Hose, Stainless	228	piece		
	Soap Holder, Ceramic	69	piece		
	Toilet Tissue Holder, Ceramic	69	piece		
	Wall Metal Door Hook Hanger	69	set		
	Pipe Hangers and Supports				
	For horizontal pipes less than 50mmØ (2m interval)	732	l.m.		
	For horizontal pipes greater than 50mmØ (1m interval)	348	l.m.		
	For vertical pipes greater than 50mmØ (1m interval)	444	l.m.		
	Miscellaneous				
	15mmØ Concrete Drill Bit	55	piece		
	15mmØ Metal Drill Bit	46	piece		

ITEM NO.	WORK DESCRIPTION & SCOPE OF WORKS	QTY.	UNIT	UNIT COST	TOTAL COST
	400cc Solvent Cement	167	can		
	All Around Sealant	21	can		
	Hacksaw Blade	32	piece		
	Teflon Tape	910	roll		
	Waste Cloth	22	kg		
				Material Cost D	₱
				Labor Cost D	
				Direct Cost D	₱
E	Electrical Works				
	Lighting and Power System				
	Roughing-ins				
	20mmØ PVC Pipe	7,655	piece	₱	₱
	32mmØ PVC Pipe	30	piece		
	100mmØ PVC Pipe	72	piece		
	20mmØ IMC Pipe	104	piece		
	25mmØ IMC Pipe	1,187	piece		
	32mmØ IMC Pipe	9	piece		
	40mmØ IMC Pipe	77	piece		
	50mmØ IMC Pipe	92	piece		
	65mmØ IMC Pipe	24	piece		
	80mmØ IMC Pipe	7	piece		
	100mmØ IMC Pipe	60	piece		
	Fittings And Accessories				
	20mmØ PVC Adaptor	4,090	piece		
	20mmØ PVC Elbow	1,365	piece		
	20mmØ PVC Locknut and Bushing	4,090	pair		
	20mmØ PVC Flexible Tube	11	roll		
	20mmØ Straight Connector with Locknut	2,168	piece		
	32mmØ PVC Adaptor	4	piece		
	32mmØ PVC Elbow	6	piece		
	32mmØ PVC Locknut and Bushing	4	pair		
	100mmØ PVC Adaptor	10	piece		
	100mmØ PVC Elbow	27	piece		
	100mmØ PVC Locknut and Bushing	10	pair		
	25mmØ IMC Coupling	110	piece		
	25mmØ IMC Elbow	250	piece		
	25mmØ IMC Locknut and Bushing	110	pair		
	32mmØ IMC Coupling	6	piece		
	32mmØ IMC Elbow	12	piece		
	32mmØ IMC Locknut and Bushing	6	pair		
	40mmØ IMC Coupling	36	piece		
	40mmØ IMC Elbow	20	piece		
	40mmØ IMC Locknut and Bushing	36	pair		
	50mmØ IMC Coupling	40	piece		

ITEM NO.	WORK DESCRIPTION & SCOPE OF WORKS	QTY.	UNIT	UNIT COST	TOTAL COST
	50mmØ IMC Elbow	48	piece		
	50mmØ IMC Locknut and Bushing	40	pair		
	65mmØ IMC Coupling	24	piece		
	65mmØ IMC Elbow	20	piece		
	65mmØ IMC Locknut and Bushing	16	pair		
	80mmØ IMC Coupling	4	piece		
	80mmØ IMC Elbow	8	piece		
	80mmØ IMC Locknut and Bushing	8	pair		
	100mmØ IMC Coupling	46	piece		
	100mmØ IMC Elbow	30	piece		
	100mmØ IMC Locknut and Bushing	130	pair		
	100mmØ Weatherproof Entrance Cap, Diecast	4	piece		
	50mm x 100mm Metal Utility Box	850	piece		
	100mm x 100mm Metal Junction Box With Cover	1,195	piece		
	50mm x 100mm Utility Box	49	piece		
	Square Box with Cover	51	piece		
	16mmØ x 250mm Oval Eye Bolt With Nut	1	piece		
	250mm ² Ø Solderless Connector w/ Two-Bolt	18	piece		
	125mm ² Ø Solderless Connector w/ Two-Bolt	24	piece		
	50mm ² Ø Solderless Connector w/ Two-Bolt	6	piece		
	Circuit Breaker Gutter Back Board (4' x 8' x 3/4" Thick	44	piece		
	20mm Ø x 3000mm Grounding Rod (Copper Clad)	35	piece		
	Wire Gutter (300mm x 300mm x 1000mm) Gauge 16	25	piece		
	Wire and Circuit Breaker Gutter (300mm x 300mm x 1950mm) Gauge 16	3	piece		
	Wire and Circuit Breaker Gutter (300mm x 300mm x 3600mm) Gauge 16	5	piece		
	Wire and Circuit Breaker Gutter (300mm x 300mm x 6000mm) Gauge 16	4	piece		
	Cable Tray (50mm x 200mmx 1800mm)	15	piece		
	Cable Tray (50mm x 200mmx 2400mm)	50	piece		
	Cable Tray (400mm x 400mmx 2400mm)	14	piece		
	Cable Tray (600mm x 400mmx 2400mm)	32	piece		
	Cable Tray Horizontal 90 Bend (600mm x 400mmx 2400mm)	4	piece		
	Cable Tray Vertical 90 Bend (600mm x 400mmx 2400mm)	4	piece		
	Cable Tray Horizontal 90 Bend (400mm x 400mmx 2400mm)	3	piece		
	Cable Tray Vertical 90 Bend (400mm x 400mmx 2400mm)	2	piece		
	Cable Tray Reducer	1	piece		
	Wires and Cables				
	3.5mm ² THHN Wire	304	roll		
	5.5mm ² THHN Wire	27	roll		
	8.0mm ² THHN Wire	34	roll		
	14.0mm ² THHN Wire	25	roll		

ITEM NO.	WORK DESCRIPTION & SCOPE OF WORKS	QTY.	UNIT	UNIT COST	TOTAL COST
	30.0mm ² THHN Wire	90	l.m.		
	38mm ² THHN Wire	693	l.m.		
	50mm ² THHN Wire	495	l.m.		
	80mm ² THHN Wire	333	l.m.		
	125mm ² THHN Wire	216	l.m.		
	150mm ² THHN Wire	63	l.m.		
	250mm ² THHN Wire	6,039	l.m.		
	2.0mm ² THW Wire	50	roll		
	3.5mm ² THW Wire	14	roll		
	5.5mm ² THW Wire	16	roll		
	8.0mm ² THW Wire	9	roll		
	14.0mm ² THW Wire	396	l.m.		
	22.0mm ² THW Wire	111	l.m.		
	30.0mm ² THW Wire	72	l.m.		
	38.0mm ² THW Wire	21	l.m.		
	60.0mm ² THW Wire	2,013	l.m.		
	50.0mm ² Bare Copper Wire	330	l.m.		
	Lighting Fixtures				
	2 x 18W LED, Dust Proof Cover, with Complete Accessories	429	set		
	300mm x 1200mm Surface Mounted Box Type Lighting Fixture with 1-18W Daylight LED Tube	295	set		
	300mm x 600mm,with 1 x 10W LED, Troffer Type with Complete Accessories, Surfaced Mounted	17	set		
	600mm x 600mm,with 2 x 10W LED, Troffer Type with Complete Accessories, Surfaced Mounted	9	set		
	Receptacle with 18W LED Bulb	225	set		
	Cylindrical Wall Lamp	6	set		
	Triangular Façade Luminaire with 2x18W LED Tube	12	set		
	150mm Ø Round Recessed Pinlight With 18W LED Bulb	71	set		
	Panel Light	20	set		
	Emergency Light, Twin-Head Exit Light	146	piece		

ITEM NO.	WORK DESCRIPTION & SCOPE OF WORKS	QTY.	UNIT	UNIT COST	TOTAL COST
	Wiring Devices				
	Outlet with Grounding, One-Gang	164	piece		
	Outlet with Grounding, Two-Gang	247	piece		
	Outlet with Grounding, For ACU	54	piece		
	Switch with Plate and Cover, One-Gang	234	piece		
	Switch with Plate and Cover, Two-Gang	19	piece		
	Switch with Plate and Cover, Three-Gang	10	piece		
	Switch with Plate and Cover, Three-Way	43	piece		
	Pipe Hangers & Supports				
	Horizontal Layout of Pipe	4,680	l.m.		
	Vertical Layout of Pipe	30	l.m.		
	Panelboard				
	HVSG Main: 6000AT, 6000AF, 3P, 100kAIC, 600V, MCCB Branches: 1 - 3200AT, 3P, MCCB 1 - 2500AT, 3P, MCCB 2 - Space	1	assy		
	LVSG 1 Main: 2500AT, 2500AF, 3P, 100kAIC, 600V, ACB Branches: 1 - 2000AT, 3P, MCCB 1 - 1000AT, 3P, MCCB 2 - Space	1	assy		
	LVSG 2 Main: 3200AT, 3200AF, 3P, 100kAIC, 600V, MCCB Branches: 1 - 150AT, 3P, MCCB 8 - 400AT, 3P, MCCB 1 - Space	1	assy		
	MCB 1 Main: 3200AT, 3200AF, 3P, 100kAIC, 600V, MCCB Enclosure: NEMA 4X with Metal Deadfont	1	assy		
	MCB 2 Main: 2500AT, 2500AF, 3P, 100kAIC, 600V, MCCB Enclosure: NEMA 4X with Metal Deadfont	1	assy		
	Automatic Transfer Switch (ATS) Main: 2000AT, 2000AF, 3P, 220V, 60Hz Enclosure: NEMA 3R	1	assy		

ITEM NO.	WORK DESCRIPTION & SCOPE OF WORKS	QTY.	UNIT	UNIT COST	TOTAL COST
	MDPAD (Admin) Main: 2000AT, 2000AF, 3P, 100kAIC, 600V, ACB Branches: 1 - 400AT, 3P, MCCB 1 - 250AT, 3P, MCCB 5 - 200AT, 3P, MCCB 1 - 150AT, 3P, MCCB 7 - 70AT, 3P, MCCB 3 - Space Enclosure: NEMA 1	1	assy		
	MPP (Ground Floor) Main: 400AT, 400AF, 3P, 65kAIC, 240V, MCCB Branches: 1 - 300AT, 3P, Bolt On 5 - 125AT, 3P, Bolt On 1 - 50AT, 3P, Bolt On 2 - 30AT, 2P, Bolt On 3 - Space Enclosure: NEMA 1	1	assy		
	STP (Ground Floor) Main: 150AT, 200AF, 3P, 35kAIC, 240V, MCCB Branches: 2 - 70AT, 3P, Bolt On 5 - 30AT, 2P, Bolt On 3 - 30AT, 2P, Bolt On, Spare Enclosure: NEMA 1	1	assy		
	DPAD A (Ground Floor) Main: 200AT, 200AF, 3P, 35kAIC, 240V, MCCB Branches: 1 - 150AT, 3P, Bolt On 1 - 100AT, 3P, Bolt On 2 - Space Enclosure: NEMA 1	1	assy		
	LPAD A (Ground Floor) Main: 150AT, 200AF, 3P, 35kAIC, 240V, MCCB Branches: 18 - 20AT, 2P, Bolt On 1 - 30AT, 2P, Bolt On, Spare 1 - 20AT, 2P, Bolt On, Spare Enclosure: NEMA 1	1	assy		

ITEM NO.	WORK DESCRIPTION & SCOPE OF WORKS	QTY.	UNIT	UNIT COST	TOTAL COST
	PPAD (Ground Floor) Main: 100AT, 100AF, 3P, 35kAIC, 240V, MCCB Branches: 4 - 30AT, 2P, Bolt On 3 - 20AT, 2P, Bolt On 1 - 40AT, 3P, Bolt On 2 - Space Enclosure: NEMA 1	1	assy		
	MDPC (Commercial Space) Main: 1000AT, 1000AF, 3P, 100kAIC, 600V, ACB Enclosure: NEMA 1 with Metal Deadfont	1	assy		
	LPPA-LPPJ TYPICAL TO LPPL-LPPN (Commercial) Main: 70AT, 100AF, 3P, 18kAIC, 240V Branches: 3 - 20AT, 2P, Bolt On 1 - 40AT, 3P, Bolt On 4 - 30AT, 2P, Bolt On, Spare Enclosure: NEMA 1	13	assy		
	LPPK (Commercial Space) Main: 70AT, 100AF, 3P, 18kAIC, 240V Branches: 3 - 20AT, 2P, Bolt On 2 - 40AT, 3P, Bolt On 3 - 30AT, 2P, Bolt On, Spare Enclosure: NEMA 1	1	assy		
	LPPO - LPPP (Commercial Space) Main: 70AT, 100AF, 3P, 18kAIC, 240V Branches: 2 - 20AT, 2P, Bolt On 2 - 30AT, 2P, Bolt On 2 - 30AT, 2P, Bolt On, Spare Enclosure: NEMA 1	2	assy		
	LPPQ - LPPV (Commercial Space) Main: 50AT, 50AF, 3P, 18kAIC, 240V Branches: 2 - 20AT, 2P, Bolt On 2 - 30AT, 2P, Bolt On 2 - 30AT, 2P, Bolt On, Spare Enclosure: NEMA 1	6	assy		
	LPPAD B (Second Floor) Main: 200AT, 200AF, 3P, 35kAIC, 240V, MCCB Branches: 19 - 20AT, 2P, Bolt On 1 - 30AT, 2P, Bolt On 4 - 30AT, 2P, Bolt On, Spare	1	assy		

ITEM NO.	WORK DESCRIPTION & SCOPE OF WORKS	QTY.	UNIT	UNIT COST	TOTAL COST
	Enclosure: NEMA 1				

ITEM NO.	WORK DESCRIPTION & SCOPE OF WORKS	QTY.	UNIT	UNIT COST	TOTAL COST
	LPPAD C (Third Floor) Main: 200AT, 200AF, 3P, 35kAIC, 240V, MCCB Branches: 19 - 20AT, 2P, Bolt On 1 - 30AT, 2P, Bolt On 4 - 30AT, 2P, Bolt On, Spare Enclosure: NEMA 1	1	assy		
	LPPAD D (Fourth Floor) Main: 125AT, 200AF, 3P, 35kAIC, 240V, MCCB Branches: 14 - 20AT, 2P, Bolt On 6 - 30AT, 2P, Bolt On 4 - 30AT, 2P, Bolt On, Spare Enclosure: NEMA 1	1	assy		
	PACUAD (Fourth Floor) Main: 100AT, 100AF, 3P, 25kAIC, 240V, MCCB Branches: 2 - 40AT, 3P, Bolt On 5 - 30AT, 2P, Bolt On 3 - 30AT, 2P, Bolt On, Spare Enclosure: NEMA 1	1	assy		
	DPAD D (Fourth Floor) Main: 200AT, 200AF, 3P, 25kAIC, 240V, MCCB Branches: 2 - 40AT, 3P, Bolt On 5 - 20AT, 2P, Bolt On 2 - Space Enclosure: NEMA 1	1	assy		
	ELEVATOR PANEL Main: 100AT, 100AF, 3P, 25kAIC, 240V, MCCB Branches: 1 - 50AT, 3P, Bolt On 1 - 20AT, 2P, Bolt On Enclosure: NEMA 1	2	assy		
	LPP (SMALL UNIT TYPICAL) Main: 40AT, 50AF, 3P, 18kAIC, 240V Branches: 2 - 20AT, 2P, Bolt On 1 - 30AT, 2P, Bolt On 1 - 30AT, 2P, Bolt On, Spare Enclosure: NEMA 1	49	assy		
	MC4 (Meter Center 4 - Fourth Floor) Main: 150AT, 200AF, 3P, 35kAIC, 240V, MCCB Enclosure: NEMA 1 with Metal Deadfont	1	assy		

ITEM NO.	WORK DESCRIPTION & SCOPE OF WORKS	QTY.	UNIT	UNIT COST	TOTAL COST
	LPPAD E (Fifth Floor) Main: 70AT, 100AF, 3P, 18kAIC, 240V, MCCB Branches: 7 - 20AT, 2P, Bolt On 1 - 30AT, 2P, Bolt On 2 - 30AT, 2P, Bolt On, Spare Enclosure: NEMA 1	1	assy		
	MC5 (Meter Center 5 - Fifth Floor) Main: 400AT, 400AF, 3P, 65kAIC, 240V, MCCB Enclosure: NEMA 1 with Metal Deadfont	1	assy		
	Enclosed Circuit Breaker (ECB) Main: 800AT, 3P Enclosure: NEMA 4X	1	assy		
	Enclosed Circuit Breaker (ECB) Main: 300AT, 3P Enclosure: NEMA 4X	1	assy		
	Enclosed Circuit Breaker (ECB) Main: 125AT, 3P Enclosure: NEMA 3R	2	assy		
	Enclosed Circuit Breaker (ECB) Main: 50AT, 3P Enclosure: NEMA 3R	1	assy		
	Enclosed Circuit Breaker (ECB) Main: 40AT, 3P Enclosure: NEMA 3R	4	assy		
	Enclosed Circuit Breaker (ECB) Main: 30AT, 2P Enclosure: NEMA 3R	15	assy		
	Circuit Breakers				
	40AT, 2P, 230V, MCCB	50	assy		
	70AT, 3P, 230V, MCCB	16	assy		
	50AT, 3P, 230V, MCCB	6	assy		
	Kilowatt-hour Meter (Submeter)	71	piece		
	CT Rated Kilowatt-hour Meter	2	piece		
	Miscellaneous & Consumables				
	400cc Solvent Cement	220	can		
	Electrical Tape	650	piece		
	Epoxy Primer	3	liter		
	GI Tie Wire, Ga. 16 (for Wire/Cable Pulling)	70	kg		
	Hacksaw Blade	50	piece		
	Masking Tape	50	piece		
	Pulling Lubricant	15	can		
	Rubber Tape	400	piece		
	Torch with Butane	15	set		
				Material Cost E	₱

ITEM NO.	WORK DESCRIPTION & SCOPE OF WORKS	QTY.	UNIT	UNIT COST	TOTAL COST
				Labor Cost E	
				Direct Cost E	₱

ITEM NO.	WORK DESCRIPTION & SCOPE OF WORKS	QTY.	UNIT	UNIT COST	TOTAL COST
F	Auxiliary Works				
	Fire Protection And Alarm System (FDAS)				
	Roughing-ins				
	15mmØ EMT Pipe	1,039	piece	₱	₱
	25mmØ EMT Pipe	65	piece		
	50mmØ EMT Pipe	7	piece		
	Fittings & Accessories				
	15mmØ EMT Connector, Compression Type	624	piece		
	15mmØ EMT Coupling, Compression Type	624	piece		
	15mmØ EMT Elbow	675	piece		
	25mmØ EMT Connector, Compression Type	39	piece		
	25mmØ EMT Coupling, Compression Type	39	piece		
	25mmØ EMT Elbow	42	piece		
	50mmØ EMT Connector, Compression Type	4	piece		
	50mmØ EMT Coupling, Compression Type	4	piece		
	50mmØ EMT Elbow	5	piece		
	300mm x 300mm x 200mm Metal Pullbox	20	assy		
	50mm x 100mm Metal Utility Box with Cover	100	piece		
	100mm x 100mm Metal Junction Box with Cover	285	piece		
	Wires and Cables				
	1.25mm² TF Wire	44	roll		
	Fixtures, Devices & Equipment				
	Combination Smoke & Carbon Monoxide Detector	140	piece		
	Heat Detector	144	piece		
	Fire Alarm Manual Pull Station	37	piece		
	150mmØ Bell / Horn with Strobe Light	37	set		
	Fire Alarm Control Panel, 8-Zones Fully Addressable	1	unit		
	Fire Alarm Control Panel, 16-Zones Fully	2	unit		
	Power Supply and Back-up Battery Pack w/ Charger	2	set		
	Pipe Hangers & Supports				
	Horizontal layout of pipe	2,440	l.m.		
	Vertical layout of pipe	680	l.m.		
	Miscellaneous & Consumables				
	Electrical Tape	40	roll		
	GI Tie Wire, Ga. 16 (for Wire/Cable Pulling)	15	kg		
	Hacksaw Blade	50	piece		
	Masking Tape	30	roll		
	Pulling Lubricant	7	can		
	Rubber Tape	30	roll		
	Waste Cloth	5	kg		
				Material Cost	₱
				Labor Cost	
				Subtotal	₱

ITEM NO.	WORK DESCRIPTION & SCOPE OF WORKS	QTY.	UNIT	UNIT COST	TOTAL COST
	Cable TV (CATV), Voice Data and Local Area Network (LAN) System				
	Roughing-ins				
	25mm Ø PVC Pipe	1,120	piece	₱	₱
	65mm Ø PVC Pipe	124	piece		
	20mm Ø IMC Pipe	64	piece		
	25mm Ø IMC Pipe	14	piece		
	50mm Ø IMC Pipe	20	piece		
	Fittings and Accessories				
	25mm Ø PVC Adaptor	840	piece		
	25mm Ø PVC Elbow	730	piece		
	25mm Ø PVC Locknut and Bushing	840	pair		
	65mm Ø PVC Adaptor	93	piece		
	65mm Ø PVC Elbow	80	piece		
	65mm Ø PVC Locknut and Bushing	93	pair		
	20mm Ø IMC Elbow	42	piece		
	20mm Ø IMC Coupling	63	piece		
	20mm Ø IMC Locknut and Bushing	65	pair		
	25mm Ø IMC Elbow	10	piece		
	25mm Ø IMC Coupling	13	piece		
	25mm Ø IMC Locknut and Bushing	15	pair		
	50mm Ø IMC Elbow	13	piece		
	50mm Ø IMC Coupling	19	piece		
	50mm Ø IMC Locknut and Bushing	21	pair		
	300mm x 300mm x 200mm Metal Pullbox	15	assy		
	50mm x 100mm Metal Utility Box with cover	145	piece		
	100mm x 100mm Metal Junction Box with Cover	145	piece		
	100mm x 100mm Metal Square Box with Cover	375	piece		
	Fiber Adapter Cable Kits	1	set		
	Telecom Backboard Flame Retardant	1	set		
	Wires and Cables				
	50 Pairs CAT5E Multi-pair Cable	20	l.m.		
	100 Pairs CAT5E Multi-pair Cable	50	l.m.		
	CAT3 Telephone Jacketed Cable (2-PAIRS)	4	roll		
	CAT6 UTP Cable, 4-pairs	380	l.m.		
	RG6 Coaxial Cable	5	roll		
	RG 11 Coaxial Cable	50	l.m.		
	Fixtures, Devices & Equipment				
	CATV Outlet Device	53	piece		
	Universal Voice/Data Outlet, Simplex (1-Device), Wall-Mounted	83	piece		
	Universal Voice/Data Outlet, Simplex (1-Device), Floor-Mounted	5	piece		
	IP PBX with 20-lines and 120 IP extensions	1	unit		

ITEM NO.	WORK DESCRIPTION & SCOPE OF WORKS	QTY.	UNIT	UNIT COST	TOTAL COST
	Distribution Frame (DF) 12U Data Rack (19") with Standard Framing & 1 - CAT6 Standard Density Feed-Thru Patch 1 - 16-port UTP 10/100/1000 Network Switch (1U) 1 - Router, 8-port Rackmounted 1 - Rackmounted UPS, 1000VA ≥ 5 mins "on-line" 1 - Rackmounted Surge Suppressor	1	assy		
	Main Telephone Terminal Cabinet (MTTC) Main Telephone Terminal Cabinet (MTTC) loaded Terminal Block ,760mmW x 1100mmL x 300mmD	1	assy		
	Telephone Terminal Cabinet 4 (TTC4) Telephone Terminal Cabinet (TTC) , loaded with 50-	1	assy		
	Telephone Terminal Cabinet 5 (TTC5) Telephone Terminal Cabinet (TTC) , loaded with	1	assy		
	Main CATV (MCATV) Main CATV Cabinet 32U STRUCTURED Enclosure 2 - Interior Equipment 1 - Main Amplifier 1 - Main Amplifier 1 - Coaxial Pre-Configured Panel 1- 32Way Passive Equipment (3U) 1- Center Expansion Board and Module Other	1	assy		
	CATVP (with slot for POE4) 16U Structured Enclosure bwith Standard Panelling 1 - Coaxial Pre-Configured Panel 1- 16Way Active Equipment (2U)	1	assy		
	CATVP (with slot for POE5) 24U Structured Enclosure bwith Standard Panelling 1 - Coaxial Pre-Configured Panel 1- 32Way Active Equipment (4U) 1- 16Way Active Equipment (2U)	1	assy		
	Pipe Hangers & Supports				
	Horizontal layout of pipe	412	l.m.		
	Vertical layout of pipe	115	l.m.		
	Miscellaneous & Consumables				
	Electrical Tape	40	roll		
	GI Tie Wire, Ga. 16 (for Wire/Cable Pulling)	4	kg		
	Hacksaw Blade	50	piece		
	Masking Tape	30	roll		
	Pulling Lubricant	5	can		
	Rubber Tape	30	roll		
	Waste Cloth	5	kg		
				Material Cost	₱
				Labor Cost	
				Subtotal	₱

ITEM NO.	WORK DESCRIPTION & SCOPE OF WORKS	QTY.	UNIT	UNIT COST	TOTAL COST
	Closed Circuit Television (CCTV) and Security System				
	Roughing-ins				
	25mmØ PVC Pipe	665	piece	₱	₱
	50mmØ IMC Pipe	5	piece		
	65mmØ IMC Pipe	60	piece		
	Fittings and Accessories				
	25mmØ PVC Adaptor	465.5	piece		
	25mmØ PVC Elbow	432.25	piece		
	25mmØ PVC Locknut and Bushing	465.5	piece		
	50mmØ IMC Coupling	4	piece		
	50mmØ IMC Elbow	5	piece		
	50mmØ IMC Locknut and Bushing	6	piece		
	65mmØ IMC Coupling	60	piece		
	65mmØ IMC Elbow	39	piece		
	65mmØ IMC Locknut and Bushing	61	piece		
	300mm x 300mm x 200mm Metal Pullbox	10	assy		
	50mm x 100mm Metal Utility Box with cover	69	piece		
	100mm x 100mm Metal Junction Box with Cover	62	piece		
	100mm x 100mm Metal Square Box with Cover	200	piece		
	Wires and Cables				
	CAT6 UTP Cable, 4-pairs	7	roll		
	A/V (VGA and HDMI) Cables	30	l.m.		
	Fixtures, Devices & Equipment				
	IP CCTV Compact Bullet Camera (Vandal resistant),	15	piece		
	IP Dome Camera (Day/Night), indoor Type	37	piece		
	26-port UTP 10/100/1000 PoE Switch/Ethernet	3	assy		
	Multi-Function Keyboard Controller	1	unit		
	32" Color LCD Display, Tilt Wall Mounted	7	unit		
	UPS, 1000VA ≥ 5 mins "on-line"	3	unit		

ITEM NO.	WORK DESCRIPTION & SCOPE OF WORKS	QTY.	UNIT	UNIT COST	TOTAL COST
	Main CCTV Cabinet				
	36U Data Rack (19') with Standard Framing & 1-12 port UTP 10/100/1000 PoE Switch Ethernet 1-26 port UTP 10/100/1000 PoE Switch Ethernet 1-CAT6 Standard-Density Feed-Thru Patch Panel, 1-20-Port UTP + 4= port FTP 10/100/1000 Network 4 - Network Video Recorder (NVR), 32-Channel 1-Rackmounted UPS, 1000VA ≥ 5 mins "on-line"	1	assy		
	Pipe Hangers & Supports				
	Vertical layout of pipe	301	l.m.		
	Miscellaneous & Consumables				
	Electrical Tape	15	roll		
	GI Tie Wire, Ga. 16 (for Wire/Cable Pulling)	5	kg		
	Hacksaw Blade	20	piece		
	Masking Tape	10	piece		
	Pulling Lubricant	2	can		
	Rubber Tape	10	roll		
	Waste Cloth	3	kg		
				Material Cost	₱
				Labor Cost	
				Subtotal	₱
				Material Cost F	₱
				Labor Cost F	
				Direct Cost F	₱
G	Mechanical Works				
	Refrigerant Pipe System				
	6mm Ø Copper Coil Tubing	56	l.m.	₱	₱
	10mm Ø Copper Coil Tubing	56	l.m.		
	16mm Ø Copper Coil Tubing	16	l.m.		
	6mm Ø x 20mm thick Rubber Foam Insulation	56	l.m.		
	10mm Ø x 20mm thick Rubber Foam Insulation	56	l.m.		
	16mm Ø x 20mm thick Rubber Foam Insulation	16	l.m.		
	Condensate Water Drainage System				
	20mm Ø x 3m uPVC Pipe	17	piece		
	32mm Ø x 3m uPVC Pipe	8	piece		
	40mm Ø x 3m uPVC Pipe	14	piece		
	20mm Ø x 12mm thick Rubber Foam Insulation	51	l.m.		
	32mm Ø x 12mm thick Rubber Foam Insulation	24	l.m.		
	40mm Ø x 12mm thick Rubber Foam Insulation	42	l.m.		
	Ventilation System				
	Pipes and Fittings				
	150mm Ø x 3m PVC Pipe	173	piece		
	150mm Ø Air Vent Cap	67	piece		

ITEM NO.	WORK DESCRIPTION & SCOPE OF WORKS	QTY.	UNIT	UNIT COST	TOTAL COST
	150mm Ø PVC Elbow	201	piece		
				Material Cost	₱
				Labor Cost	
				Subtotal	₱
	Equipment and Accessories				
	Exhaust and Ceiling Fans				
	EF 1 - Ceiling Mounted Exhaust Fan, 205cmh, 230V / 1φ / 60Hz	67	unit	₱	₱
	EF 2 - Wall Mounted Axial Exhaust Fan, 1260cmh, 52W, 230V / 1φ / 60Hz	3	unit		
	CF 1 - Ceiling Fan, 0.50cms, 100W, 230V / 1φ / 60Hz	3	unit		
	Window Type Airconditioning Unit				
	WAC 1 - Window Type Airconditioning Unit, 1.5hp, 1.0TR, 7.20cmm, 1100W, 230V / 1φ / 60Hz	1	unit		
				Material Cost	₱
				Labor Cost	
				Subtotal	₱
	Split-Type Air Conditioning Unit				
	FCU 1 - Ceiling Cassette Split Type Air Conditioning Unit, 3.0TR, 9.52mm Ø L, 15.88mm Ø G, 3340W, 230V / 1φ / 60Hz	2	unit	₱	₱
	FCU 2 - Wall Mounted Split Type Air Conditioning Unit, 1.0TR, 6.35mm Ø L, 9.52mm Ø G, 1070W, 230V / 1φ / 60Hz	3	unit		
				Material Cost	₱
				Labor Cost with	
				Subtotal	₱
	Pipe Hangers and Supports				
	Condensate Water Drainage System Support	117	l.m.	₱	₱
	Refrigerant Pipe System Support (150mm Ø U-Bolt)	64	l.m.		
	ACCU Support	5	unit		
	Window Type Aircon Steel Bracket	1	unit		
	Vibration Isolator	20	piece		
	Miscellaneous & Consumables				
	400cc Pipe Solvent Cement	5	can		
	25mm wide x 50m long Polyethylene Tape	3	roll		

ITEM NO.	WORK DESCRIPTION & SCOPE OF WORKS	QTY.	UNIT	UNIT COST	TOTAL COST
	Brazing Rod (10pcs/box)	5	box		
	Waste Cloth	3	kg		
				Material Cost	₱
				Labor Cost	
				Subtotal	₱
				Material Cost G	₱
				Labor Cost G	
				Direct Cost G	₱
H	Fire Protection Works				
	Fire Sprinkler System				
	Roughing-ins, Pipes and Fittings				
	25mm Ø B.I. Pipe, Schedule 40	229	piece	₱	₱
	32mm Ø B.I. Pipe, Schedule 40	165	piece		
	40mm Ø B.I. Pipe, Schedule 40	275	piece		
	50mm Ø B.I. Pipe, Schedule 40	10	piece		
	65mm Ø B.I. Pipe, Schedule 40	20	piece		
	75mm Ø B.I. Pipe, Schedule 40	14	piece		
	100mm Ø B.I. Pipe, Schedule 40	13	piece		
	150mm Ø B.I. Pipe, Schedule 40	8	piece		
	100mm Ø x 65mm Ø B.I. Tee, Weldable	4	piece		
	100mm Ø x 75mm Ø B.I. Tee, Weldable	8	piece		
	100mm Ø x 100mm Ø B.I. Tee, Weldable	7	piece		
	65mm Ø B.I. 90° Elbow, Weldable	5	piece		
	75mm Ø B.I. 90° Elbow, Weldable	5	piece		
	100mm Ø B.I. 90° Elbow, Weldable	9	piece		
	65mm Ø x 40mm Ø B.I. Reducer, Weldable	5	piece		
	75mm Ø x 65mm Ø B.I. Reducer, Weldable	5	piece		
	100mm Ø x 65mm Ø B.I. Reducer, Weldable	3	piece		
	65mm Ø B.I. Slip-on-Flange	7	piece		
	75mm Ø B.I. Slip-on-Flange	7	piece		
	100mm Ø B.I. Slip-on-Flange	5	piece		
	25mm Ø x 25mm Ø B.I. Tee, Threaded	319	piece		
	32mm Ø x 25mm Ø B.I. Tee, Threaded	47	piece		
	32mm Ø x 32mm Ø B.I. Tee, Threaded	299	piece		
	40mm Ø x 25mm Ø B.I. Tee, Threaded	11	piece		
	40mm Ø x 40mm Ø B.I. Tee, Threaded	319	piece		
	50mm Ø x 25mm Ø B.I. Tee, Threaded	10	piece		
	50mm Ø x 50mm Ø B.I. Tee, Threaded	9	piece		
	25mm Ø 90° B.I. Elbow, Threaded	393	piece		
	32mm Ø 90° B.I. Elbow, Threaded	345	piece		
	40mm Ø 90° B.I. Elbow, Threaded	363	piece		
	50mm Ø 90° B.I. Elbow, Threaded	6	piece		
	25mm Ø x 12mm Ø B.I. Reducer, Threaded	1,067	piece		

ITEM NO.	WORK DESCRIPTION & SCOPE OF WORKS	QTY.	UNIT	UNIT COST	TOTAL COST
	32mm Ø x 25mm Ø B.I. Reducer, Threaded	186	piece		
	40mm Ø x 32mm Ø B.I. Reducer, Threaded	176	piece		
	50mm Ø x 25mm Ø B.I. Reducer, Threaded	5	piece		
	50mm Ø x 40mm Ø B.I. Reducer, Threaded	45	piece		
	25mm Ø B.I. Threadolet, Threaded	3	piece		
	32mm Ø B.I. Threadolet, Threaded	9	piece		
	40mm Ø B.I. Threadolet, Threaded	55	piece		
	50mm Ø B.I. Threadolet, Threaded	47	piece		
	25mm Ø B.I. Union Patent, Threaded	5	piece		
	40mm Ø B.I. End Cap, Threaded	5	piece		
	50mm Ø B.I. End Cap, Threaded	3	piece		
	65mm Ø B.I. End Cap, Threaded	3	piece		
	75mm Ø B.I. End Cap, Threaded	2	piece		
	100mm Ø B.I. End Cap, Threaded	4	piece		
	13mm Ø B.I. Plug, Threaded	1,067	piece		
	Valves and Appurtenances				
	25mm Ø Inspector Test Connection	5	piece		
	25mm Ø Globe Valve	5	piece		
	Fixtures				
	Fire Sprinkler Head				
	13mm Ø Upright-type Fire Sprinkler Head, 68°C	606	piece		
	13mm Ø Pendent-type Fire Sprinkler Head, 68°C	396	piece		
	13mm Ø Sidewall-type Fire Sprinkler Head, 68°C	65	piece		
	Floor Control Assembly				
	Roughing-ins, Pipes and Fittings				
	25mm Ø B.I. Pipe, Schedule 40	6	piece		
	50mm Ø B.I. Pipe, Schedule 40	8	piece		
	100mm Ø B.I. Pipe, Schedule 40	5	piece		
	150mm Ø B.I. Pipe, Schedule 40	8	piece		
	150mm Ø x 100mm Ø B.I. Reducer, Weldable	5	piece		
	100mm Ø B.I. Slip-on-Flange	4	piece		
	25mm Ø x 25mm Ø B.I. Tee, Threaded	15	piece		
	25mm Ø 90° B.I. Elbow, Threaded	10	piece		
	25mm Ø B.I. Union Patent, Threaded	5	piece		
	Valves and Appurtenances				
	65mm Ø Fire Hose Valve	24	piece		
	25mm Ø Sight Glass	5	piece		
	25mm Ø Globe Valve	15	piece		
	75mm Ø Butterfly Valve with Tamper Switch	5	piece		
	100mm Ø Flow Switch	5	piece		
	300psi Pressure Gauge	5	piece		
	Pump Assembly				
	Pipes and Fittings				
	50mm Ø B.I. Pipe, Schedule 40	3	piece		
	100mm Ø B.I. Pipe, Schedule 40	10	piece		

ITEM NO.	WORK DESCRIPTION & SCOPE OF WORKS	QTY.	UNIT	UNIT COST	TOTAL COST
	150mm Ø B.I. Pipe, Schedule 40	12	piece		
	150mm Ø x 150mm Ø B.I. Tee, Weldable	5	piece		
	150mm Ø B.I. 90° Elbow, Weldable	6	piece		
	100mm Ø B.I. Slip-on-Flange	5	piece		
	150mm Ø B.I. Slip-on-Flange	5	piece		
	50mm Ø 90° B.I. Elbow, Threaded	4	piece		
	50mm Ø B.I. Threadolet, Threaded	4	piece		
	Valves and Appurtenances				
	50mm Ø Globe Valve	1	piece		
	50mm Ø Check Valve	1	piece		
	100mm Ø Check Valve	1	piece		
	100mm Ø Alarm Check Valve	1	piece		
	75mm Ø Relief Valve	2	piece		
	750gpm Flow Meter	1	piece		
	150mm Ø Victaulic Coupling	1	piece		
	150mm Ø OS & Y	2	piece		
	Fixtures				
	Fire Department Connection	1	set		
	Fire Extinguisher, ABC, 10 lbs	8	piece		
	Fire Extinguisher, HCFC, 10 lbs	8	piece		
	Fire Hose Cabinet with Standard Accessories	24	set		
				Material Cost	₱
				Labor Cost	
				Subtotal	₱
	Equipment and Accessories				
	FP 1 - Vertical Turbine Fire Pump, 750gpm, 158psi head, 100.0hp, 230V / 3φ / 60Hz	1	unit	₱	₱
	JP 1 - Vertical Turbine Jockey Pump, 25gpm, 168psi head, 5.0hp, 230V / 3φ / 60Hz	1	unit		
				Material Cost	₱
				Labor Cost with	
				Subtotal	₱
	Pipe Hangers and Supports				
	Hangers for 25mm Ø B.I. Pipe	1374	l.m.	₱	₱
	Hangers for 40mm Ø B.I. Pipe	2640	l.m.		
	Hangers for 50mm Ø B.I. Pipe	60	l.m.		
	Hangers for 65mm Ø B.I. Pipe	120	l.m.		
	Hangers for 75mm Ø B.I. Pipe	84	l.m.		
	Hangers for 100mm Ø B.I. Pipe	78	l.m.		
	Support for Vertical Pipes	108	l.m.		
	Miscellaneous & Consumables				
	20mm Ø Masonry Drill Bit	16	piece		
	20mm Ø Metal Drill Bit	16	piece		
	Hacksaw Blade	10	piece		

ITEM NO.	WORK DESCRIPTION & SCOPE OF WORKS	QTY.	UNIT	UNIT COST	TOTAL COST
	Rubber Gasket	11	l.m.		
	Special Purpose Sealant	20	tube		
	Teflon Tape	105	roll		
	Threading Oil	4	gal		
	Waste Cloth	3	kg		
	Welding Rod	3	box		
				Material Cost	₱
				Labor Cost	
				Subtotal	₱
				Material Cost H	₱
				Labor Cost H	
				Direct Cost H	₱

ITEM NO.	WORK DESCRIPTION & SCOPE OF WORKS	QTY.	UNIT	UNIT COST	TOTAL COST
I	Utility And Ancillary Works				
	310mm Ø Area Drain/Catch Basin	1	unit	₱	₱
	610mm Ø Area Drain/Catch Basin	7	unit		
	760mm Ø Area Drain/Catch Basin	4	unit		
	760mm Ø Manhole	1	unit		
	350mm Ø HDPE Pipe	9	l.m.		
	610mm Ø HDPE Pipe	40	l.m.		
	760mm Ø Reinforced Concrete Pipe	60	l.m.		
	300mm x 400mm x 5000mm Electrical Service Entrance	1	unit		
	600mm x 600mm Concrete Encasement	25	unit		
	600mm x 1000mm Cable Trench	26	unit		
	1000mm x 0.7m x 0.65m Hand Hole	1	unit		
	Ground Test Well	27	unit		
	Trench with Steel Grating	12	l.m.		
	Fire Reserve Tank and Cistern Tank w/ 10m L x 6.2m W x 3m D	186	cu.m.		
	STP Chamber (STP Equipment and Pumps not included)	1	unit		
	Equipments & Accessories				
	Elevator Pit Pump				
	Non-clog pump with a capacity of 20 GPM against 40 FT. and driven by 0.5 HP, 220V, 1Ø, 60Hz coupled with submersible motor and complete accessories.	1	unit		
	Rainwater Collector				
	Polyethylene Construction, capacity of 2 m ³ , 1250mm Max, Diameter, 260mm Complete w/ Inlet & Outlet Ports Drain Port, Manhole, Ladder, and Level Indications.	16	set		
	Sump Pumps				
	Submersible type, cast iron casing, stainless steel shaft, hard plastic impeller, double mechanical seal w/ a capacity of 20GPM against 40 ft to dynamic head, close- coupled to a 0.5 HP, 220V, 1Ø, 60Hz submersible motor. Complete w/ float switch for auto	2	set		
	Transfer Pumps				
	Centrifugal end-suction, cast-iron casing, stainless steel shaft, mechanical seal, hard plastic impeller, with a capacity of 225GPM against 225 FT. TDH, close coupled to a 20 HP, 220V, 75mmØ, 1Ø, 60Hz high efficient motor complete with electrodes for cist	2	set		
				Material Cost I	₱
				Labor Cost I	
				Direct Cost I	₱
				MATERIAL COST II	₱
				LABOR COST II	
				DIRECT COST II	₱

ITEM NO.	WORK DESCRIPTION & SCOPE OF WORKS	QTY.	UNIT	UNIT COST	TOTAL COST
III	CONSTRUCTION OF GENSET ROOM				
A	Site Works				
	Layout and Staking	25	sq.m.	₱	₱
	Site Clearing and Preparation	25	sq.m.		
	Excavation for Structures	11	cu.m.		
	Soil Treatment	25	sq.m.		
	Gravel Bedding	2	cu.m.		
				Material Cost	₱
				Labor Cost	
				Subtotal	₱
	Backfill and Compaction	5	cu.m.	₱	₱
				Subtotal	₱
				Material Cost A	₱
				Labor Cost A	
				Direct Cost A	₱
B	Civil / Structural Works				
	Concrete Works				
	On Site Mix Concrete, 21MPa, 3/4" Gravel @ 28 days				
	Wall Footing	3	cu.m.	₱	₱
	Slab-On-Fill	2	cu.m.		
	On Site Mix Concrete, 28MPa, 3/4" Gravel @ 28 days				
	Column Footing	1	cu.m.		
	Column	1	cu.m.		
	Genset Pad	3	cu.m.		
	Reinforcing Steel Bars				
	Grade 40 Reinforcing Steel Bars including G.I. Tie Wire # 16				
	10mmØ Slab-On-Fill	40	kg		
	10mmØ Column	21	kg		
	12mmØ Column	30	kg		
	12mmØ Wall Footing	120	kg		
	12mmØ Genset Pad	60	kg		
	Grade 60 Reinforcing Steel Bars including G.I. Tie Wire # 16				
	16mmØ Column Footing	32	kg		
	Formworks				
	Wall Footing	10	sq.m.		
	Column Footing	2	sq.m.		
	Column	7	sq.m.		
	Slab-On-Fill	2	sq.m.		
	Genset Pad	5	sq.m.		

ITEM NO.	WORK DESCRIPTION & SCOPE OF WORKS	QTY.	UNIT	UNIT COST	TOTAL COST
	Scaffoldings / Shoring				
	Column	7	l.m.		
	Masonry Works				
	100mm CHB Laying including Mortar, Reinforcement and Two-Face Plastering	5	sq.m.		
	150mm CHB Laying including Mortar, Reinforcement and Two-Face Plastering	41	sq.m.		
	Metal Works				
	Roof Framing				
	12mmØ Sag Rod	8	kg		
	50mm x 100mm C-Purlins, Ga.18	110	kg		
	63mmØ G.I. Pipe, Sch.20	110	kg		
	Steel Perimeter Fence				
	10mmØ x 50mm Cylindrical Hinge	36	piece		
	25mmØ Anchor Bolt	8	piece		
	38mm x 5mm Thick Flat Bar	263	kg		
	38mmØ Foot Bolt	2	piece		
	50mmØ G.I. Pipe, Sch.20	748	kg		
	50mm x 50mm x 6mmØ Wire Mesh	36	sq.m.		
	200mm x 200mm x 10mm Thick Base Plate	7	kg		
	Miscellaneous and Consumables				
	Acetylene Tank Refill	2	tank		
	Cut Off Blade	2	piece		
	Grinding Disc Metal	1	piece		
	Oxygen Tank for Refill	4	tank		
	Welding Rod	2	box		
	Roofing Works				
	Pre-Painted Rib-type G.I. Roofing	31	sq.m.		
	Pre-Painted G.I. End Flashing	24	l.m.		
	Blind Rivets	99	piece		
	Tekscrew	34	piece		
	Silicon Sealant	1	tube		
				Material Cost B	₱
				Labor Cost B	
				Direct Cost B	₱
C	Architectural Works				
	Painting Works				
	Elastomeric Paint Finish (Exterior Surfaces)	93	sq.m.	₱	₱
	Epoxy Enamel Paint Finish (Steel Members)	64	sq.m.		
				Material Cost C	₱
				Labor Cost C	
				Direct Cost C	₱
D	Electrical Works				
	Lighting and Power System				

ITEM NO.	WORK DESCRIPTION & SCOPE OF WORKS	QTY.	UNIT	UNIT COST	TOTAL COST
	Wires and Cables				
	250mm ² THHN Wire	11,255	l.m.	₱	₱
	60.0mm ² THW Wire	375	l.m.		
				Material Cost	₱
				Labor Cost	
				Subtotal	₱
	Generator Set				
	1 - 625kVA, 3P, 220V, 60Hz, 1800rpm, 0.80 p.f (4670mm x 1620mm x 2250mm) Diesel Engine Driven, Stand-By Silent Type Generator Set	1	unit	₱	₱
				Direct Cost	₱
				Material Cost D	₱
				Labor Cost D	
				Direct Cost D	₱
				MATERIAL COST III	₱
				LABOR COST III	
				DIRECT COST III	₱

SUMMARY

ITEM NO	WORK DESCRIPTION AND SCOPE OF WORKS	TOTAL COST
I	GENERAL REQUIREMENTS	₱
II	CONSTRUCTION OF HIGH RISE HOUSING	
III	CONSTRUCTION OF GENSET ROOM	
	NOTE: • Strictly enforce Health Protocols relative to the latest applicable DPWH Memorandum	
	TOTAL DIRECT COST	₱
	Overhead, Contingencies and Miscellaneous and Consumables Expenses (OCM)	
	Profit	
	VAT	
	TOTAL ESTIMATED COST	₱

Section IX. Checklist of Technical and Financial Documents

Notes on the Checklist of Technical and Financial Documents

The prescribed documents in the checklist are mandatory to be submitted in the Bid, but shall be subject to the following:

- a. GPPB Resolution No. 09-2020 on the efficient procurement measures during a State of Calamity or other similar issuances that shall allow the use of alternate documents in lieu of the mandated requirements; or
- b. any subsequent GPPB issuances adjusting the documentary requirements after the effectivity of the adoption of the PBDs.

The BAC shall be checking the submitted documents of each Bidder against this checklist to ascertain if they are all present, using a non-discretionary “pass/fail” criterion pursuant to Section 30 of the 2016 revised IRR of RA No. 9184.

Checklist of Technical and Financial Documents

I. TECHNICAL COMPONENT ENVELOPE

Class “A” Documents

Legal Documents

- (a) Valid PhilGEPS Registration Certificate (Platinum Membership) (all pages);
and
- (b) Registration certificate from Securities and Exchange Commission (SEC), Department of Trade and Industry (DTI) for sole proprietorship, or Cooperative Development Authority (CDA) for cooperatives or its equivalent document;
and
- (c) Mayor’s or Business permit issued by the city or municipality where the principal place of business of the prospective bidder is located, or the equivalent document for Exclusive Economic Zones or Areas;
and
- (e) Tax clearance per E.O. No. 398, s. 2005, as finally reviewed and approved by the Bureau of Internal Revenue (BIR).

Technical Documents

- (f) Statement of the prospective bidder of all its ongoing government and private contracts, including contracts awarded but not yet started, if any, whether similar or not similar in nature and complexity to the contract to be bid (*please see attached prescribed forms required by the QC – BAC for Infrastructure and Consultancy*); **and**
- (g) Statement of the bidder’s Single Largest Completed Contract (SLCC) similar to the contract to be bid, except under conditions provided under the rules with an attached Notice of Award, Notice to Proceed, Contract and Certificate of Acceptance (*please see attached prescribed form required by the QC – BAC for Infrastructure and Consultancy*); **and**
- (h) Philippine Contractors Accreditation Board (PCAB) License;
or
Special PCAB License in case of Joint Ventures;
and registration for the type and cost of the contract to be bid; **and**
- (i) Original copy of Bid Security. If in the form of a Surety Bond, submit also a certification issued by the Insurance Commission;
or
Original copy of Notarized Bid Securing Declaration; **and**
- (j) Project Requirements, which shall include the following:
 - a. Organizational chart for the contract to be bid;
 - b. List of contractor’s key personnel (*e.g.*, Project Manager, Project Engineers, Materials Engineers, and Foremen), to be assigned to the contract to be bid, with their complete qualification and experience data (*please see attached prescribed form required by the QC – BAC for Infrastructure and Consultancy*);
 - c. List of contractor’s major equipment units, which are owned, leased, and/or under purchase agreements, supported by proof of ownership or certification of availability of equipment from the equipment

lessor/vendor for the duration of the project, as the case may be (*please see attached prescribed form required by the QC – BAC for Infrastructure and Consultancy*); **and**

- (k) Original duly signed Omnibus Sworn Statement (OSS); **and** if applicable, Original Notarized Secretary's Certificate in case of a corporation, partnership, or cooperative; or Original Special Power of Attorney of all members of the joint venture giving full power and authority to its officer to sign the OSS and do acts to represent the Bidder.

Additional Technical Requirements:

- Certificate of Site Inspection or Affidavit of Site Inspection as part of Omnibus Sworn Statement
- Affidavit of Undertaking for Key Personnel and Equipment (*please see attached prescribed form required by the QC – BAC for Infrastructure and Consultancy*)
- Equipment Utilization Schedule
- Manpower Schedule
- Construction Schedule and S-Curve
- PERT-CMP
- Construction Methods

Financial Documents

- (l) The prospective bidder's audited financial statements, showing, among others, the prospective bidder's total and current assets and liabilities, stamped "received" by the BIR or its duly accredited and authorized institutions, for the preceding calendar year which should not be earlier than two (2) years from the date of bid submission; **and**
- (m) The prospective bidder's computation of Net Financial Contracting Capacity (NFCC) (*please see attached prescribed form required by the QC – BAC for Infrastructure and Consultancy*).

Class "B" Documents

- (n) If applicable, duly signed joint venture agreement (JVA) in accordance with RA No. 4566 and its IRR in case the joint venture is already in existence; **or** duly notarized statements from all the potential joint venture partners stating that they will enter into and abide by the provisions of the JVA in the instance that the bid is successful.

II. FINANCIAL COMPONENT ENVELOPE

- (o) Original of duly signed and accomplished Financial Bid Form; **and**

Other documentary requirements under RA No. 9184

- (p) Original of duly signed Bid Prices in the Bill of Quantities; **and**
- (q) Duly accomplished Detailed Estimates Form, including a summary sheet indicating the unit prices of construction materials, labor rates, and equipment rentals used in coming up with the Bid; **and**
- (r) Cash Flow by Quarter.

Bid Form for the Procurement of Infrastructure Projects
[shall be submitted with the Bid]

BID FORM

Date : _____
Project Identification No. : _____

To: *[name and address of Procuring Entity]*

Having examined the Philippine Bidding Documents (PBDs) including the Supplemental or Bid Bulletin Numbers *[insert numbers]*, the receipt of which is hereby duly acknowledged, we, the undersigned, declare that:

- a. We have no reservation to the PBDs, including the Supplemental or Bid Bulletins, for the Procurement Project: *[insert name of contract]*;
- b. We offer to execute the Works for this Contract in accordance with the PBDs;
- c. The total price of our Bid in words and figures, excluding any discounts offered below is: *[insert information]*;
- d. The discounts offered and the methodology for their application are: *[insert information]*;
- e. The total bid price includes the cost of all taxes, such as, but not limited to: *[specify the applicable taxes, e.g. (i) value added tax (VAT), (ii) income tax, (iii) local taxes, and (iv) other fiscal levies and duties]*, which are itemized herein and reflected in the detailed estimates,
- f. Our Bid shall be valid within the a period stated in the PBDs, and it shall remain binding upon us at any time before the expiration of that period;
- g. If our Bid is accepted, we commit to obtain a Performance Security in the amount of *[insert percentage amount]* percent of the Contract Price for the due performance of the Contract, or a Performance Securing Declaration in lieu of the the allowable forms of Performance Security, subject to the terms and conditions of issued GPPB guidelines¹ for this purpose;
- h. We are not participating, as Bidders, in more than one Bid in this bidding process, other than alternative offers in accordance with the Bidding Documents;
- i. We understand that this Bid, together with your written acceptance thereof included in your notification of award, shall constitute a binding contract between us, until a formal Contract is prepared and executed; and
- j. We understand that you are not bound to accept the Lowest Calculated Bid or any other Bid that you may receive.

¹ currently based on GPPB Resolution No. 09-2020

- k. We likewise certify/confirm that the undersigned, is the duly authorized representative of the bidder, and granted full power and authority to do, execute and perform any and all acts necessary to participate, submit the bid, and to sign and execute the ensuing contract for the [Name of Project] of the [Name of the Procuring Entity].
- l. We acknowledge that failure to sign each and every page of this Bid Form, including the Bill of Quantities, shall be a ground for the rejection of our bid.

Name: _____

Legal Capacity: _____

Signature: _____

Duly authorized to sign the Bid for and behalf of: _____

Date: _____

Bid Securing Declaration Form

[shall be submitted with the Bid if bidder opts to provide this form of bid security]

REPUBLIC OF THE PHILIPPINES)
CITY OF _____) S.S.

BID SECURING DECLARATION **Project Identification No.: *[Insert number]***

To: *[Insert name and address of the Procuring Entity]*

I/We, the undersigned, declare that:

1. I/We understand that, according to your conditions, bids must be supported by a Bid Security, which may be in the form of a Bid Securing Declaration.
2. I/We accept that: (a) I/we will be automatically disqualified from bidding for any procurement contract with any procuring entity for a period of two (2) years upon receipt of your Blacklisting Order; and, (b) I/we will pay the applicable fine provided under Section 6 of the Guidelines on the Use of Bid Securing Declaration, within fifteen (15) days from receipt of the written demand by the procuring entity for the commission of acts resulting to the enforcement of the bid securing declaration under Sections 23.1(b), 34.2, 40.1 and 69.1, except 69.1(f), of the IRR of RA No. 9184; without prejudice to other legal action the government may undertake.
3. I/We understand that this Bid Securing Declaration shall cease to be valid on the following circumstances:
 - a. Upon expiration of the bid validity period, or any extension thereof pursuant to your request;
 - b. I am/we are declared ineligible or post-disqualified upon receipt of your notice to such effect, and (i) I/we failed to timely file a request for reconsideration or (ii) I/we filed a waiver to avail of said right; and
 - c. I am/we are declared the bidder with the Lowest Calculated Responsive Bid, and I/we have furnished the performance security and signed the Contract.

IN WITNESS WHEREOF, I/We have hereunto set my/our hand/s this ____ day of *[month]* *[year]* at *[place of execution]*.

*[Insert NAME OF BIDDER OR ITS AUTHORIZED
REPRESENTATIVE]
[Insert signatory's legal capacity]
Affiant*

[Jurat]

[Format shall be based on the latest Rules on Notarial Practice]

Omnibus Sworn Statement (Revised)

[shall be submitted with the Bid]

REPUBLIC OF THE PHILIPPINES)
CITY/MUNICIPALITY OF _____) S.S.

AFFIDAVIT

I, [Name of Affiant], of legal age, [Civil Status], [Nationality], and residing at [Address of Affiant], after having been duly sworn in accordance with law, do hereby depose and state that:

1. *[Select one, delete the other:]*

[If a sole proprietorship:] I am the sole proprietor or authorized representative of [Name of Bidder] with office address at [address of Bidder];

[If a partnership, corporation, cooperative, or joint venture:] I am the duly authorized and designated representative of [Name of Bidder] with office address at [address of Bidder];

2. *[Select one, delete the other:]*

[If a sole proprietorship:] As the owner and sole proprietor, or authorized representative of [Name of Bidder], I have full power and authority to do, execute and perform any and all acts necessary to participate, submit the bid, and to sign and execute the ensuing contract for [Name of the Project] of the [Name of the Procuring Entity], as shown in the attached duly notarized Special Power of Attorney;

[If a partnership, corporation, cooperative, or joint venture:] I am granted full power and authority to do, execute and perform any and all acts necessary to participate, submit the bid, and to sign and execute the ensuing contract for [Name of the Project] of the [Name of the Procuring Entity], as shown in the attached [state title of attached document showing proof of authorization (e.g., duly notarized Secretary's Certificate, Board/Partnership Resolution, or Special Power of Attorney, whichever is applicable)];

3. [Name of Bidder] is not "blacklisted" or barred from bidding by the Government of the Philippines or any of its agencies, offices, corporations, or Local Government Units, foreign government/foreign or international financing institution whose blacklisting rules have been recognized by the Government Procurement Policy Board, **by itself or by relation, membership, association, affiliation, or controlling interest with another blacklisted person or entity as defined and provided for in the Uniform Guidelines on Blacklisting;**

4. Each of the documents submitted in satisfaction of the bidding requirements is an authentic copy of the original, complete, and all statements and information provided therein are true and correct;

5. [Name of Bidder] is authorizing the Head of the Procuring Entity or its duly authorized representative(s) to verify all the documents submitted;

6. *[Select one, delete the rest:]*

[If a sole proprietorship:] The owner or sole proprietor is not related to the Head of the Procuring Entity, members of the Bids and Awards Committee (BAC), the Technical Working Group, and the BAC Secretariat, the head of the Project Management Office or the end-user unit, and the project consultants by consanguinity or affinity up to the third civil degree;

[If a partnership or cooperative:] None of the officers and members of [Name of Bidder] is related to the Head of the Procuring Entity, members of the Bids and Awards Committee (BAC), the Technical Working Group, and the BAC Secretariat, the head of the Project

Management Office or the end-user unit, and the project consultants by consanguinity or affinity up to the third civil degree;

[If a corporation or joint venture:] None of the officers, directors, and controlling stockholders of *[Name of Bidder]* is related to the Head of the Procuring Entity, members of the Bids and Awards Committee (BAC), the Technical Working Group, and the BAC Secretariat, the head of the Project Management Office or the end-user unit, and the project consultants by consanguinity or affinity up to the third civil degree;

7. *[Name of Bidder]* complies with existing labor laws and standards; and
8. *[Name of Bidder]* is aware of and has undertaken the responsibilities as a Bidder in compliance with the Philippine Bidding Documents, which includes:
 - a. Carefully examining all of the Bidding Documents;
 - b. Acknowledging all conditions, local or otherwise, affecting the implementation of the Contract;
 - c. Making an estimate of the facilities available and needed for the contract to be bid, if any; and
 - d. Inquiring or securing Supplemental/Bid Bulletin(s) issued for the *[Name of the Project]*.
9. *[Name of Bidder]* did not give or pay directly or indirectly, any commission, amount, fee, or any form of consideration, pecuniary or otherwise, to any person or official, personnel or representative of the government in relation to any procurement project or activity.
10. **In case advance payment was made or given, failure to perform or deliver any of the obligations and undertakings in the contract shall be sufficient grounds to constitute criminal liability for Swindling (Estafa) or the commission of fraud with unfaithfulness or abuse of confidence through misappropriating or converting any payment received by a person or entity under an obligation involving the duty to deliver certain goods or services, to the prejudice of the public and the government of the Philippines pursuant to Article 315 of Act No. 3815 s. 1930, as amended, or the Revised Penal Code.**
11. We pledge that the project will be completed in accordance and congruency with the approved plans and programs.

IN WITNESS WHEREOF, I have hereunto set my hand this ___ day of _____ 20_ at _____, Philippines.

[Insert NAME OF BIDDER OR ITS AUTHORIZED REPRESENTATIVE]

[Insert signatory's legal capacity]

Affiant

[Jurat]

[Format shall be based on the latest Rules on Notarial Practice]

**Contract Agreement Form for the
Procurement of Infrastructure Projects (Revised)**

*[not required to be submitted with the Bid, but it shall be submitted within ten (10) days after
receiving the Notice of Award]*

CONTRACT AGREEMENT

THIS AGREEMENT, made this *[insert date]* day of *[insert month]*, *[insert year]* between *[name and address of PROCURING ENTITY]* (hereinafter called the "Entity") and *[name and address of Contractor]* (hereinafter called the "Contractor").

WHEREAS, the Entity is desirous that the Contractor execute *[name and identification number of contract]* (hereinafter called "the Works") and the Entity has accepted the Bid for *[contract price in words and figures in specified currency]* by the Contractor for the execution and completion of such Works and the remedying of any defects therein.

NOW THIS AGREEMENT WITNESSETH AS FOLLOWS:

1. In this Agreement, words and expressions shall have the same meanings as are respectively assigned to them in the Conditions of Contract hereinafter referred to.
2. The following documents as required by the 2016 revised Implementing Rules and Regulations of Republic Act No. 9184 shall be deemed to form and be read and construed as part of this Agreement, viz.:
 - a. Philippine Bidding Documents (PBDs);
 - i. Drawings/Plans;
 - ii. Specifications;
 - iii. Bill of Quantities;
 - iv. General and Special Conditions of Contract;
 - v. Supplemental or Bid Bulletins, if any;
 - b. Winning bidder's bid, including the Eligibility requirements, Technical and Financial Proposals, and all other documents or statements submitted;

Bid form, including all the documents/statements contained in the Bidder's bidding envelopes, as annexes, and all other documents submitted (e.g., Bidder's response to request for clarifications on the bid), including corrections to the bid, if any, resulting from the Procuring Entity's bid evaluation;
 - c. Performance Security;
 - d. Notice of Award of Contract and the Bidder's conforme thereto; and
 - e. Other contract documents that may be required by existing laws and/or the Procuring Entity concerned in the PBDs. **Winning bidder agrees that additional contract documents or information prescribed by the GPPB that are subsequently required for submission after the contract execution, such as the Notice to Proceed, Variation Orders, and Warranty Security, shall likewise form part of the Contract.**
3. In consideration for the sum of *[total contract price in words and figures]* or such other sums as may be ascertained, *[Named of the bidder]* agrees to *[state the object of the contract]* in accordance with his/her/its Bid.

4. The *[Name of the procuring entity]* agrees to pay the above-mentioned sum in accordance with the terms of the Bidding.

IN WITNESS whereof the parties thereto have caused this Agreement to be executed the day and year first before written.

[Insert Name and Signature] [Insert Name and Signature]

[Insert Signatory's Legal Capacity] [Insert Signatory's Legal Capacity]

for: for:

[Insert Procuring Entity] [Insert Name of Supplier]

Acknowledgment

[Format shall be based on the latest Rules on Notarial Practice]

Performance Securing Declaration (Revised)

[if used as an alternative performance security but it is not required to be submitted with the Bid, as it shall be submitted within ten (10) days after receiving the Notice of Award]

REPUBLIC OF THE PHILIPPINES)
CITY OF _____) S.S.

PERFORMANCE SECURING DECLARATION

Invitation to Bid: [Insert Reference Number indicated in the Bidding Documents] To:
[Insert name and address of the Procuring Entity]

I/We, the undersigned, declare that:

1. I/We understand that, according to your conditions, to guarantee the faithful performance by the supplier/distributor/manufacturer/contractor/consultant of its obligations under the Contract, I/we shall submit a Performance Securing Declaration within a maximum period of ten (10) calendar days from the receipt of the Notice of Award prior to the signing of the Contract.
2. I/We accept that: I/we will be automatically disqualified from bidding for any procurement contract with any procuring entity for a period of one (1) year for the first offense, or two (2) years **for the second offense**, upon receipt of your Blacklisting Order if I/We have violated my/our obligations under the Contract;
3. I/We understand that this Performance Securing Declaration shall cease to be valid upon:
 - a. issuance by the Procuring Entity of the Certificate of Final Acceptance, subject to the following conditions:
 - i. Procuring Entity has no claims filed against the contract awardee;
 - ii. It has no claims for labor and materials filed against the contractor; and
 - iii. Other terms of the contract; or
 - b. replacement by the winning bidder of the submitted PSD with a performance security in any of the prescribed forms under Section 39.2 of the 2016 revised IRR of RA No. 9184 as required by the end-user.

IN WITNESS WHEREOF, I/We have hereunto set my/our hand/s this ____ day of [month] [year] at [place of execution].

*[Insert NAME OF BIDDER OR ITS
AUTHORIZED REPRESENTATIVE]
[Insert signatory's legal capacity]
Affiant*

[Jurat]

[Format shall be based on the latest Rules on Notarial Practice]

LIST OF ALL ON-GOING GOVERNMENT AND PRIVATE CONTRACTS

NAME OF CONTRACTOR: _____

PROJECT TITLE (Name of the Contract) & EXACT PROJECT LOCATION	DATE OF CONTRACT	CONTRACT DURATION	PROJECT OWNER & POSTAL ADDRESS	NATURE OF WORK	CONTRACTOR'S ROLE (SOLE CONTRACTOR, SUBCONTRACTOR, PARTNER IN A JV) and PERCENTAGE OF PARTICIPATION	TOTAL CONTRACT VALUE AT AWARD	DATE OF COMPLETION or ESTIMATED COMPLETION TIME	TOTAL CONTRACT VALUE AT COMPLETION IF APPLICABLE	PERCENTAGE		VALUE OF OUTSTANDING WORKS (IN PHP)
									ACTUAL ACCOMPLISHMENT	PLANNED ACCOMPLISHMENT	
									TOTAL AMOUNT (Php) OF OUTSTANDING WORKS		

PHOTOCOPY ADDITIONAL FORMS, IF NECESSARY

Page _____ of _____

LIST OF ALL AWARDED BUT NOT YET STARTED GOVERNMENT AND PRIVATE CONTRACTS OF THE BIDDER

NAME OF CONTRACTOR: _____

PROJECT TITLE: _____

PROJECT TITLE & EXACT LOCATION	MAJOR SCOPE OF WORKS & DATE STARTED	NAME AND ADDRESS OF PROJECT OWNER	CONTRACT PRICE (PHP) AS AWARDED	DATE OF SCHEDULED COMPLETION	ROLE OF BIDDER IN THE <u>CONTRACT</u> <u>SOLE CONTRACTOR / SUB-CONTRACTOR/PARTNER IN A</u>
	TOTAL AMOUNT OF CONTRACT (Php)				

SINGLE LARGEST COMPLETED CONTRACT SIMILAR TO THE CONTRACT TO BE BID

NAME OF CONTRACTOR: _____

PROJECT TITLE: _____

PROJECT TITLE (Name of the Contract) & EXACT PROJECT LOCATION	DATE OF CONTRACT	CONTRACT DURATION	PROJECT OWNER & POSTAL ADDRESS	NATURE OF WORK	CONTRACTOR'S ROLE (SOLE CONTRACTOR, SUBCONTRACTOR, PARTNER IN A JV) and PERCENTAGE OF PARTICIPATION	TOTAL CONTRACT VALUE AT AWARD	DATE OF COMPLETION or ESTIMATED COMPLETION TIME	TOTAL CONTRACT VALUE AT COMPLETION IF APPLICABLE

PHOTOCOPY ADDITIONAL FORMS, IF NECESSARY

Page _____ of _____

LIST OF MAJOR EQUIPMENT TO BE USED FOR THE PROJECT

NAME OF CONTRACTOR: _____

PROJECT TITLE: _____

TYPE	DESCRIPTION / CAPACITY	SERIAL NO.	YEAR ACQUIRED	PRESENT LOCATION (SPECIFIC ADDRESS)	STATUS OF AVAILABILITY (OWNED/LEASED)

A. LIST OF KEY CONSTRUCTION PERSONNEL TO BE ASSIGNED TO THE PROJECT

NAME OF CONTRACTOR: _____

PROJECT TITLE: _____

NAME	POSITION	AGE	EDUCATIONAL ATTAINMENT	TYPE OF CONSTRUCTION EXPERIENCE	NO.OF YEARS WITH THE CONTRACTOR	PROFESSION	PRC NO.

COMPUTATION OF NET FINANCIAL CONTRACTING CAPACITY (NFCC)

NAME OF BIDDER: _____

CURRENT ASSETS*		PHP	_____
(LESS) CURRENT LIABILITIES*	(LESS)	PHP	_____
NETWORTH		PHP	_____
NETWORTH x 15	x 15	PHP	_____
(LESS) VALUE OF ALL OUTSTANDING ON-GOING CONTRACTS**	(LESS)	PHP	_____
(LESS) VALUE OF ALL AWARDED BUT NOT YET STARTED CONTRACTS AS OF DATE**	(LESS)	PHP	_____
NET FINANCIAL CONTRACTING CAPACITY		PHP	_____

NOTES: * CURRENT ASSETS AND LIABILITIES BASED ON AUDITED FINANCIAL STATEMENT FOR THE PRECEDING CALENDAR YEAR SUBMITTED TO B.I.R.

** BASED ON LIST OF ON-GOING AND AWARDED BUT NOT YET STARTED CONTRACTS SUBMITTED

REPUBLIC OF THE PHILIPPINES)

_____) S.S.

AFFIDAVIT OF UNDERTAKING

I, _____ of legal age, Filipino, _____ [OFFICER OR REPRESENTATIVE]

with office address at _____ after having been duly sworn to in accordance with law, hereby voluntary depose and state:

That I am duly authorized representative of the [Name of Bidder] to execute this undertaking as evidenced by Secretary's Certificate and Board Resolution.

That [Name of Bidder] bidding for the (Name of Project)

That relative to the aforementioned Project, the [Name of Bidder] hereby undertake that the equipment to be use and the key personnel to be assign shall exclusively be used and will only perform to the said project until its completion.

That I am executing this affidavit to attest to the truth of the foregoing and in compliance with the submission of the technical requirements for the public bidding of the said project.

IN WITNESS HEREOF, I have hereunto signed my name below this _____ day of _____ at _____.

AFFIANT FURTHER SAYETH NAUGHT.

Affiant

SUBSCRIBED AND SWORN TO BEFORE ME this _____ day of _____
in _____

affiant exhibiting to me his/her _____ issued at _____
on _____

Doc. No. ;
Page No. ;
Book No. ;
Series of 2020

Notary Public

